

Site Registration

Date

February 2026

Complete the following fields prior to calculating the Security Deposit.

Mine Name:	Berrima Colliery		
Lease(s):	CCL748, MPL603, MPL604		
Title Holder:	Boral Limited		
Term of RCE:	Boral Cement		
Current Security:	\$10,152,000	Date of last Security Deposit review	1/01/2024
Mine Contact:	Greg Johnson		
List key changes since previous submission:	Completion of Loch Catherine Mine Entries. Remvoal and rehabilitation of Vibrating Wire Piezometers. Added an additional corrugated iron water tank. Reduced costs of installing underground bulkheads.		



Underground Summary Rehabilitation Cost Estimation

Note: Sections of this page are automatically filled in from the registration page

Mine Name:	Berrima Colliery		
Lease(s):	CCL748, MPL603, MPL604		
Mine Owner:	Boral Limited		
Term of RCE:	Boral Cement		
Current Security:	\$10,152,000	Date of Last Security Deposit Review:	1/01/2024
Mine Contact:	Greg Johnson		

Domain		Security Deposit
Domain 1: Infrastructure		5,495,569.50
Domain 2: Tailings & Rejects		
Domain 3: Overburden & Waste		
Domain 4: Subsidence & Management		192,160.00
Subtotal (Domains and Sundry Items)		\$5,687,729.50
Contingency	10%	\$568,772.95
Post Closure Environmental Monitoring	10%	\$568,772.95
Project Management and Surveying	10%	\$568,772.95
Total Security Deposit for the Mining Project (excl. of GST)		\$7,394,048.35

Note: GST is not included in the above calculation or as part of rehabilitation security deposits required by the Department

- Alterations have been made to unit prices within this spreadsheet. (Attach a separate sheet providing details of changes).
- The proposed rehabilitation design is generally consistent with the development consent for the project.

This mine security calculation has been estimated using the best available information at the time.
It is a true and accurate reflection of the total rehabilitation liability held by this mine.

Greg Johnson

Company Representative's Name

25/02/2026

Date

Senior Environmental Business Partner

Company Representative's Role / Responsibility

GAJohnson

Signature

Underground Operations

Domain 1a: Infrastructure

Total Cost for Infrastructure Domain

\$5,495,570

Additional Assumptions: Record any relevant assumptions to this domain below:

		Key Rehabilitation Area Data for Domain	Enter data below manually
		Total Landform Establishment:	
		Total Growth Media Development:	
		Total Ecosystem Establishment:	

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Termination of Services and Demolition Works	Disconnect and terminate all services (Water, electricity, gas etc at point of attachment to site)	Y	1	allow	\$35,000		\$35,000		For disconnection of all services, at building boundaries, physical cut at the point of attachment or distribution location. If infrastructure is not consolidated (i.e., administration, camp and workshops are in separate places), consider multiple disconnection fees.
	Removal of low/medium voltage powerlines including disconnection, rolling up the wires and removing the poles - does not include the removal of substations	Y	6.2	km	\$15,000		\$93,000		Applies to power lines on stobie, concrete or similar poles.
	Remove small rail, road, water course overpass - manage potential interruptions and demolish and remove bridge supports/pylons/bridge structure etc. and dispose of waste material on-site/locally	Y	1	Item	\$350,000		\$350,000		Smaller structures - minimal civil works to demolish (constructed for the purposes of mining related works - does not include transport to regional disposal facility or equivalent).
	Demolish and/or remove substations (assumes they are in a closed building). Dispose of waste material on-site/locally	Y	12	m2	\$100.00		\$1,200		Simple structure to demolish mechanically (no labour required), assumes single story building with no asbestos and segregation of contents for scrap as applicable.
	Demolish and remove switchyard. Dispose of waste material on-site/locally	Y	25	m2	\$75.00		\$1,875		Includes demolition and removal of all switchgear and transformers etc. and segregation of contents for scrap as applicable.
	Demolish and remove demountable structures on concrete stumps. Assumes not being re-used	Y	68	m2	\$40.00		\$2,720		Crib huts, temporary offices and other 'non permanent' structures. Does not include transport to regional disposal facility or equivalent.
	Demolish and remove small buildings/tanks (admin buildings, single story accommodation etc) and disposal on-site/locally	Y	1910	m2	\$61.00		\$116,510		Simple structure to demolish, assumes no greater than 2 stories high. Does not include transport to regional disposal facility or equivalent.
	Demolish and remove light industrial buildings and disposal on-site/locally	Y	375	m2/floor	\$90.00		\$33,750		Needs to be calculated per floor/level (Assume 1 floor/level = 3.4 m) - does not include transport to regional disposal facility or equivalent. Assumes asbestos free and mechanically demolished.
	Demolish and remove industrial buildings (workshops tyre change and servicing area etc not CHPP/process plant) and disposal on-site/locally	Y	86	m2/floor	\$130.00		\$11,180		Needs to be calculated per floor/level (Assume 1 floor/level = 3.4 m). Does not include transport to regional disposal facility or equivalent.
	Demolition and removal of vent raise fans, electrical substation and winch and disposal on-site/locally	Y	1	allow	\$25,000		\$25,000		Does not include filling and capping the shaft. Does not include transport to regional disposal facility or equivalent.
	Removal of UG tank 5000 L - 15000 L - including pipes, bunds etc. and disposal on-site/locally	Y	1	allow	\$30,000.00		\$30,000		Assume tank is clean (contents removed), does not include transport to regional disposal facility or equivalent.
	Remove small underground pipe and disposal on-site/locally	Y	400	m	\$25.00		\$10,000		For example: 300 mm pipes - 0.5 m deep, does not include transport to regional disposal facility or equivalent.
	Remove above ground pipe (supported) and disposal on-site/locally	Y	900	m	\$12.00		\$10,800		~300 mm pipes and assumes pipes are in close proximity to infrastructure areas. Does not include transport to regional disposal facility or equivalent.
	Remove surface pipelines (unsupported) and disposal on-site/locally	Y	350	m	\$15		\$5,250		~300 mm pipes and assumes pipes are used for water transfer between pits (or similar) and remotely located. Does not include transport to regional disposal facility or equivalent.
	Remove bitumen (car park and access roads) and dispose on-site/locally	Y	5800	m2	\$10.00		\$58,000		Scalp bitumen and stabilised material. Generally haulage rates will be \$0.60 - \$1.20 / km, depending on truck fleet, loaders etc. For off-site disposal use alternate rate option and add \$0.90 / km for transport.
	Remove concrete pads & footings (<300 mm thickness) and disposal on-site/locally	Y	1535	m2	\$36.00		\$55,260		Breaking up slab and disposal or for conversion to aggregate. Generally haulage rates will be \$0.60 - \$1.20 / km, depending on truck fleet, loaders etc. For off-site disposal use alternate rate option and add \$0.90 / km for transport.
	Remove concrete pads & footings (>300 mm thickness) and disposal on-site/locally	Y	35	m2	\$75.00		\$2,625		Breaking up slab and disposal or for conversion to aggregate. Generally haulage rates will be \$0.60 - \$1.20 / km, depending on truck fleet, loaders etc. For off-site disposal use alternate rate option and add \$0.90 / km for transport.
	Removal of small plastic tanks	Y	5	each	\$1,000.00		\$5,000		Remove small poly tanks used for water storage, etc.

	Demolish and remove galvanised/corrugated light weight tanks	Y	1	each	\$500.00		\$500		Demolish and remove small lightweight metal tanks. No costs included for managing liquids, etc.
	Removal of UG services (power within main gate areas, etc.)	Y	1	allow	\$50,000.00		\$50,000		Assume service disconnection at the mine boundary is at surface level. This cost covers all fees and charges
	Waste disposal to Council landfill (general waste) - haulage >10 km but <15 km	Y	50	tonne	\$7.00		\$350		Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
	Waste disposal to Council landfill (industrial demolition / concrete / scrap metal) - haulage >10 km but <15 km	Y	200	tonne	\$32.00		\$6,400		Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
	Waste disposal to Council landfill - fees (general waste)	Y	200	tonne	\$193.00		\$38,600		Fee for waste disposal of general waste to local Council landfill; transport rates separate. Please note that this is not applicable to operations with approval for building and demolition waste disposal on site.
Termination of Services and Demolition Works Subtotal							\$943,020		
Rail Infrastructure Subtotal							\$0		
Contaminated Materials	Develop a Remediation Action Plan on sites with small footprints based on outcomes of intrusive investigation including strategies to address contamination exceedances	Y	1	allow	\$35,000		\$35,000		Develop remediation plan for approval including designs and detailed costs. Costs may increase if detailed designs required for construction.
	Removal and disposal of contaminated water from tanks, bunded areas and sumps	Y	800	L	\$0.35		\$280		Cost for recent sump clean-up from resource activity - requires specialists to treat.
	Onsite remediation of hydrocarbon contaminated soils (>50 m3 but <100 m3) - manual land farming	Y	80	m3	\$89.00		\$7,120	> 50m3 but <100m3	Overall rate for bio-remediation in the order of \$75 - \$120 /m3 depending on volume, additives, treatment durations and contamination levels. \$45 /m3 for spreading contaminated soils on a prepared surface and stimulation of aerobic microbial activity within the soils through aeration and/or the addition of minerals, nutrients
Contaminated Materials Subtotal							\$42,400		
Vents, Shafts and Boreholes	Seal portals / drifts (width >3 m) – only entry seal / plug required with in front of access backfill with engineered fill for 5 m	Y	1	allow	\$126,000		\$126,000	Ventilation Fan	This cost is not applicable to coal operations which require backfilling to MDG6001 or similar due to gases. Costs include engineering and QA/QC. Costs assume engineered fill backfilled between 2 x 1 m plugs for sealing, + haul material to backfill per >5 km distance + concrete pump and secondary support.
	Seal portals / drifts (width >3 m) accessible to men and machinery requiring a bulkhead – grout backfill against a concrete bulkhead to be constructed	Y	1	allow	\$250,000		\$250,000	Main Drift Entry	Cost includes engineering the bulkhead and underground construction (access available) followed by grout backfill via workings and rehabilitation (reshape, bulk push and full rehabilitation). Assume tunnel length of 20 m. For every additional m add \$7,250 for grouting. If no bulkhead required, deduct \$60,000.
Vents, Shafts and Boreholes Subtotal							\$376,000		
Roads and Tracks	Unsealed roads / vehicle park-up areas – minor works including deep rip and trim	Y	0.5	ha	\$1,040.00		\$520		Assumes ~6 m road width - 16H Grader.
	Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip and seed (pasture grass)	Y	0.8	ha	\$3,700		\$2,960		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed

	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (pasture grass)	Y	2.5	ha	\$4,870		\$12,175	Access to Loch Catherine Site	D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed	
Roads and Tracks Subtotal							\$15,655			
Earthworks / Structural Works (Landform Establishment)	Minor reshaping and pushing	Y	2.5	ha	\$3,900		\$9,750	Just pit top now, Loch Catherine complete	D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation).	
	Trim, rock rake & deep rip (includes levelling / landscaping and rip in 1 direction)	Y	2.5	ha	\$1,130.00		\$2,825		Undertaken using D10 dozer and 16M grader.	
	Structural works, banks, waterways - contour banks, drainage channels and other soil conservation measures	Y	2.5	ha	\$1,600		\$4,000		Combination of dozer and excavator work plus grader for ~4 hours each per ha.	
	Construction of spine drains / drop structures and/or stabilising water course entry points - required for large catchments	Y	600	m2	\$27.00		\$16,200		Installation of on-site rock material (rip-rap) where managing water run-off from disturbed land and/or upon entry to water courses - prevents erosion of gully head (assumes competent material is locally available). If required to be sourced off site, assume an additional \$20/m2.	
Earthworks / Structural Works (Landform Establishment) Subtotal							\$32,775			
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment)	Source, cart and spread growth media - haul distance >1 km but <2 km	Y	6700	m3	\$4.32		\$28,944	> 1km but <= 2km	Undertaken with scraper and D10 dozer.	
	Planting tube stock (<15 cm)	Y	1340	allow	\$6.60		\$8,844		4 m centres.	
	Direct seeding / fertiliser (tree or native grass species)	Y	6.7	ha	\$4,135		\$27,705		Includes treating, weighing, mixing with fertiliser + spreading by tractor or helicopter (aerial seeding).	
	Hydromulch - bonded fibre matrix grade for steep areas to stabilise up to 12 months	Y	2500	m2	\$1.80		\$4,500		Assumes use on steep areas where stabilisation is required for up to 12 months. Application rate of ~3500kg/ha. This cost includes cover crop only, additional seeding required.	
	Single application of fertiliser (trees)	Y	6.7	ha	\$140.00		\$938		These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.	
	Spoil amelioration (adding lime / gypsum etc.)	Y	6.7	ha	\$1,000.00		\$6,700		Assumes 2.5 t / ha as an average application rate.	
	growth media amelioration with biosolids	Y		ha	\$1,015		\$0		Recent experience with agronomy projects.	
	Construct no-climb stock fence around rehabilitated areas	Y		m	\$22.00		\$0		Standard rate for no-climb stock fencing.	
	Construct standard stock fence around rehabilitated areas	Y		m	\$13.00		\$0		Standard rate for standard stock fencing.	
	Purchase and erect warning signs	Y	2	allow	\$250.00		\$500		Compliance with AS 1319-1994 - Safety signs for the occupational environment - installed every 25 m.	
	Supply from external sources virgin excavated natural material (VENM) for growth media.	Y		m3	\$80.80		\$0		D7 to spread material at \$205/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$70/m3 for imported fill material.	
	Supply from external sources a combination of virgin excavated natural material (VENM) and spoil from large excavation for filling voids and/or capping etc.	Y		m3	\$72.50		\$0		D10 push into void at \$270/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$60/m3 for imported fill material.	
	Clearing and grubbing of trees and vegetation	Y		ha	\$4,730.00		\$0		Clearing and grubbing of light vegetation growth e.g. regrowth	
	Topsoil stripping	Y		m3	\$4.86		\$0		Stripping or topsoil at an approximate depth of 0.2 m into stockpiles; load and haul to final rehabilitation location required or respreading where necessary.	
Growth media supplementation with manure	Y		ha	\$747.50		\$0		Addition of manure to improve soil quality.		
Utilise biotic soil media - organic topsoil alternative	Y		m2	\$2.50		\$0		Material that can be applied as an alternative to spreading topsoil prior to hydromulching.		
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment) Subtotal							\$78,131			
Water Management	Clean water dams to be retained after decommissioning – make safe and minor earthworks	Y	3	allow	\$2,500		\$7,500		Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) @ ~\$200 per hour and pasture grass.	
	Remove sediments from the floor of the dam to enable it to be converted into clean water structure (haul distance >1km but <2km)	Y	20	m3	\$4.45		\$89	> 1km but <= 2km	Undertaken with excavator, trucks, 16 M grader and D10 Dozer	
Water Management Subtotal							\$7,589			
Maintenance of Rehabilitated Areas Subtotal							\$0			
Additional Items	Other 1 <insert>	Y	1		#####		\$4,000,000	Underground bulkheads	This item includes <<to be added by the operator>>	
	Additional Items Subtotal							\$4,000,000		
Total Cost for Infrastructure Domain								\$5,495,570		

Underground Operations

Domain 2a: Tailings & Rejects

Total Cost for Tailings & Rejects Domain

\$0

Additional Assumptions: Record any relevant assumptions to this domain below:

Key Rehabilitation Area Data for Domain		Enter data below manually
Total Landform Establishment:		
Total Growth Media Development:		
Total Ecosystem Establishment:		

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Contaminated Materials	Undertake a preliminary site investigation (Phase 1). This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple studies may be required.	Y		Cluster	\$15,000		\$0		The preliminary investigation would include at minimum a desktop assessment of the area and site history, incidents, etc. as per the National Environmental Protection (NEPM) Phase 1 assessment (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. A cluster may include: - Mine infrastructure (i.e., fuel / chemical store, workshop, vehicle wash-down, sewage treatment etc.) - Processing plants (i.e., ore and product storage, mine waste storage and disposal, rail load-out etc.) - Remote pit-top facilities (i.e., vehicle re-fuel, sewage treatment, secondary workshop, chemical storage etc.)
	Undertake an intrusive site investigation on sites with small footprints to investigate e.g. ≤15 ha. This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple intrusive investigations should be included.	Y		Cluster	\$44,000		\$0		The intrusive investigation would include at minimum a site walkover and field sampling as per the National Environmental Protection (NEPM) Phase 2 intrusive investigation (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. Note: An intrusive investigation is not required for all contaminated areas and should be applied considering the rehabilitation program, site history, location, etc. A cluster area where it is highly anticipated that contamination has occurred (i.e., underground tanks / pipes that are known to have leaked, chemical stores with earthen bunds, around ineffective oil/water separators etc.) and further field work is required involving intrusive investigation. Assumes site is easily accessible and a small area e.g. ~10-15 ha requires investigation and testing (test pits, boreholes, etc.) based on Sampling and Analysis Quality Plan. Includes SAQP, fieldwork, sampling and analysis.
	Undertake an intrusive site investigation on sites with large footprints to investigate e.g. >15 ha. This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple intrusive investigations should be included.	Y		Cluster	\$106,000		\$0		The intrusive investigation would include at minimum a site walkover and field sampling as per the National Environmental Protection (NEPM) Phase 2 intrusive investigation (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. Note: An intrusive investigation is not required for all contaminated areas and should be applied considering the rehabilitation program, site history, location, etc. A cluster area where it is highly anticipated that contamination has occurred (i.e., underground tanks / pipes that are known to have leaked, chemical stores with earthen bunds, around ineffective oil/water separators etc.) and further field work is required involving intrusive investigation. Assume site has a history of contamination and/or a large area >15 ha requires investigation and testing (test pits, boreholes, etc.) based on Sampling and Analysis Quality Plan. Includes SAQP, fieldwork, sampling and analysis.
	Develop a Remediation Action Plan on sites with small footprints based on outcomes of intrusive investigation including strategies to address contamination exceedances	Y		allow	\$35,000		\$0		Develop remediation plan for approval including designs and detailed costs. Costs may increase if detailed designs required for construction.

	Develop a Remediation Action Plan on sites with large footprints based on outcomes of intrusive investigation including strategies to address contamination exceedances	Y		allow	Use alternate rate cell		\$0		Assumes complex site; detailed design drawings required for cover.
	Removal and disposal of contaminated water from tanks, bunded areas and sumps	Y		L	\$0.35		\$0		Cost for recent sump clean-up from resource activity - requires specialists to treat.
	Remove material (carbonaceous / metalliferous spillage or otherwise) from footprint of the process facility (teach pads) / stockpile area (ROM product) / roads and dump in a void on-site (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here	This item includes scraping and removal of the volume of carbonaceous material using dozer, grader etc. to make safe an area and enable the establishment of rehabilitation.
	Load, cart and dispose of Hazardous classified contaminated material off site to a licensed landfill. Assumes cartage to a licensed landfill.	Y		m3	\$800.00		\$0		Includes load, haul and dump fees to a licensed facility.
	Load, cart and disposal of Restricted classified contaminated material off site to a licensed landfill. Add \$50/m3 for cartage from regional areas	Y		m4	\$660.00		\$0		Includes load, haul and dump fees to a licensed facility.
	Load, cart and disposal of Low Level contaminated material off site to a licensed landfill. Add \$50/m3 for cartage to regional landfill	Y		m3	\$220.00		\$0		Includes load, haul and dump fees to a licensed facility.
	Onsite remediation of hydrocarbon contaminated soils manual land farming (Select Volume from List)	Y		m3	Select from List			Select Volume Here	Spreading of contaminated soils on a prepared surface and stimulation of aerobic microbial activity within the soils through aeration and/or the addition of minerals, nutrients and moisture to promote the aerobic degradation of organic chemicals - time frame of up to 24 months.
	Mobilisation of cement stabilisation plant and equipment for hydrocarbon (i.e., PAH, long chain hydrocarbons, etc.) contaminated soil treatment	Y		Item	\$150,000		\$0		Required if treatment of hydrocarbon contamination is required to be fast tracked.
	On-site remediation of hydrocarbon contaminated soils - using a mobile treatment unit	Y		m3	\$165.00		\$0		Additional cost as the treatment process is fast tracked.
	Remove and dispose of asbestos (<750 m2)	Y		m2	\$50.00		\$0		Where an assessment/estimation has been made to confirm the volume of asbestos to be removed.
	Remove and dispose of asbestos (>750 m2)	Y		m2	\$40.00		\$0		Where an assessment/estimation has been made to confirm the volume of asbestos to be removed.
	Waste disposal to Council landfill - fees (asbestos)	Y		tonne	\$290		\$0		Landfill fees to regional landfill.
Contaminated Materials Subtotal							\$0		
Roads and Tracks	Unsealed roads / vehicle park-up areas – minor works including deep rip and trim	Y		ha	\$1,040.00		\$0		Assumes ~6 m road width - 16H Grader.
	Unsealed roads / access tracks / vehicle park-up areas with windrows and/or small earthen bunds – minor earthworks and deep rip and trim	Y		ha	\$1,500		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - no seed
	Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip and seed (pasture grass)	Y		ha	\$3,700		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$4,485		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (pasture grass)	Y		ha	\$4,870		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$7,025		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Remove stabilised material (blue metal, aggregate etc.) from roadways and disposal on-site/locally (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here	This item includes the scraping and removal of the volume of stabilised material from the road, laydown or other surface using an excavator, dozer and grader to enable the establishment of rehabilitation.
Roads and Tracks Subtotal							\$0		
Earthworks / Structural Works (Landform Establishment)	Major bulk pushing to achieve grades nominated in the approval/permit – Select Push Length	Y		m3	Select from List			Select Push Length Here	Major bulk pushing to achieve grades nominated in the approval/permit
	Minor reshaping and pushing	Y		ha	\$3,900		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation).
	Fill dams, voids etc. - Source local material, cart and spread to cap or backfill, cap thickness determined by approval / permit (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here	This item includes the volume of material requiring backfill using an excavator and scraper to fill the void and enable the establishment of rehabilitation.
	Trim, rock rake & deep rip (includes levelling / landscaping and rip in 1 direction)	Y		ha	\$1,130.00		\$0		Undertaken using D10 dozer and 16M grader.
	Structural works, banks, waterways - contour banks, drainage channels and other soil conservation measures	Y		ha	\$1,600		\$0		Combination of dozer and excavator work plus grader for ~4 hours each per ha.
	Construction of spine drains / drop structures and/or stabilising water course entry points - required for large catchments	Y		m2	\$27.00		\$0		Installation of on-site rock material (rip-rap) where managing water run-off from disturbed land and/or upon entry to water courses - prevents erosion of gully head (assumes competent material is locally available). If required to be sourced off site, assume an additional \$20/m2.

Earthworks / Structural Works (Landform Establishment) Subtotal					\$0		
Mine Waste	Ideal Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with little chemical reactivity (no to low risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and good physical properties (not significantly hydrophilic, shear strength does not limit equipment choice, no artificial strengthening required)	Y		ha	\$82,000	\$0	This includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume material with the appropriate chemical and physical properties. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness of approximately 0.5 m to 1 m and 0.15 m - 0.2 m growth media (assume at least 1 m thick cover required for carbonaceous material covers). Water quality from runoff, seepage etc. meets site-specific environment water quality values. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in additional to any long haulage volume in 8.05.
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell	\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell	\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Efficient Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with moderate chemical reactivity (low to medium risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and moderate physical properties (not significantly hydrophilic, shear strength limits equipment choice somewhat, no artificial strengthening required)	Y		ha	\$146,500	\$0	This item includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume of material to cap / cover facilities where the tailings or rejects base is at a strength that enables economically efficient construction methods with small plant. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness ranging from >1 m to 2 m thickness constructed in 1 m layers + growth media up to 0.2 m depth. This may require additional materials (such as capillary breaks, geofabric, etc.) - use alternate rate cells below, specific material types (e.g. acid neutralising / consuming materials, competent rock etc.), and associated activities (i.e., load / haul / place / crush / screen / borrow etc.). Costs for haulage of specialised/additional materials must be added separately if required. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell	\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell	\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).

	Adverse Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with moderate chemical reactivity (medium to high risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or moderate to high propensity for spontaneous combustion) and moderate physical properties (not significantly hydrophilic, shear strength limits equipment choice somewhat, no artificial strengthening required)	Y	ha	\$313,000		\$0	This item includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume of material to cap / cover facilities of high geochemical risk, and / or low shear strength that prohibits economically efficient construction methods. This rate assumes suitable capping material/s are available on site within 10 km, and an average cap thickness of approximately >2 m + growth media up to 0.2 m depth. This may require additional materials (i.e. capillary breaks, geofabric, etc.), specific material types (e.g. acid neutralising / consuming materials, competent rock etc.), and associated activities (i.e. load / haul / place / crush / screen / borrow etc.). Costs for haulage of specialised materials must be added separately if required. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in addition to any long haulage volume in 8.05.
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y	allow	Use alternate rate cell		\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y	allow	Use alternate rate cell		\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Difficult Tailings Capping- reshaping, capping / sealing of weak or soft surfaced tailings facility with poor physical properties (significantly hydrophilic, low shear strength limits equipment choice greatly, artificial strengthening required) OR visible adverse impacts on legacy sites from chemical reactivity over lengthy exposure prior to rehabilitation	Y	ha	\$843,000		\$0	This option is typically driven by time constraints and/or when tailings properties significantly restrict adequate desiccation, resulting in a tailings shear strength that is very weak excluding access by conventional small plant. Small equipment used for rehabilitation. This excludes any additional material required to form the final landform profile in addition to this cap. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in addition to any long haulage volume in 8.05.
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y	allow	Use alternate rate cell		\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y	allow	Use alternate rate cell		\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Long haulage soil / weathered rock / sediment e.g. capping/covers, removal of contamination, etc.	Y	m3	Select from List			Select Haul Distance Here
Mine Waste Subtotal						\$0	
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment)	Source, cart and spread growth media (Select Haul Distance from List)	Y	m3	Select from List			Select Haul Distance Here
	Direct seeding / fertiliser (pasture grass species)	Y	ha	\$1,875		\$0	Includes treating, weighing, mixing with fertiliser + spreading by tractor or helicopter (aerial seeding).
	Direct seeding / fertiliser (tree or native grass species)	Y	ha	\$4,135		\$0	Includes treating, weighing, mixing with fertiliser + spreading by tractor or helicopter (aerial seeding).
	Hydro-seeding with straw mulching and bitumen tack with native seed	Y	m2	\$1.90		\$0	Process to be used on flat well prepared surfaces under irrigation e.g. sewage treatment irrigation areas. Ranges from \$0.15 - \$0.50 depending on size and input variables. Native seed +\$1.00
	Hydro-seeding with straw mulching and bitumen tack with pasture seed	Y	m2	\$0.43		\$0	Process to be used on flat well prepared surfaces under irrigation e.g. sewage treatment irrigation areas. Ranges from \$0.15 - \$0.50 depending on size and input variables. Pasture seed +\$0.10

	Hydromulch - base grade or standard for flat areas that can be irrigated by water cart	Y		m2	\$0.80		\$0	Assumes use on flat areas with a gradient of less than 4:1, and where irrigation from water cart may be possible. Industry standard application rate of 2500kg/ha. Product will last short term (less than 3 months) and vegetation is required to grow ASAP for stability. This cost includes cover crop only, additional seeding required.
	Hydromulch - bonded fibre matrix grade for steep areas to stabilise up to 12 months	Y		m2	\$1.80		\$0	Assumes use on steep areas where stabilisation is required for up to 12 months. Application rate of ~3500kg/ha. This cost includes cover crop only, additional seeding required.
	Hydromulch - high performance flexible growth medium grade	Y		m2	\$2.50		\$0	Assumes use on extreme slopes where stabilisation is required for up to 18 months. Application rate of ~4,000kg/ha minimum. This cost includes cover crop only, additional seeding required.
	Single application of fertiliser (pasture)	Y		ha	\$420.00		\$0	Assumes 250 kg / ha. These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Single application of fertiliser (trees)	Y		ha	\$140.00		\$0	These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Spoil amelioration (adding lime / gypsum etc.)	Y		ha	\$1,000.00		\$0	Assumes 2.5 t / ha as an average application rate.
	growth media amelioration with biosolids	Y		ha	\$1,015		\$0	Recent experience with agronomy projects.
	Construct no-climb stock fence around rehabilitated areas	Y		m	\$22.00		\$0	Standard rate for no-climb stock fencing.
	Construct standard stock fence around rehabilitated areas	Y		m	\$13.00		\$0	Standard rate for standard stock fencing.
	Purchase and erect warning signs	Y		allow	\$250.00		\$0	Compliance with AS 1319-1994 - Safety signs for the occupational environment - installed every 25 m.
	Supply from external sources virgin excavated natural material (VENM) for growth media.	Y		m3	\$80.80		\$0	D7 to spread material at \$205/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$70/m3 for imported fill material.
	Supply from external sources a combination of virgin excavated natural material (VENM) and spoil from large excavation for filling voids and/or capping etc.	Y		m3	\$72.50		\$0	D10 push into void at \$270/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$60/m3 for imported fill material.
	Clearing and grubbing of trees and vegetation	Y		ha	\$4,730.00		\$0	Clearing and grubbing of light vegetation growth e.g. regrowth
	Topsoil stripping	Y		m3	\$4.86		\$0	Stripping or topsoil at an approximate depth of 0.2 m into stockpiles; load and haul to final rehabilitation location required or respreading where necessary.
	Growth media supplementation with manure	Y		ha	\$747.50		\$0	Addition of manure to improve soil quality.
	Utilise biotic soil media - organic topsoil alternative	Y		m2	\$2.50		\$0	Material that can be applied as an alternative to spreading topsoil prior to hydromulching.
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment) Subtotal							\$0	
Water Management	Clean water dams to be retained after decommissioning – make safe and minor earthworks	Y		allow	\$2,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) @ ~\$200 per hour and pasture grass.
	Large clean water dams (i.e. ≥ 2 ha) to be retained after mine closure – make safe and minor earthworks	Y		allow	\$10,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) + pasture grass.
	Remove sediments from the floor of the dam to enable it to be converted into clean water structure (Select Haul Distance from list)	Y		m3	Select from List		\$0	Select Haul Distance Here This item includes the volume of contaminated sediment requiring removal using an excavator, truck and dozer to clean out the dam.
Water Management Subtotal							\$0	
Maintenance of Rehabilitated Areas	Maintenance of areas that have been shaped and seeded and revegetation has been 'successful'	Y		ha	\$925		\$0	Rehabilitation maintenance might include re-seeding, watering, fertilising, minor re-shaping, erosion control, inspections/audits - does not include major repair works.
	Existing rehabilitation repair - minor	Y		ha	\$1,200		\$0	Areas requiring minor repair - rills, minor growth media replacement.
	Existing rehabilitation repair - moderate	Y		ha	\$1,700		\$0	Areas requiring moderate repair - rills, significant growth media replacement.
	Existing rehabilitation repair - major	Y		ha	\$2,500		\$0	Areas requiring major repair - rills, gullies, growth media replacement, some level of additional surface water management.
	Existing rehabilitation repair - total failure of landform	Y		ha	\$40,000		\$0	Areas that require extensive rehabilitation repair - re-design and re-construction of landform.
Maintenance of Rehabilitated Areas Subtotal							\$0	
Additional Items Subtotal							\$0	
Total Cost for Tailings & Rejects Domain							\$0	

Underground Operations

Domain 3a: Overburden & Waste

Total Cost for Overburden & Waste Domain

\$0

Additional Assumptions: Record any relevant assumptions to this domain below:

Key Rehabilitation Area Data for Domain		Enter data below manually
Total Landform Establishment:		
Total Growth Media Development:		
Total Ecosystem Establishment:		

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Contaminated Materials	Treatment of known Acid Sulfate Soils	Y		ha	\$2,580		\$0		Assumes ASS is treatable via neutralisation and does not require capping and isolation. Assumes 1% by weight lime addition and treatment to 100 mm depth only.
	Removal and disposal of plastic liner (i.e. dam, leach pad, sump etc.)	Y		m2	\$1		\$0		Provisional sum for cutting using ripping tynes and on-site disposal of the liner.
	Long haulage brine/salt for disposal (Select Haul Distance from list)	Y		tonne	Select from List			Select Haul Distance Here	Costs for haulage to location for authorised disposal.
	Brine disposal to landfill - fees only	Y		tonne	\$288		\$0		Rate for trackable liquid levy of \$78.20 per tonne and authorised disposal to landfill.
	Long haulage water (clean or contaminated) (Select Haul Distance from list)	Y		tonne	Select from List			Select Haul Distance Here	Assumes transport in a 20,000 L tanker. Add disposal costs to
Contaminated Materials Subtotal							\$0		
Roads and Tracks	Unsealed roads / vehicle park-up areas – minor works including deep rip and trim	Y		ha	\$1,040.00		\$0		Assumes ~6 m road width - 16H Grader.
	Unsealed roads / access tracks / vehicle park-up areas with windrows and/or small earthen bunds – minor earthworks and deep rip and trim	Y		ha	\$1,500		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - no seed
	Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip and seed (pasture grass)	Y		ha	\$3,700		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$4,485		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (pasture grass)	Y		ha	\$4,870		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$7,025		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Remove stabilised material (blue metal, aggregate etc.) from roadways and disposal on-site/locally (Select Haul Distance from list)	Y			m3	Select from List			Select Haul Distance Here
Roads and Tracks Subtotal							\$0		
Earthworks / Structural Works (Landform Establishment)	Major bulk pushing to achieve grades nominated in the approval/permit – Select Push Length	Y		m3	Select from List			Select Push Length Here	Major bulk pushing to achieve grades nominated in the approval/permit
	Minor reshaping and pushing	Y		ha	\$3,900		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation).
	Fill dams, voids etc. - Source local material, cart and spread to cap or backfill, cap thickness determined by approval / permit (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here	This item includes the volume of material requiring backfill using an excavator and scraper to fill the void and enable the establishment of rehabilitation.
	Shotcrete application on cuttings and steep slopes	Y		m2	\$185.00		\$0		This rate is used to rehabilitate steep slopes of weathered rock, roadway cuttings, etc that cannot be cut back and stabilised.
	Trim, rock rake & deep rip (includes levelling / landscaping and rip in 1 direction)	Y		ha	\$1,130.00		\$0		Undertaken using D10 dozer and 16M grader.
	Structural works, banks, waterways - contour banks, drainage channels and other soil conservation measures	Y		ha	\$1,600		\$0		Combination of dozer and excavator work plus grader for ~4 hours each per ha.
Construction of spine drains / drop structures and/or stabilising water course entry points - required for large catchments	Y			m2	\$27.00		\$0		Installation of on-site rock material (rip-rap) where managing water run-off from disturbed land and/or upon entry to water courses - prevents erosion of gully head (assumes competent material is locally available). If required to be sourced off site, assume an additional \$20/m2.
Earthworks / Structural Works (Landform Establishment) Subtotal							\$0		

Mine Waste

<p>Ideal Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with little chemical reactivity (no to low risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and good physical properties (not significantly hydrophilic, shear strength does not limit equipment choice, no artificial strengthening required)</p>	<p>Y</p>	<p>ha</p>	<p>\$82,000</p>	<p></p>	<p>\$0</p>	<p></p>	<p>This includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume material with the appropriate chemical and physical properties. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness of approximately 0.5 m to 1 m and 0.15 m - 0.2 m growth media (assume at least 1 m thick cover required for carbonaceous material covers). Water quality from runoff, seepage etc. meets site-specific environment water quality values. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in addition to any long haulage volume in 8.05.</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p></p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p></p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>
<p>Efficient Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with moderate chemical reactivity (low to medium risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and moderate physical properties (not significantly hydrophilic, shear strength limits equipment choice somewhat, no artificial strengthening required)</p>	<p>Y</p>	<p>ha</p>	<p>\$146,500</p>	<p></p>	<p>\$0</p>	<p></p>	<p>This item includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume of material to cap / cover facilities where the tailings or rejects base is at a strength that enables economically efficient construction methods with small plant. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness ranging from >1 m to 2 m thickness constructed in 1 m layers + growth media up to 0.2 m depth. This may require additional materials (such as capillary breaks, geofabric, etc.) - use alternate rate cells below, specific material types (e.g. acid neutralising / consuming materials, competent rock etc.), and associated activities (i.e., load / haul / place / crush / screen / borrow etc.). Costs for haulage of specialised/additional materials must be added separately if required. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in addition to any long haulage volume in 8.05.</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p></p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p></p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>

	Hydromulch - base grade or standard for flat areas that can be irrigated by water cart	Y		m2	\$0.80		\$0	Assumes use on flat areas with a gradient of less than 4:1, and where irrigation from water cart may be possible. Industry standard application rate of 2500kg/ha. Product will last short term (less than 3 months) and vegetation is required to grow ASAP for stability. This cost includes cover crop only, additional seeding required.
	Hydromulch - bonded fibre matrix grade for steep areas to stabilise up to 12 months	Y		m2	\$1.80		\$0	Assumes use on steep areas where stabilisation is required for up to 12 months. Application rate of ~3500kg/ha. This cost includes cover crop only, additional seeding required.
	Hydromulch - high performance flexible growth medium grade	Y		m2	\$2.50		\$0	Assumes use on extreme slopes where stabilisation is required for up to 18 months. Application rate of ~4,000kg/ha minimum. This cost includes cover crop only, additional seeding required.
	Single application of fertiliser (pasture)	Y		ha	\$420.00		\$0	Assumes 250 kg / ha. These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Single application of fertiliser (trees)	Y		ha	\$140.00		\$0	These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Spoil amelioration (adding lime / gypsum etc.)	Y		ha	\$1,000.00		\$0	Assumes 2.5 t / ha as an average application rate.
	growth media amelioration with biosolids	Y		ha	\$1,015		\$0	Recent experience with agronomy projects.
	Construct no-climb stock fence around rehabilitated areas	Y		m	\$22.00		\$0	Standard rate for no-climb stock fencing.
	Construct standard stock fence around rehabilitated areas	Y		m	\$13.00		\$0	Standard rate for standard stock fencing.
	Purchase and erect warning signs	Y		allow	\$250.00		\$0	Compliance with AS 1319-1994 - Safety signs for the occupational environment - installed every 25 m.
	Supply from external sources virgin excavated natural material (VENM) for growth media.	Y		m3	\$80.80		\$0	D7 to spread material at \$205/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$70/m3 for imported fill material.
	Supply from external sources a combination of virgin excavated natural material (VENM) and spoil from large excavation for filling voids and/or capping etc.	Y		m3	\$72.50		\$0	D10 push into void at \$270/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$60/m3 for imported fill material.
	Clearing and grubbing of trees and vegetation	Y		ha	\$4,730.00		\$0	Clearing and grubbing of light vegetation growth e.g. regrowth
	Topsoil stripping	Y		m3	\$4.86		\$0	Stripping or topsoil at an approximate depth of 0.2 m into stockpiles; load and haul to final rehabilitation location required or respreading where necessary.
	Growth media supplementation with manure	Y		ha	\$747.50		\$0	Addition of manure to improve soil quality.
	Utilise biotic soil media - organic topsoil alternative	Y		m2	\$2.50		\$0	Material that can be applied as an alternative to spreading topsoil prior to hydromulching.
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment) Subtotal							\$0	
Water Management	Clean water dams to be retained after decommissioning – make safe and minor earthworks	Y		allow	\$2,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) @ ~\$200 per hour and pasture grass.
	Large clean water dams (i.e. ≥ 2 ha) to be retained after mine closure – make safe and minor earthworks	Y		allow	\$10,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) + pasture grass.
	Remove sediments from the floor of the dam to enable it to be converted into clean water structure (Select Haul Distance from list)	Y		m3	Select from List		\$0	Select Haul Distance Here This item includes the volume of contaminated sediment requiring removal using an excavator, truck and dozer to clean out the dam.
Water Management Subtotal							\$0	
Maintenance of Rehabilitated Areas	Maintenance of areas that have been shaped and seeded and revegetation has been 'successful'	Y		ha	\$925.00		\$0	Rehabilitation maintenance might include re-seeding, watering, fertilising, minor re-shaping, erosion control, inspections/audits - does not include major repair works.
	Existing rehabilitation repair - minor	Y		ha	\$1,200		\$0	Areas requiring minor repair - rills, minor growth media replacement.
	Existing rehabilitation repair - moderate	Y		ha	\$1,700		\$0	Areas requiring moderate repair - rills, significant growth media replacement.
	Existing rehabilitation repair - major	Y		ha	\$2,500		\$0	Areas requiring major repair - rills, gullies, growth media replacement, some level of additional surface water management.
	Existing rehabilitation repair - total failure of landform	Y		ha	\$40,000		\$0	Areas that require extensive rehabilitation repair - re-design and re-construction of landform.
Maintenance of Rehabilitated Areas Subtotal							\$0	
Additional Items Subtotal							\$0	
Total Cost for Overburden & Waste Domain							\$0	

Underground Operations

Domain 4a: Subsidence and Management

Total Cost for Subsidence and Management Activities

\$192,160

Additional Assumptions: Record any relevant assumptions to this domain below:

		Key Rehabilitation Area Data for Domain	
		Total Landform Establishment:	Enter data below manually
		Total Growth Media Development:	
		Total Ecosystem Establishment:	

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Subsidence Repairs	Minor stabilisation works and maintenance of mine subsidence areas - ripping etc.	Y	3	ha	\$1,470		\$4,410		Undertaken using Dozer. Costs subject to the extent of subsidence impacts
	Crack filling to repair subsidence impacts	Y		m	\$1,450		\$0		Undertake more substantial works to backfill cracks and/or sink holes (e.g., filling with mulch prior to grouting, grouting, etc.) Costs subject to the extent of subsidence impacts. Include >5 km haul of fill.
	Water course restoration to repair subsidence impacts	Y		allow	Use alternate rate cell		\$0		Undertake more substantial works to remediate water courses (e.g., channel bed repairs, rock bar repairs, swamp stabilisation etc.)
	Create cut-through to re-establish natural water courses/drainage channels following subsidence	Y		allow	\$3,000		\$0		Includes all earthworks and revegetation required to re-establish the natural drainage profile of the subsidised area.
Subsidence Repairs Subtotal							\$4,410		
Vents, Shafts and Boreholes	Maintenance and monitoring of sealed adits/portals and shafts (for a total of 5 years)	Y	6	allow	\$25,000		\$150,000		Assume 1 x day visual inspection (10hrs inc' travel) for suitably qualified / competent person + reporting, for an annual inspection @ \$5,000 per year. Exclusions are intrusive investigation and testing (e.g. concrete strength etc).
Vents, Shafts and Boreholes Subtotal							\$150,000		
Water Management	On-site treatment of contaminated water due to high salt (includes removal of metals etc, brine disposal and cost of mobile water treatment unit)	Y		ML	\$3,600		\$0		Rate can fluctuate depending on treatment type however this is a suitable standard rate for current programs at mining operations.
	On-site treatment of contaminated water due to low pH (includes removal of metals etc, neutralisation treatments and cost of mobile water treatment unit)	Y		ML	\$1,500		\$0		Rate can fluctuate depending on treatment type however this is a suitable standard rate for current programs at mining operations.
Water Management Subtotal							\$0		
Creek Diversions	Repairs and/or stabilisation of new or compromised water course diversion	Y		m	\$2,500		\$0		Assumes material is suitable for revegetating and has a reasonable chance of stabilising.
	Long term maintenance of water course diversion - Channel constructed through backfilled material	Y		m	\$1,500		\$0		Assumes maintenance has been kept up and significant works are not required.
	Long term maintenance of water course diversion - Channel constructed through competent material	Y		m	\$750.00		\$0		Assumes maintenance has been kept up and significant works are not required.
	Installation of rock armouring	Y		m2	\$6.00		\$0		Assumes competent material is locally available - multiply costs by 2 for sourcing and transporting from offsite location.
Creek Diversions Subtotal							\$0		
Land Management	Pest management on buffer lands, non-disturbed, and rehabilitated areas	Y	25	ha	\$150.00		\$3,750		Feral animal baiting programs if required and waste materials required to be removed.
	Land management of undisturbed areas (rehabilitation, weeds, ferals, erosion and sediment control works)	Y	25	ha	\$400.00		\$10,000		Undisturbed areas within the lease boundary that require land management activities.
Land Management Subtotal							\$13,750		
Heritage Items	The restoration and care and maintenance of items that have heritage significance	Y		allow	Use alternate rate cell		\$0		Item for the redistribution of Aboriginal artefacts, preservation of European heritage items or a combination of activities.
Heritage Items Subtotal							\$0		
Sundry Items	Development of an 'Unplanned' Project Closure Plan - State Significant Development with closure planning well progressed i.e. preferred cover design, closure environment modelled e.g. groundwater /subsidence / pit lakes, preliminary seal designs, etc. and only finalisation of detailed engineering designs required	Y		allow	\$100,000		\$0		Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities. Assumes outcomes of studies readily available including modelling, landform design, geochemistry, demolition, etc. Costs to finalise options by domain and finalise designs for construction. Assume a simple site e.g. single open cut, no legacy operations historic in the area, little social dependence, etc. Depending on site size, complexity, final land use requirements and knowledge base investigations can range from ~\$75k to >\$1 M. Sites with more than 1 pit to add \$50,000 to rate.

Development of an 'Unplanned' Project Closure Plan - Non State Significant Development with at least ≥2 of the following aspects requiring closure planning, but no significant issues realised at this time: previous subsidence, medium or higher geochemistry risk and/or spontaneous combustion propensity, known/ likely contamination, tailings / rejects, final void	Y		allow	\$90,000		\$0	Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities. Estimated cost for developing closure plan including studies - basic to satisfy risks and decisions includes risk assessment, options analysis, Closure Plan. Sites with more than 1 pit to add \$50,000 to rate.
Development of an 'Unplanned' Project Closure Plan - Non State Significant Development with no EPL and/or only one of the following relevant aspects: previous subsidence, low to medium geochemistry risk and/or spontaneous combustion propensity, known limited contamination, small approved final void	Y		allow	\$15,000		\$0	Assumes sediment control is the key concern for rehabilitation e.g. small mines, exploration operations. Includes risk assessment, sampling and analyses on <5 samples, one study and Closure Plan.
Development of an 'Unplanned' Project Closure Plan - State Significant Development with only preliminary to conceptual closure planning in place	Y		allow	\$300,000		\$0	Includes costs for key investigations and studies including designs e.g. geochemistry, Contamination Remediation Action Plan, subsidence risk, cover/capping and final landform, site wide surface water, etc. Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities. Assume at least 15 types of studies required ranging from geotechnical to ecology and social, development of a closure plan including address of obligations. Assume a simple site e.g. single open cut, no legacy operations historic in the area, little social dependence, etc. Depending on site size, complexity, final land use requirements and knowledge base investigations can range to >\$3 M. Sites with more than 1 pit to add \$50,000 to rate.
Development of an 'Unplanned' Project Closure Plan - Non State Significant Development with at least ≥2 of the following aspects resulting in significant issues requiring remediation: previous subsidence, medium or higher geochemistry risk and/or spontaneous combustion propensity, known/ likely contamination, tailings / rejects, final void	Y		allow	\$125,000		\$0	Includes costs for key investigations and studies including economic treatments and designs e.g. geochemistry, Contamination Remediation Action Plan, subsidence risk, cover/capping and final landform, site wide surface water, etc. Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities.
Develop a Review of Environmental Factors (REF) to facilitate rehabilitation including contamination works.	Y	0	allow	\$27,950		\$0	Based on experience for a REF after completion of a detailed closure study (e.g. contamination investigation) costs could range from \$10,000 to \$100,000 ex GST. Note this does not apply to a Statement of Environmental Effects or Environmental Impact Statement.
Site security during closure	Y		yr.	\$75,000		\$0	Provisional sum for site security measures required during closure. This includes nightly patrols and first response in the event of an out of hours incident.
Choose type of HAZMAT Clean-up required - cleaning and decontaminating plant and equipment, chemical storage locations, oil and grease traps, tanks, vessels, and pipe work etc	Y	1	allow	\$0		\$0	Select type of HAZMAT Clean-up Required Type of HAZMAT Clean-up required - cleaning and decontaminating plant and equipment, chemical storage locations, oil and grease traps, tanks, vessels, and pipe work etc
Removal and disposal of radiation devices	Y		each	\$31,630		\$0	Provisional sum for removal and disposal of monitoring devices on conveyors using a radiation source (i.e., Americium - 241, Plutonium - 238, Caesium - 137 etc). Source isotope type, quantity, strength, weight, source holder type, source holder weight, pick-up location (among others) will directly affect pricing.
Additional fees for accessing State, Crown or other public lands for rehabilitation/remediation activities	Y		allow	Use alternate rate call		\$0	Provisional sum.
Sundry Items Subtotal						\$0	
Mobilisation and Demobilisation							
Mobilisation & Demobilisation for small mine or quarry - small fleet	Y	2	Item	\$12,000		\$24,000	May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.
Mobilisation & Demobilisation for small mine or quarry - medium to large fleet	Y		Item	\$35,000		\$0	May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.
Mobilisation & Demobilisation (Distance to site <150 km)	Y		item	\$100,000		\$0	May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.

	Mobilisation & Demobilisation (Distance to site >150 km but <500 km)	Y		item	\$150,000		\$0		May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.	
	Mobilisation & Demobilisation (Distance to site >500 km but <1000 km)	Y		item	\$300,000		\$0		May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.	
	Mobilisation & Demobilisation (Distance to site >1000 km)	Y		item	\$500,000		\$0		May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.	
Mobilisation and Demobilisation Subtotal							\$24,000			
Additional Items	Other 1 <insert>	N			This is				This item includes <<to be added by the operator>>	
	Other 2 <insert>	N			deliberately				This item includes <<to be added by the operator>>	
	Other 3 <insert>	N			left blank				This item includes <<to be added by the operator>>	
Additional Items Subtotal							\$0			
Total Cost for Subsidence and Management Activities							\$192,160			

Underground Operations

Domain 1b: Infrastructure

Total Cost for Infrastructure Domain

\$0

Additional Assumptions: Record any relevant assumptions to this domain below:

Key Rehabilitation Area Data for Domain		Enter data below manually
Total Landform Establishment:		
Total Growth Media Development:		
Total Ecosystem Establishment:		

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Termination of Services and Demolition Works	Disconnect and terminate all services (Water, electricity, gas etc at point of attachment to site)	Y		allow	\$35,000		\$0		For disconnection of all services, at building boundaries, physical cut at the point of attachment or distribution location. If infrastructure is not consolidated (i.e., administration, camp and workshops are in separate places), consider multiple disconnection fees.
	Disconnect and terminate services at remote areas (i.e. pump stations, remote workshops, sewage treatment plant etc.)	Y		allow	\$5,850		\$0		Used for infrastructure remote from primary connection. Can also be used for small mines / quarries that do not have dedicated supplies from supply authorities such as steel lattice power lines.
	Removal of low/medium voltage powerlines including disconnection, rolling up the wires and removing the poles - does not include the removal of substations	Y		km	\$15,000		\$0		Applies to power lines on stobie, concrete or similar poles.
	Removal of power lines on tower or lattice structures (this includes disconnection, rolling up the wires and removing the structures) - does not include the removal of substations	Y		km	\$100,000		\$0		Applies to power lines on steel tower and steel lattice structures assuming 3 towers / km.
	Remove small rail, road, water course overpass - manage potential interruptions and demolish and remove bridge supports/pylons/bridge structure etc. and dispose of waste material on-site/locally	Y		Item	\$350,000		\$0		Smaller structures - minimal civil works to demolish (constructed for the purposes of mining related works - does not include transport to regional disposal facility or equivalent).
	Remove medium rail, road, water course overpass - manage potential interruptions and demolish and remove bridge supports/pylons/bridge structure etc. and dispose of waste material on-site/locally	Y		Item	\$500,000		\$0		Medium structures - minimal civil works to demolish (constructed for the purposes of mining related works - does not include transport to regional disposal facility or equivalent).
	Remove large / significant rail, road, water course overpass - manage potential interruptions and demolish and remove bridge supports/pylons/bridge structure etc. and dispose of waste material on-site/locally	Y		Item	\$1,300,000		\$0		Large structures - includes significant water management e.g. watercourse diversion and civil works to demolish (constructed for the purposes of mining related works - does not include transport to regional disposal facility or equivalent).
	Demolish and/or remove substations (assumes they are in a closed building). Dispose of waste material on-site/locally	Y		m2	\$100.00		\$0		Simple structure to demolish mechanically (no labour required), assumes single story building with no asbestos and segregation of contents for scrap as applicable.
	Demolish and remove switchyard. Dispose of waste material on-site/locally	Y		m2	\$75.00		\$0		Includes demolition and removal of all switchgear and transformers etc. and segregation of contents for scrap as applicable.
	Demolish and remove demountable structures on concrete stumps. Assumes not being re-used	Y		m2	\$40.00		\$0		Crib huts, temporary offices and other 'non permanent' structures. Does not include transport to regional disposal facility or equivalent.
	Demolish and remove small buildings/tanks (admin buildings, single story accommodation etc) and disposal on-site/locally	Y		m2	\$61.00		\$0		Simple structure to demolish, assumes no greater than 2 stories high. Does not include transport to regional disposal facility or equivalent.
	Demolish and remove light industrial buildings and disposal on-site/locally	Y		m2/floor	\$90.00		\$0		Needs to be calculated per floor/level (Assume 1 floor/level = 3.4 m) - does not include transport to regional disposal facility or equivalent. Assumes asbestos free and mechanically demolished.
	Demolish and remove industrial buildings (workshops tyre change and servicing area etc not CHPP/process plant) and disposal on-site/locally	Y		m2/floor	\$130.00		\$0		Needs to be calculated per floor/level (Assume 1 floor/level = 3.4 m). Does not include transport to regional disposal facility or equivalent.
	Demolish and remove CHPP/process plant (include the area of each floor of the structure) and disposal on-site/locally	Y		m2/floor	\$225.00		\$0		Needs to be calculated per floor/level (Assume 1 floor/level = 3.4 m). Does not include transport to regional disposal facility or equivalent.
	Collapse, demolish and remove washery, crushers, hoppers, mills, furnaces, agglomeration, electrowinning, floatation, sizing stations, rotary breakers, etc (include the area of each floor of the structure) and disposal on-site/locally	Y		m2/floor	\$225.00		\$0		Needs to be calculated per floor/level (Assume 1 floor/level = 3.4 m). Does not include transport to regional disposal facility or equivalent.
	Collapse, demolish and remove stacker OR reclaim (radial or luffing etc. with maneuverability for stockpile control) and disposal on-site/locally	Y		allow	\$750,000		\$0		Cost for removal of stacker or reclaim unit only. Does not include terminate services, remove rails and ballast etc. Does not include transport to regional disposal facility or equivalent.
Collapse, demolish and remove bucket wheel stacker/reclaimer and disposal on-site/locally	Y		allow	\$2,000,000		\$0		Cost for just removal of the bucket wheel stacker/reclaim units. Does not include terminate services, remove rails and ballast etc. Does not include transport to regional disposal facility or equivalent.	

Remove stacker/reclaimer rails and ballast and demolish and remove concrete footings etc and disposal on-site/locally	Y		m	\$75.00		\$0	Includes both rails, does not include the conveyor system. Does not include transport to regional disposal facility or equivalent.
Collapse, Cut and Remove 5000T coal silo and disposal on-site/locally	Y		allow	\$92,500		\$0	Collapse structure and remove. Does not include transport to regional disposal facility or equivalent.
Collapse, Cut and Remove 3000 T coal silo and disposal on-site/locally	Y		allow	\$77,500		\$0	Collapse structure and remove. Does not include transport to regional disposal facility or equivalent.
Collapse, Cut and Remove 1250 T coal silo and disposal on-site/locally	Y		allow	\$62,500		\$0	Collapse structure and remove. Does not include transport to regional disposal facility or equivalent.
Collapse, Cut and Remove rail loading bins and disposal on-site/locally	Y		allow	\$65,000		\$0	Collapse structure and remove. Does not include transport to regional disposal facility or equivalent.
Demolish and Remove large concrete rail loading bin - and disposal on-site/locally	Y		allow	\$460,000		\$0	Collapse structure and remove. Does not include transport to regional disposal facility or equivalent.
Demolish and remove onground conveyors, transfer stations & gantries (scrap only – does not include dismantling for reuse at another site) and disposal on-site/locally	Y		m	\$185.00		\$0	Estimate for on-ground conveyor including anything up to 10 m off the ground. Does not include transport to regional disposal facility or equivalent.
Demolish and remove elevated conveyors, transfer stations & gantries (scrap only, does not include dismantling for reuse at another site) and disposal on-site/locally	Y		m	\$295.00		\$0	Estimate for elevated conveyor up to -10 m off the ground. Does not include transport to regional disposal facility or equivalent.
Demolish and remove overhead conveyors, transfer stations & gantries (scrap only, does not include dismantling for reuse at another site) and disposal on-site/locally. This may include small scale fixed material stacking infrastructure	Y		m	\$850		\$0	Estimate for overhead conveyor including conveyors that are >10 m off the ground that require a crane to remove. Does not include transport to regional disposal facility or equivalent.
Remove and demolish conveyor from reclaim tunnel (Does not include excavation and demolition of reclaim tunnel roof)	Y		m	\$150.00		\$0	Due to no canopy or infrastructure attached.
Demolition of reclaim tunnel concrete (Assumes complete removal and dumping in mine pit void)	Y		m	\$950.00		\$0	Assumes this area will be used for another land-use that requires the structure to be dug up and re-buried somewhere else.
Demolition and removal of vent raise fans, electrical substation and winch and disposal on-site/locally	Y		allow	\$25,000.00		\$0	Does not include filling and capping the shaft. Does not include transport to regional disposal facility or equivalent.
Demolish and remove small tank clean (Thickener etc 3 - 9 m diameter) and disposal on-site/locally	Y		allow	\$10,000		\$0	Assume tank is clean - contents removed. If tank is full allow extra 30% for excavator and 2 men to dig out and dispose. Does not include transport to regional disposal facility or equivalent.
Demolish and remove medium tank clean (Thickener etc 10 - 15 m diameter) and disposal on-site/locally	Y		allow	\$30,000		\$0	Assume tank is clean - contents removed. If tank is full allow extra 30% for excavator and 2 men to dig out and dispose. Does not include transport to regional disposal facility or equivalent.
Demolish and remove large tank clean (Thickener etc 15 - 30 m diameter) and disposal on-site/locally	Y		allow	\$45,000		\$0	Assume tank is clean - contents removed. If tank is full allow extra 30% for excavator and 2 men to dig out and dispose. Does not include transport to regional disposal facility or equivalent.
Demolish and remove extra large tank clean (Thickener etc >30 m diameter) and disposal on-site/locally	Y		allow	\$100,000		\$0	Assume tank is clean - contents removed. If tank is full allow extra 30% for excavator and 2 men to dig out and dispose. Does not include transport to regional disposal facility or equivalent.
Demolish and remove tank clean (Thickener etc) >50 m diameter and disposal on-site/locally	Y		allow	\$100,000		\$0	Estimate only - may require a detailed assessment from demolition expert due to specialised equipment required for removal. Does not include transport to regional disposal facility or equivalent.
Removal of UG tank <5000 L - including pipes, bunds etc. and disposal on-site/locally	Y		allow	\$21,000		\$0	Assume tank is clean (contents removed), does not include transport to regional disposal facility or equivalent.
Removal of UG tank 5000 L - 15000 L - including pipes, bunds etc. and disposal on-site/locally	Y		allow	\$30,000		\$0	Assume tank is clean (contents removed), does not include transport to regional disposal facility or equivalent.
Remove small underground pipe and disposal on-site/locally	Y		m	\$25.00		\$0	For example: 300 mm pipes - 0.5 m deep, does not include transport to regional disposal facility or equivalent.
Remove medium underground pipe and disposal on-site/locally	Y		m	\$60.00		\$0	For example: 500 mm pipes - 1 m deep, does not include transport to regional disposal facility or equivalent.
Remove large underground pipe and disposal on-site/locally	Y		m	\$165.00		\$0	For example: 1 m pipes - 2 m deep.
Remove above ground pipe (supported) and disposal on-site/locally	Y		m	\$12.00		\$0	~300 mm pipes and assumes pipes are in close proximity to infrastructure areas. Does not include transport to regional disposal facility or equivalent.
Remove surface pipelines (unsupported) and disposal on-site/locally	Y		m	\$15.00		\$0	~300 mm pipes and assumes pipes are used for water transfer between pits (or similar) and remotely located. Does not include transport to regional disposal facility or equivalent.

Remove pump and pontoon from small lake or dam including pipes and electrical supply or diesel tanks	Y		allow	\$20,000		\$0	Includes equipment for retrieval - boats, etc. and labour. Does not include transport to regional disposal facility or equivalent.
Remove bitumen (car park and access roads) and dispose on-site/locally	Y		m2	\$10.00		\$0	Scalp bitumen and stabilised material. Generally haulage rates will be \$0.60 - \$1.20 / km, depending on truck fleet, loaders etc. For off-site disposal use alternate rate option and add \$0.90 / km for transport.
Remove bitumen (airstrip) and dispose on-site/locally	Y		m2	\$20.00		\$0	Scalp bitumen and stabilised material. Generally haulage rates will be \$0.60 - \$1.20 / km, depending on truck fleet, loaders etc. For off-site disposal use alternate rate option and add \$0.90 / km for transport.
Remove concrete pads & footings (<300 mm thickness) and disposal on-site/locally	Y		m2	\$36.00		\$0	Breaking up slab and disposal or for conversion to aggregate. Generally haulage rates will be \$0.60 - \$1.20 / km, depending on truck fleet, loaders etc. For off-site disposal use alternate rate option and add \$0.90 / km for transport.
Remove concrete pads & footings (>300 mm thickness) and disposal on-site/locally	Y		m2	\$75.00		\$0	Breaking up slab and disposal or for conversion to aggregate. Generally haulage rates will be \$0.60 - \$1.20 / km, depending on truck fleet, loaders etc. For off-site disposal use alternate rate option and add \$0.90 / km for transport.
Crush concrete to make road aggregate - 75 mm	Y		tonne	\$10.00		\$0	Does not include haulage of materials - assumes crushing plant is readily available.
Crush concrete to make road aggregate - 50 mm	Y		tonne	\$13.00		\$0	Does not include haulage of materials - assumes crushing plant is readily available.
Crush concrete to make road aggregate - 30 mm	Y		tonne	\$15.00		\$0	Does not include haulage of materials - assumes crushing plant is readily available.
Remove fence (cyclone/wire fence) and disposal on-site/locally	Y		m	\$20.00		\$0	Roll up fence and remove posts.
Removal of small plastic tanks	Y		each	\$1,000.00		\$0	Remove small poly tanks used for water storage, etc.
Demolish and remove galvanised/corrugated light weight tanks	Y		each	\$500.00		\$0	Demolish and remove small lightweight metal tanks. No costs included for managing liquids, etc.
Demolish and remove communication towers	Y		each	\$5,000.00		\$0	Cost includes demolition and removal of tower only; separate costs required for disconnection of services, demolition of footings, etc.
Removal of UG services (power within main gate areas, etc.)	Y		allow	\$50,000.00		\$0	Assume service disconnection at the mine boundary is at surface level. This cost covers all fees and charges
Waste disposal to Council landfill (general waste) - haulage >10 km but <15 km	Y		tonne	\$7.00		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill (general waste) - haulage >15 km but <25 km	Y		tonne	\$9.00		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill (general waste) - haulage >25 km but <50 km	Y		tonne	\$12.50		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill (industrial demolition / concrete / scrap metal) - haulage >10 km but <15 km	Y		tonne	\$32.00		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill (industrial demolition / concrete / scrap metal) - haulage >15 km but <25 km	Y		tonne	\$36.00		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill (industrial demolition / concrete / scrap metal) - haulage >25 km but <50 km	Y		allow	Use alternate rate call		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill - fees (general waste)	Y		tonne	\$193.00		\$0	Fee for waste disposal of general waste to local Council landfill; transport rates separate. Please note that this is not applicable to operations with approval for building and demolition waste disposal on site.
Waste disposal to Council landfill - fees (industrial demolition / concrete / scrap metal)	Y		tonne	\$174.00		\$0	Fee for waste disposal of industrial demolition / concrete / scrap metal waste to local Council landfill; transport rates separate. Rate does not assume material is recyclable. Please note that this is not applicable to operations with approval for building and demolition waste disposal on site.
Termination of Services and Demolition Works Subtotal						\$0	

Rail Infrastructure									
Remove rail loop and spur, ballast etc. and disposal on-site/locally	Y		m	\$60.00		\$0		Remove all materials to allow area to be reshaped and rehabilitated - does not include transport to regional disposal facility or equivalent.	
Remove train loading facilities and disposal on-site/locally	Y		m2	\$185.00		\$0		Remove rail load point infrastructure including gantries and control structures. Does not include transport to regional disposal facility or equivalent.	
Reshape rail spur and load out areas. Does not include growth media and revegetation	Y		ha	\$2,860		\$0		D10 Dozer and 16 H Grader (50% utilisation).	
Rail Infrastructure Subtotal						\$0			
Contaminated Materials									
Undertake a preliminary site investigation (Phase 1). This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple studies may be required.	Y		Cluster	\$15,000		\$0		The preliminary investigation would include at minimum a desktop assessment of the area and site history, incidents, etc. as per the National Environmental Protection (NEPM) Phase 1 assessment (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. A cluster may include: - Mine infrastructure (i.e., fuel / chemical store, workshop, vehicle wash-down, sewage treatment etc.) - Processing plants (i.e., ore and product storage, mine waste storage and disposal, rail load-out etc.) - Remote pit-top facilities (i.e., vehicle re-fuel, sewage treatment, secondary workshop, chemical storage etc.)	
Undertake an intrusive site investigation on sites with small footprints to investigate e.g. ≤15 ha. This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple intrusive investigations should be included.	Y		Cluster	\$44,000		\$0		The intrusive investigation would include at minimum a site walkover and field sampling as per the National Environmental Protection (NEPM) Phase 2 intrusive investigation (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. Note: An intrusive investigation is not required for all contaminated areas and should be applied considering the rehabilitation program, site history, location, etc. A cluster area where it is highly anticipated that contamination has occurred (i.e., underground tanks / pipes that are known to have leaked, chemical stores with earthen bunds, around ineffective oil/water separators etc.) and further field work is required involving intrusive investigation. Assumes site is easily accessible and a small area e.g. ~10-15 ha requires investigation and testing (test pits, boreholes, etc.) based on Sampling and Analysis Quality Plan. Includes SAQP, fieldwork, sampling and analysis.	
Undertake an intrusive site investigation on sites with large footprints to investigate e.g. >15 ha. This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple intrusive investigations should be included.	Y		Cluster	\$106,000		\$0		The intrusive investigation would include at minimum a site walkover and field sampling as per the National Environmental Protection (NEPM) Phase 2 intrusive investigation (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. Note: An intrusive investigation is not required for all contaminated areas and should be applied considering the rehabilitation program, site history, location, etc. A cluster area where it is highly anticipated that contamination has occurred (i.e., underground tanks / pipes that are known to have leaked, chemical stores with earthen bunds, around ineffective oil/water separators etc.) and further field work is required involving intrusive investigation. Assume site has a history of contamination and/or a large area >15 ha requires investigation and testing (test pits, boreholes, etc.) based on Sampling and Analysis Quality Plan. Includes SAQP, fieldwork, sampling and analysis.	
Develop a Remediation Action Plan on sites with small footprints based on outcomes of intrusive investigation including strategies to address contamination exceedances	Y		allow	\$35,000		\$0		Develop remediation plan for approval including designs and detailed costs. Costs may increase if detailed designs required for construction.	
Develop a Remediation Action Plan on sites with large footprints based on outcomes of intrusive investigation including strategies to address contamination exceedances	Y		allow	Use alternate rate cell		\$0		Assumes complex site; detailed design drawings required for cover.	
Removal and disposal of contaminated water from tanks, bunded areas and sumps	Y		L	\$0.35		\$0		Cost for recent sump clean-up from resource activity - requires specialists to treat.	

Remove material (carbonaceous / metalliferous spillage or otherwise) from footprint of the process facility (leach pads) / stockpile area (ROM product) / roads and dump in a void on-site (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here	This item includes scraping and removal of the volume of carbonaceous material using dozer, grader etc. to make safe an area and enable the establishment of rehabilitation.
Load, cart and dispose of Hazardous classified contaminated material off site to a licensed landfill. Assumes cartage to a licensed landfill.	Y		m3	\$800.00		\$0		Includes load, haul and dump fees to a licensed facility.
Load, cart and disposal of Restricted classified contaminated material off site to a licensed landfill. Add \$50/m3 for cartage from regional areas	Y		m4	\$660.00		\$0		Includes load, haul and dump fees to a licensed facility.
Load, cart and disposal of Low Level contaminated material off site to a licensed landfill. Add \$50/m3 for cartage to regional landfill	Y		m3	\$220.00		\$0		Includes load, haul and dump fees to a licensed facility.
Onsite remediation of hydrocarbon contaminated soils manual land farming (Select Volume from List)	Y		m3	Select from List			Select Volume Here	Spreading of contaminated soils on a prepared surface and stimulation of aerobic microbial activity within the soils through aeration and/or the addition of minerals, nutrients and moisture to promote the aerobic degradation of organic
Mobilisation of cement stabilisation plant and equipment for hydrocarbon (i.e., PAH, long chain hydrocarbons, etc.) contaminated soil treatment	Y		Item	\$150,000		\$0		Required if treatment of hydrocarbon contamination is required to be fast tracked.
On-site remediation of hydrocarbon contaminated soils - using a mobile treatment unit	Y		m3	\$165.00		\$0		Additional cost as the treatment process is fast tracked.
Remove and dispose of asbestos (<750 m2)	Y		m2	\$50.00		\$0		Where an assessment/estimation has been made to confirm the volume of asbestos to be removed.
Remove and dispose of asbestos (>750 m2)	Y		m2	\$40.00		\$0		Where an assessment/estimation has been made to confirm the volume of asbestos to be removed.
Waste disposal to Council landfill - fees (asbestos)	Y		tonne	\$290		\$0		Landfill fees to regional landfill.
Treatment of known Acid Sulfate Soils	Y		ha	\$2,580		\$0		Assumes ASS is treatable via neutralisation and does not require capping and isolation. Assumes 1% by weight lime addition and treatment to 100 mm depth only.
Removal and disposal of plastic liner (i.e. dam, leach pad, sump etc.)	Y		m2	\$1		\$0		Provisional sum for cutting using ripping tynes and on-site disposal of the liner.
Long haulage brine/salt for disposal (Select Haul Distance from list)	Y		tonne	Select from List			Select Haul Distance Here	Costs for haulage to location for authorised disposal.
Brine disposal to landfill - fees only	Y		tonne	\$288		\$0		Rate for trackable liquid levy of \$78.20 per tonne and authorised disposal to landfill.
Long haulage water (clean or contaminated) (Select Haul Distance from list)	Y		tonne	Select from List			Select Haul Distance Here	Assumes transport in a 20,000 L tanker. Add disposal costs to additional items where warranted.
Contaminated Materials Subtotal						\$0		
Vents, Shafts and Boreholes								
Seal portals / drifts (width >3 m) – only entry seal / plug required with in front of access backfill with engineered fill for 5 m	Y		allow	\$126,000		\$0		This cost is not applicable to coal operations which require backfilling to MDG6001 or similar due to gases. Costs include engineering and QA/QC. Costs assume engineered fill backfilled between 2 x 1 m plugs for sealing, + haul material to backfill per >5 km distance + concrete pump and secondary support.
Seal portals / drifts (width >3 m) accessible to men and machinery requiring a bulkhead – grout backfill against a concrete bulkhead to be constructed	Y		allow	\$250,000		\$0		Cost includes engineering the bulkhead and underground construction (access available) followed by grout backfill via workings and rehabilitation (reshape, bulk push and full rehabilitation). Assume tunnel length of 20 m. For every additional m add \$7,250 for grouting. If no bulkhead required, deduct \$60,000.
Seal portals / drifts (width >3 m) not accessible by men or machinery – grout backfill against a concrete bulkhead existing or to be constructed	Y		allow	\$250,000		\$0		Cost includes engineering the bulkhead if required and construction via access directly above heading followed by grout backfill via boreholes every 10 m to fill voids and rehabilitation (bulk push, final trim, seeding and full rehabilitation). Assume tunnel length of 20 m. For every additional m add \$8,700 for grouting. If no bulkhead required, deduct \$60,000. Assumes any existing bulkhead is observable by camera and satisfies regulations and engineer (location, etc.).
Seal small adits (width ≤3 m) accessible by men and/or machinery or neither requiring a bulkhead – backfill with appropriate material against a concrete bulkhead existing or to be constructed. The rate includes reshaping and rehabilitation of the batter around the entrance of the adit	Y		allow	\$25,000		\$0		Costs estimated from executed works program in NSW from multiple sites. Rate assumes standard works program with suitable access, and additional roof and rib stabilisation works etc. is not required.
Costs to grout fill tunnel via mine workings to seal and eliminate voids and/or likelihood of failures of ground	Y		m	\$7,250		\$0		Workings are accessible to run grout lines via machine or seam dip is favourable i.e. dips inbye
Costs to grout fill tunnel by drilling directly above to seal and eliminate voids and/or likelihood of failures of ground	Y		m	\$8,700		\$0		Area directly above heading is accessible by drill rig with depth of cover <30 m and access outbye. One borehole required every 10m to fill void.

Demolish ventilation fans	Y		Item	\$30,000		\$0		Costs for demolition of ventilation fan prior to sealing shaft.
Seal and rehabilitate ventilation shafts on hard rock operations (no to low gas risk) or coal operations - allows for works in a remote location	Y		allow	\$150,000		\$0		Rate accounts for a range of factors including variations in depth and size, accessibility limitations, equipment transport to the shaft etc. Assumes engineered fill is available within 10 km round trip and no bulkhead required. Excludes demolition of ventilation fans.
Install gate or grill over the adit (Where site might be used by bats)	Y		Item	\$200,000		\$0		Rate accounts for a range of factors including establishing clear access, and/or working in remote locations without services, and/or stabilisation works to prevent the entry collapsing and compromising the gate etc.
Option 1 - Coal bore hole Exploration boreholes – rehabilitate coal boreholes and drill pads as required	Y		depth (m)	\$44.55		\$0		Cost to grout and cap an open exploration borehole. Assume a 20 m x 20 m drill pad requires rehabilitation - push cover of nearby growth media, rip and seed.
Option 3 - Mineral RAB and aircore drill holes Exploration boreholes – backfill open Rotary Airblast (RAB) or aircore drill holes with cuttings	Y		allow	\$42.50		\$0		May include cutting of casing, installation of a casing cap, and/or manually backfilling the hole with drill cuttings. Does not include reshaping / ripping the drill pad, amelioration / seeding etc.
Option 2 - Mineral drill hole requiring grouting Exploration boreholes – grout and cap open bore holes	Y		allow	\$5,700		\$0		Includes grouting and capping 100 - 200 m exploration boreholes to meet the requirements of Departmental Guidelines.
Boreholes – cap and seal open bore holes with steel casing (i.e., goaf drainage etc.)	Y		allow	\$6,960		\$0		Holes deeper than 100 m - includes cutting steel collar 6 m below surface, grouting and capping.
Boreholes – cap and seal open bore holes - surface-to-in-seam gas drainage	Y		allow	\$17,890		\$0		Surface-to-in-seam gas drainage boreholes.
Boreholes – cap and seal open bore holes - vertical gas drainage	Y		allow	\$16,000		\$0		Vertical gas drainage boreholes.
Boreholes – grout (with concrete) cap and seal bore holes (i.e. where sealing aquifers)	Y		allow	\$35,000		\$0		Includes multi skin sleeves to prevent aquifer mixing.
Boreholes – cap and seal service boreholes for UG coal operations	Y		allow	\$45,000		\$0		Includes large diameter boreholes used for supplying electricity (66kV), compressed air, water, solsenic etc.
Option 4 - Mineral diamond drill hole Rehabilitation of diamond drill holes and pad including sealing drill holes for mineral exploration	Y		Item	\$2,070		\$0		Bog out cuttings, remove fencing, remove rubbish, push sumps in, rehabilitate pads and tracks, cut and plug collars. Includes labour and equipment, disposal of rubbish locally on site
Option 5 - Mineral reverse circulation drill holes Rehabilitation of reverse circulation drill holes and pad including sealing drill holes for mineral exploration	Y		Item	\$1,340		\$0		Sealing required, but not complete filling with concrete/grout
Option 6 - Rehabilitation of drill hole collars Rehabilitation of drill hole collars (mineral exploration)	Y		each	\$415		\$0		Cut collar, remove, cap, backfill capped collar and cover with nearby organic or growth material
Vents, Shafts and Boreholes Subtotal						\$0		
Roads and Tracks								
Unsealed roads / vehicle park-up areas – minor works including deep rip and trim	Y		ha	\$1,040.00		\$0		Assumes ~6 m road width - 16H Grader.
Unsealed roads / access tracks / vehicle park-up areas with windrows and/or small earthen bunds – minor earthworks and deep rip and trim	Y		ha	\$1,500		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - no seed
Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip and seed (pasture grass)	Y		ha	\$3,700		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$4,485		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed

	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (pasture grass)	Y		ha	\$4,870		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$7,025		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Remove stabilised material (blue metal, aggregate etc.) from roadways and disposal on-site/locally (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here	This item includes the scraping and removal of the volume of stabilised material from the road, laydown or other surface using an excavator, dozer and grader to enable the establishment of rehabilitation.
Roads and Tracks Subtotal							\$0		
Earthworks / Structural Works (Landform Establishment)	Major bulk pushing to achieve grades nominated in the approval/permit – Select Push Length	Y		m3	Select from List			Select Push Length Here	Major bulk pushing to achieve grades nominated in the approval/permit
	Minor reshaping and pushing	Y		ha	\$3,900		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation).
	Fill dams, voids etc. - Source local material, cart and spread to cap or backfill, cap thickness determined by approval / permit (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here	This item includes the volume of material requiring backfill using an excavator and scraper to fill the void and enable the establishment of rehabilitation.
	Shotcrete application on cuttings and steep slopes	Y		m2	\$185.00		\$0		This rate is used to rehabilitate steep slopes of weathered rock, roadway cuttings, etc that cannot be cut back and stabilised.
	Trim, rock rake & deep rip (includes levelling / landscaping and rip in 1 direction)	Y		ha	\$1,130.00		\$0		Undertaken using D10 dozer and 16M grader.
	Deep rip hard stand / lay down areas	Y		ha	\$960.00		\$0		D10 deep ripping.
	Structural works, banks, waterways - contour banks, drainage channels and other soil conservation measures	Y		ha	\$1,600		\$0		Combination of dozer and excavator work plus grader for ~4 hours each per ha.
	Construction of spine drains / drop structures and/or stabilising water course entry points - required for large catchments	Y		m2	\$27.00		\$0		Installation of on-site rock material (rip-rap) where managing water run-off from disturbed land and/or upon entry to water courses - prevents erosion of gully head (assumes competent material is locally available). If required to be sourced off site, assume an additional \$20/m2.
Earthworks / Structural Works (Landform Establishment) Subtotal							\$0		
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment)	Source, cart and spread growth media (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here	If topsoil is not available on-site, then Virgin Excavated Natural Material (VENM) may need to be externally sourced.
	Planting mature trees (>15 cm)	Y		allow	\$15.00		\$0		4 m centres.
	Planting tube stock (<15 cm)	Y		allow	\$6.60		\$0		4 m centres.
	Direct seeding / fertiliser (pasture grass species)	Y		ha	\$1,875		\$0		Includes treating, weighing, mixing with fertiliser + spreading by tractor or helicopter (aerial seeding).
	Direct seeding / fertiliser (tree or native grass species)	Y		ha	\$4,135		\$0		Includes treating, weighing, mixing with fertiliser + spreading by tractor or helicopter (aerial seeding).
	Hydro-seeding with straw mulching and bitumen tack with native seed	Y		m2	\$2		\$0		Process to be used on flat well prepared surfaces under irrigation e.g. sewage treatment irrigation areas. Ranges from \$0.15 - \$0.50 depending on size and input variables. Native seed +\$1.00
	Hydro-seeding with straw mulching and bitumen tack with pasture seed	Y		m2	\$0		\$0		Process to be used on flat well prepared surfaces under irrigation e.g. sewage treatment irrigation areas. Ranges from \$0.15 - \$0.50 depending on size and input variables. Pasture seed +\$0.10
	Hydromulch - base grade or standard for flat areas that can be irrigated by water cart	Y		m2	\$1		\$0		Assumes use on flat areas with a gradient of less than 4:1, and where irrigation from water cart may be possible. Industry standard application rate of 2500kg/ha. Product will last short term (less than 3 months) and vegetation is required to grow ASAP for stability. This cost includes cover crop only, additional seeding required.
	Hydromulch - bonded fibre matrix grade for steep areas to stabilise up to 12 months	Y		m2	\$1.80		\$0		Assumes use on steep areas where stabilisation is required for up to 12 months. Application rate of ~3500kg/ha. This cost includes cover crop only, additional seeding required.
	Hydromulch - high performance flexible growth medium grade	Y		m2	\$2.50		\$0		Assumes use on extreme slopes where stabilisation is required for up to 18 months. Application rate of ~4,000kg/ha minimum. This cost includes cover crop only, additional seeding required.
	Single application of fertiliser (pasture)	Y		ha	\$420.00		\$0		Assumes 250 kg / ha. These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.

Single application of fertiliser (trees)	Y		ha	\$140.00		\$0	These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
Spoil amelioration (adding lime / gypsum etc.)	Y		ha	\$1,000.00		\$0	Assumes 2.5 t / ha as an average application rate.
growth media amelioration with biosolids	Y		ha	\$1,015		\$0	Recent experience with agronomy projects.
Construct no-climb stock fence around rehabilitated areas	Y		m	\$22.00		\$0	Standard rate for no-climb stock fencing.
Construct standard stock fence around rehabilitated areas	Y		m	\$13.00		\$0	Standard rate for standard stock fencing.
Purchase and erect warning signs	Y		allow	\$250.00		\$0	Compliance with AS 1319-1994 - Safety signs for the occupational environment - installed every 25 m.
Supply from external sources virgin excavated natural material (VENM) for growth media.	Y		m3	\$80.80		\$0	D7 to spread material at \$205/hr, Excavator (\$220/hr) load Artic Trucks (90c/km) from imported stockpile - allow nominal rate of \$70/m3 for imported fill material.
Supply from external sources a combination of virgin excavated natural material (VENM) and spoil from large excavation for filling voids and/or capping etc.	Y		m3	\$72.50		\$0	D10 push into void at \$270/hr, Excavator (\$220/hr) load Artic Trucks (90c/km) from imported stockpile - allow nominal rate of \$60/m3 for imported fill material.
Clearing and grubbing of trees and vegetation	Y		ha	\$4,730.00		\$0	Clearing and grubbing of light vegetation growth e.g. regrowth
Topsoil stripping	Y		m3	\$4.86		\$0	Stripping or topsoil at an approximate depth of 0.2 m into stockpiles; load and haul to final rehabilitation location required or respreading where necessary.
Growth media supplementation with manure	Y		ha	\$747.50		\$0	Addition of manure to improve soil quality.
Utilise biotic soil media - organic topsoil alternative	Y		m2	\$2.50		\$0	Material that can be applied as an alternative to spreading topsoil prior to hydromulching.
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment) Subtotal						\$0	
Water Management							
Clean water dams to be retained after decommissioning – make safe and minor earthworks	Y		allow	\$2,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) @ ~\$200 per hour and pasture grass.
Large clean water dams (i.e. ≥ 2 ha) to be retained after mine closure – make safe and minor earthworks	Y		allow	\$10,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) + pasture grass.
Remove sediments from the floor of the dam to enable it to be converted into clean water structure (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here This item includes the volume of contaminated sediment requiring removal using an excavator, truck and dozer to clean out the dam.
Removal of evaporation fans and/or other water transfer and management infrastructure	Y		allow	\$25,000		\$0	Provisional sum for removal of water management infrastructure.
Water Management Subtotal						\$0	
Maintenance of Rehabilitated Areas							
Maintenance of areas that have been shaped and seeded and revegetation has been 'successful'	Y		ha	\$925.00		\$0	Rehabilitation maintenance might include re-seeding, watering, fertilising, minor re-shaping, erosion control, inspections/audits - does not include major repair works.
Existing rehabilitation repair - minor	Y		ha	\$1,200		\$0	Areas requiring minor repair - rills, minor growth media replacement.
Existing rehabilitation repair - moderate	Y		ha	\$1,700		\$0	Areas requiring moderate repair - rills, significant growth media replacement.
Existing rehabilitation repair - major	Y		ha	\$2,500		\$0	Areas requiring major repair - rills, gullies, growth media replacement, some level of additional surface water management.
Existing rehabilitation repair - total failure of landform	Y		ha	\$40,000		\$0	Areas that require extensive rehabilitation repair - re-design and re-construction of landform.
Maintenance of Rehabilitated Areas Subtotal						\$0	
Additional Items Subtotal						\$0	
Total Cost for Infrastructure Domain						\$0	

Underground Operations

Domain 2b: Tailings & Rejects

Total Cost for Tailings & Rejects Domain

\$0

Additional Assumptions: Record any relevant assumptions to this domain below:

		Key Rehabilitation Area Data for Domain	Enter data below manually
		Total Landform Establishment:	
		Total Growth Media Development:	
		Total Ecosystem Establishment:	

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Contaminated Materials	Undertake a preliminary site investigation (Phase 1). This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple studies may be required.	Y		Cluster	\$15,000		\$0		The preliminary investigation would include at minimum a desktop assessment of the area and site history, incidents, etc. as per the National Environmental Protection (Site Contamination) Measure (NEPM) Phase 1 assessment (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. A cluster may include: - Mine infrastructure (i.e., fuel / chemical store, workshop, vehicle wash-down, sewage treatment etc.) - Processing plants (i.e., ore and product storage, mine waste storage and disposal, rail load-out etc.) - Remote pit-top facilities (i.e., vehicle re-fuel, sewage treatment, secondary workshop, chemical storage etc.)
	Undertake an intrusive site investigation on sites with small footprints to investigate e.g. ≤15 ha. This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple intrusive investigations should be included.	Y		Cluster	\$44,000		\$0		The intrusive investigation would include at minimum a site walkover and field sampling as per the National Environmental Protection (Site Contamination) Measure (NEPM) Phase 2 intrusive investigation (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. Note: An intrusive investigation is not required for all contaminated areas and should be applied considering the rehabilitation program, site history, location, etc. A cluster area where it is highly anticipated that contamination has occurred (i.e., underground tanks / pipes that are known to have leaked, chemical stores with earthen bunds, around ineffective oil/water separators etc.) and further field work is required involving intrusive investigation. Assumes site is easily accessible and a small area e.g. ~10-15 ha requires investigation and testing (test pits, boreholes, etc.) based on Sampling and Analysis Quality Plan. Includes SAQP, fieldwork, sampling and analysis.
	Undertake an intrusive site investigation on sites with large footprints to investigate e.g. >15 ha. This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple intrusive investigations should be included.	Y		Cluster	\$106,000		\$0		The intrusive investigation would include at minimum a site walkover and field sampling as per the National Environmental Protection (Site Contamination) Measure (NEPM) Phase 2 intrusive investigation (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. Note: An intrusive investigation is not required for all contaminated areas and should be applied considering the rehabilitation program, site history, location, etc. A cluster area where it is highly anticipated that contamination has occurred (i.e., underground tanks / pipes that are known to have leaked, chemical stores with earthen bunds, around ineffective oil/water separators etc.) and further field work is required involving intrusive investigation. Assume site has a history of contamination and/or a large area >15 ha requires investigation and testing (test pits, boreholes, etc.) based on Sampling and Analysis Quality Plan. Includes SAQP, fieldwork, sampling and analysis.
	Develop a Remediation Action Plan on sites with small footprints based on outcomes of intrusive investigation including strategies to address contamination exceedances	Y		allow	\$35,000		\$0		Develop remediation plan for approval including designs and detailed costs. Costs may increase if detailed designs required for construction.

Develop a Remediation Action Plan on sites with large footprints based on outcomes of intrusive investigation including strategies to address contamination exceedances	Y		allow	Use alternate rate cell		\$0		Assumes complex site; detailed design drawings required for cover.
Removal and disposal of contaminated water from tanks, bunded areas and sumps	Y		L	\$0.35		\$0		Cost for recent sump clean-up from resource activity - requires specialists to treat.
Remove material (carbonaceous / metalliferous spillage or otherwise) from footprint of the process facility (leach pads) / stockpile area (ROM product) / roads and dump in a void on-site (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here	This item includes scraping and removal of the volume of carbonaceous material using dozer, grader etc. to make safe an area and enable the establishment of rehabilitation.
Load, cart and dispose of Hazardous classified contaminated material off site to a licensed landfill. Assumes cartage to a licensed landfill.	Y		m3	\$800.00		\$0		Includes load, haul and dump fees to a licensed facility.
Load, cart and disposal of Restricted classified contaminated material off site to a licensed landfill. Add \$50/m3 for cartage from regional areas	Y		m4	\$660.00		\$0		Includes load, haul and dump fees to a licensed facility.
Load, cart and disposal of Low Level contaminated material off site to a licensed landfill. Add \$50/m3 for cartage to regional landfill	Y		m3	\$220.00		\$0		Includes load, haul and dump fees to a licensed facility.
Onsite remediation of hydrocarbon contaminated soils manual land farming (Select Volume from List)	Y		m3	Select from List			Select Volume Here	Spreading of contaminated soils on a prepared surface and stimulation of aerobic microbial activity within the soils through aeration and/or the addition of minerals, nutrients and moisture to promote the aerobic degradation of organic chemicals - time frame of up to 24 months.
Mobilisation of cement stabilisation plant and equipment for hydrocarbon (i.e. PAH, long chain hydrocarbons, etc.) contaminated soil treatment	Y		Item	\$150,000		\$0		Required if treatment of hydrocarbon contamination is required to be fast tracked.
On-site remediation of hydrocarbon contaminated soils - using a mobile treatment unit	Y		m3	\$165.00		\$0		Additional cost as the treatment process is fast tracked.
Remove and dispose of asbestos (<750 m2)	Y		m2	\$50.00		\$0		Where an assessment/estimation has been made to confirm the volume of asbestos to be removed.
Remove and dispose of asbestos (>750 m2)	Y		m2	\$40.00		\$0		Where an assessment/estimation has been made to confirm the volume of asbestos to be removed.
Waste disposal to Council landfill - fees (asbestos)	Y		tonne	\$290		\$0		Landfill fees to regional landfill.
Contaminated Materials Subtotal						\$0		
Roads and Tracks								
Unsealed roads / vehicle park-up areas – minor works including deep rip and trim	Y		ha	\$1,040.00		\$0		Assumes ~6 m road width - 16H Grader.
Unsealed roads / access tracks / vehicle park-up areas with windrows and/or small earthen bunds – minor earthworks and deep rip and trim	Y		ha	\$1,500		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - no seed
Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip and seed (pasture grass)	Y		ha	\$3,700		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$4,485		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (pasture grass)	Y		ha	\$4,870		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$7,025		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
Remove stabilised material (blue metal, aggregate etc.) from roadways and disposal on-site/locally (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here	This item includes the scraping and removal of the volume of stabilised material from the road, laydown or other surface using an excavator, dozer and grader to enable the establishment of rehabilitation.
Roads and Tracks Subtotal						\$0		
Earthworks / Structural Works (Landform Establishment)								
Major bulk pushing to achieve grades nominated in the approval/permit – Select Push Length	Y		m3	Select from List			Select Push Length Here	Major bulk pushing to achieve grades nominated in the approval/permit
Minor reshaping and pushing	Y		ha	\$3,900		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation).
Fill dams, voids etc. - Source local material, cart and spread to cap or backfill, cap thickness determined by approval / permit (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here	This item includes the volume of material requiring backfill using an excavator and scraper to fill the void and enable the establishment of rehabilitation.
Trim, rock rake & deep rip (includes levelling / landscaping and rip in 1 direction)	Y		ha	\$1,130.00		\$0		Undertaken using D10 dozer and 16M grader.
Structural works, banks, waterways - contour banks, drainage channels and other soil conservation measures	Y		ha	\$1,600		\$0		Combination of dozer and excavator work plus grader for ~4 hours each per ha.
Construction of spine drains / drop structures and/or stabilising water course entry points - required for large catchments	Y		m2	\$27.00		\$0		Installation of on-site rock material (rip-rap) where managing water run-off from disturbed land and/or upon entry to water courses - prevents erosion of gully head (assumes competent material is locally available). If required to be sourced off site, assume an additional \$20/m2.

Earthworks / Structural Works (Landform Establishment) Subtotal					\$0		
Mine Waste							
Ideal Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with little chemical reactivity (no to low risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and good physical properties (not significantly hydrophilic, shear strength does not limit equipment choice, no artificial strengthening required)	Y		ha	\$82,000		\$0	This includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume material with the appropriate chemical and physical properties. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness of approximately 0.5 m to 1 mand 0.15 m - 0.2 m growth media (assume at least 1 m thick cover required for carbonaceous material covers). Water quality from runoff, seepage etc. meets site-specific environment water quality values. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in additional to any long haulage volume in 8.05.
Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
Efficient Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with moderate chemical reactivity (low to medium risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and moderate physical properties (not significantly hydrophilic, shear strength limits equipment choice somewhat, no artificial strengthening required)	Y		ha	\$146,500		\$0	This item includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume of material to cap / cover facilities where the tailings or rejects base is at a strength that enables economically efficient construction methods with small plant. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness ranging from >1 m to 2 m thickness constructed in 1 m layers + growth media up to 0.2 m depth. This may require additional materials (such as capillary breaks, geofabric, etc.) - use alternate rate cells below, specific material types (e.g. acid neutralising / consuming materials, competent rock etc.), and associated activities (i.e., load / haul / place / crush / screen / borrow etc.). Costs for haulage of specialised/additional materials must be added separately if required. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage.
Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0	Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).

	Adverse Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with moderate chemical reactivity (medium to high risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or moderate to high propensity for spontaneous combustion) and moderate physical properties (not significantly hydrophilic, shear strength limits equipment choice somewhat, no artificial strengthening required)	Y	ha	\$313,000		\$0		This item includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume of material to cap / cover facilities of high geochemical risk, and / or low shear strength that prohibits economically efficient construction methods. This rate assumes suitable capping material/s are available on site within 10 km, and an average cap thickness of approximately >2 m + growth media up to 0.2 m depth. This may require additional materials (i.e., capillary breaks, geofabric, etc.), specific material types (e.g. acid neutralising / consuming materials, competent rock etc.), and associated activities (i.e. load / haul / place / crush / screen / borrow etc.). Costs for haulage of specialised materials must be added separately if required. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in addition to any long haulage volume in 8.05.
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y	allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y	allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Difficult Tailings Capping- reshaping, capping / sealing of weak or soft surfaced tailings facility with poor physical properties (significantly hydrophilic, low shear strength limits equipment choice greatly, artificial strengthening required) OR visible adverse impacts on legacy sites from chemical reactivity over lengthy exposure prior to rehabilitation	Y	ha	\$843,000		\$0		This option is typically driven by time constraints and/or when tailings properties significantly restrict adequate desiccation, resulting in a tailings shear strength that is very weak excluding access by conventional small plant. Small equipment used for rehabilitation. This excludes any additional material required to form the final landform profile in addition to this cap. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in addition to any long haulage volume in 8.05.
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y	allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y	allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Long haulage soil / weathered rock / sediment e.g. capping/covers, removal of contamination, etc. (Select Haul Distance from List)	Y	m3	Select from List			Select Haul Distance Here	Capping/cover material available within 50 km round trip e.g. waste / overburden dumps, borrow areas, etc.
Mine Waste Subtotal						\$0		
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment)	Source, cart and spread growth media (Select Haul Distance from List)	Y	m3	Select from List			Select Haul Distance Here	If topsoil is not available on-site, then Virgin Excavated Natural Material (VENM) may need to be externally sourced.
	Direct seeding / fertiliser (pasture grass species)	Y	ha	\$1,875		\$0		Includes treating, weighing, mixing with fertiliser + spreading by tractor or helicopter (aerial seeding).
	Direct seeding / fertiliser (tree or native grass species)	Y	ha	\$4,135		\$0		Includes treating, weighing, mixing with fertiliser + spreading by tractor or helicopter (aerial seeding).
	Hydro-seeding with straw mulching and bitumen tack with native seed	Y	m2	\$1.90		\$0		Process to be used on flat well prepared surfaces under irrigation e.g. sewage treatment irrigation areas. Ranges from \$0.15 - \$0.50 depending on size and input variables. Native seed +\$1.00
	Hydro-seeding with straw mulching and bitumen tack with pasture seed	Y	m2	\$0.43		\$0		Process to be used on flat well prepared surfaces under irrigation e.g. sewage treatment irrigation areas. Ranges from \$0.15 - \$0.50 depending on size and input variables. Pasture seed +\$0.10

	Hydromulch - base grade or standard for flat areas that can be irrigated by water cart	Y		m2	\$0.80		\$0	Assumes use on flat areas with a gradient of less than 4:1, and where irrigation from water cart may be possible. Industry standard application rate of 2500kg/ha. Product will last short term (less than 3 months) and vegetation is required to grow ASAP for stability. This cost includes cover crop only, additional seeding required.
	Hydromulch - bonded fibre matrix grade for steep areas to stabilise up to 12 months	Y		m2	\$1.80		\$0	Assumes use on steep areas where stabilisation is required for up to 12 months. Application rate of ~3500kg/ha. This cost includes cover crop only, additional seeding required.
	Hydromulch - high performance flexible growth medium grade	Y		m2	\$2.50		\$0	Assumes use on extreme slopes where stabilisation is required for up to 18 months. Application rate of ~4,000kg/ha minimum. This cost includes cover crop only, additional seeding required.
	Single application of fertiliser (pasture)	Y		ha	\$420.00		\$0	Assumes 250 kg / ha. These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Single application of fertiliser (trees)	Y		ha	\$140.00		\$0	These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Spoil amelioration (adding lime / gypsum etc.)	Y		ha	\$1,000.00		\$0	Assumes 2.5 t / ha as an average application rate.
	growth media amelioration with biosolids	Y		ha	\$1.015		\$0	Recent experience with agronomy projects.
	Construct no-climb stock fence around rehabilitated areas	Y		m	\$22.00		\$0	Standard rate for no-climb stock fencing.
	Construct standard stock fence around rehabilitated areas	Y		m	\$13.00		\$0	Standard rate for standard stock fencing.
	Purchase and erect warning signs	Y		allow	\$250.00		\$0	Compliance with AS 1319-1994 - Safety signs for the occupational environment - installed every 25 m.
	Supply from external sources virgin excavated natural material (VENM) for growth media.	Y		m3	\$80.80		\$0	D7 to spread material at \$205/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$70/m3 for imported fill material.
	Supply from external sources a combination of virgin excavated natural material (VENM) and spoil from large excavation for filling voids and/or capping etc.	Y		m3	\$72.50		\$0	D10 push into void at \$270/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$60/m3 for imported fill material.
	Clearing and grubbing of trees and vegetation	Y		ha	\$4,730.00		\$0	Clearing and grubbing of light vegetation growth e.g. regrowth
	Topsoil stripping	Y		m3	\$4.86		\$0	Stripping or topsoil at an approximate depth of 0.2 m into stockpiles; load and haul to final rehabilitation location required or respreading where necessary.
	Growth media supplementation with manure	Y		ha	\$747.50		\$0	Addition of manure to improve soil quality.
	Utilise biotic soil media - organic topsoil alternative	Y		m2	\$2.50		\$0	Material that can be applied as an alternative to spreading topsoil prior to hydromulching.
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment) Subtotal							\$0	
Water Management	Clean water dams to be retained after decommissioning – make safe and minor earthworks	Y		allow	\$2,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) @ ~\$200 per hour and pasture grass.
	Large clean water dams (i.e. ≥ 2 ha) to be retained after mine closure – make safe and minor earthworks	Y		allow	\$10,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) + pasture grass.
	Remove sediments from the floor of the dam to enable it to be converted into clean water structure (Select Haul Distance from list)	Y		m3	Select from List		\$0	Select Haul Distance Here This item includes the volume of contaminated sediment requiring removal using an excavator, truck and dozer to clean out the dam.
Water Management Subtotal							\$0	
Maintenance of Rehabilitated Areas	Maintenance of areas that have been shaped and seeded and revegetation has been 'successful'	Y		ha	\$925		\$0	Rehabilitation maintenance might include re-seeding, watering, fertilising, minor re-shaping, erosion control, inspections/audits - does not include major repair works.
	Existing rehabilitation repair - minor	Y		ha	\$1,200		\$0	Areas requiring minor repair - rills, minor growth media replacement.
	Existing rehabilitation repair - moderate	Y		ha	\$1,700		\$0	Areas requiring moderate repair - rills, significant growth media replacement.
	Existing rehabilitation repair - major	Y		ha	\$2,500		\$0	Areas requiring major repair - rills, gullies, growth media replacement, some level of additional surface water management.
	Existing rehabilitation repair - total failure of landform	Y		ha	\$40,000		\$0	Areas that require extensive rehabilitation repair - re-design and re-construction of landform.
Maintenance of Rehabilitated Areas Subtotal							\$0	
Additional Items Subtotal							\$0	
Total Cost for Tailings & Rejects Domain							\$0	

Underground Operations

Domain 3b: Overburden & Waste

Total Cost for Overburden & Waste Domain

\$0

Additional Assumptions: Record any relevant assumptions to this domain below:

		Key Rehabilitation Area Data for Domain	Enter data below manually
		Total Landform Establishment:	
		Total Growth Media Development:	
		Total Ecosystem Establishment:	

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Contaminated Materials	Treatment of known Acid Sulfate Soils	Y		ha	\$2,580		\$0		Assumes ASS is treatable via neutralisation and does not require capping and isolation. Assumes 1% by weight lime addition and treatment to 100 mm depth only.
	Removal and disposal of plastic liner (i.e. dam, leach pad, sump etc.)	Y		m2	\$1		\$0		Provisional sum for cutting using ripping tyres and on-site disposal of the liner.
	Long haulage brine/salt for disposal (Select Haul Distance from list)	Y		tonne	Select from List			Select Haul Distance Here	Costs for haulage to location for authorised disposal.
	Brine disposal to landfill - fees only	Y		tonne	\$288		\$0		Rate for trackable liquid levy of \$78.20 per tonne and authorised disposal to landfill.
	Long haulage water (clean or contaminated) (Select Haul Distance from list)	Y		tonne	Select from List			Select Haul Distance Here	Assumes transport in a 20,000 L tanker. Add disposal costs to additional items where warranted.
Contaminated Materials Subtotal							\$0		
Roads and Tracks	Unsealed roads / vehicle park-up areas – minor works including deep rip and trim	Y		ha	\$1,040.00		\$0		Assumes ~6 m road width - 16H Grader.
	Unsealed roads / access tracks / vehicle park-up areas with windrows and/or small earthen bunds – minor earthworks and deep rip and trim	Y		ha	\$1,500		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - no seed
	Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip and seed (pasture grass)	Y		ha	\$3,700		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$4,485		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (pasture grass)	Y		ha	\$4,870		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$7,025		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Remove stabilised material (blue metal, aggregate etc.) from roadways and disposal on-site/locally (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here	This item includes the scraping and removal of the volume of stabilised material from the road, laydown or other surface using an excavator, dozer and grader to enable the establishment of rehabilitation.
Roads and Tracks Subtotal							\$0		
Earthworks / Structural Works (Landform Establishment)	Major bulk pushing to achieve grades nominated in the approval/permit – Select Push Length	Y		m3	Select from List			Select Push Length Here	Major bulk pushing to achieve grades nominated in the approval/permit
	Minor reshaping and pushing	Y		ha	\$3,900		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation).
	Fill dams, voids etc. - Source local material, cart and spread to cap or backfill, cap thickness determined by approval / permit (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here	This item includes the volume of material requiring backfill using an excavator and scraper to fill the void and enable the establishment of rehabilitation.
	Shotcrete application on cuttings and steep slopes	Y		m2	\$185.00		\$0		This rate is used to rehabilitate steep slopes of weathered rock, roadway cuttings, etc that cannot be cut back and stabilised.
	Trim, rock rake & deep rip (includes levelling / landscaping and rip in 1 direction)	Y		ha	\$1,130.00		\$0		Undertaken using D10 dozer and 16M grader.
	Structural works, banks, waterways - contour banks, drainage channels and other soil conservation measures	Y		ha	\$1,600		\$0		Combination of dozer and excavator work plus grader for ~4 hours each per ha.
Construction of spine drains / drop structures and/or stabilising water course entry points - required for large catchments	Y		m2	\$27.00		\$0		Installation of on-site rock material (rip-rap) where managing water run-off from disturbed land and/or upon entry to water courses - prevents erosion of gully head (assumes competent material is locally available). If required to be sourced off site, assume an additional \$20/m2.	
Earthworks / Structural Works (Landform Establishment) Subtotal							\$0		

Mine Waste

<p>Ideal Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with little chemical reactivity (no to low risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and good physical properties (not significantly hydrophilic, shear strength does not limit equipment choice, no artificial strengthening required)</p>	<p>Y</p>	<p>ha</p>	<p>\$82,000</p>	<p></p>	<p>\$0</p>	<p>This includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume material with the appropriate chemical and physical properties. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness of approximately 0.5 m to 1 m and 0.15 m - 0.2 m growth media (assume at least 1 m thick cover required for carbonaceous material covers). Water quality from runoff, seepage etc. meets site-specific environment water quality values. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in addition to any long haulage volume in 8.05.</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>
<p>Efficient Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with moderate chemical reactivity (low to medium risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and moderate physical properties (not significantly hydrophilic, shear strength limits equipment choice somewhat, no artificial strengthening required)</p>	<p>Y</p>	<p>ha</p>	<p>\$146,500</p>	<p></p>	<p>\$0</p>	<p>This item includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume of material to cap / cover facilities where the tailings or rejects base is at a strength that enables economically efficient construction methods with small plant. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness ranging from >1 m to 2 m thickness constructed in 1 m layers + growth media up to 0.2 m depth. This may require additional materials (such as capillary breaks, geofabric, etc.) - use alternate rate cells below, specific material types (e.g. acid neutralising / consuming materials, competent rock etc.), and associated activities (i.e., load / haul / place / crush / screen / borrow etc.). Costs for haulage of specialised/additional materials must be added separately if required. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>

	Hydromulch - base grade or standard for flat areas that can be irrigated by water cart	Y		m2	\$0.80		\$0	Assumes use on flat areas with a gradient of less than 4:1, and where irrigation from water cart may be possible. Industry standard application rate of 2500kg/ha. Product will last short term (less than 3 months) and vegetation is required to grow ASAP for stability. This cost includes cover crop only, additional seeding required.
	Hydromulch - bonded fibre matrix grade for steep areas to stabilise up to 12 months	Y		m2	\$1.80		\$0	Assumes use on steep areas where stabilisation is required for up to 12 months. Application rate of ~3500kg/ha. This cost includes cover crop only, additional seeding required.
	Hydromulch - high performance flexible growth medium grade	Y		m2	\$2.50		\$0	Assumes use on extreme slopes where stabilisation is required for up to 18 months. Application rate of ~4,000kg/ha minimum. This cost includes cover crop only, additional seeding required.
	Single application of fertiliser (pasture)	Y		ha	\$420.00		\$0	Assumes 250 kg / ha. These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Single application of fertiliser (trees)	Y		ha	\$140.00		\$0	These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Spoil amelioration (adding lime / gypsum etc.)	Y		ha	\$1,000.00		\$0	Assumes 2.5 t / ha as an average application rate.
	growth media amelioration with biosolids	Y		ha	\$1.015		\$0	Recent experience with agronomy projects.
	Construct no-climb stock fence around rehabilitated areas	Y		m	\$22.00		\$0	Standard rate for no-climb stock fencing.
	Construct standard stock fence around rehabilitated areas	Y		m	\$13.00		\$0	Standard rate for standard stock fencing.
	Purchase and erect warning signs	Y		allow	\$250.00		\$0	Compliance with AS 1319-1994 - Safety signs for the occupational environment - installed every 25 m.
	Supply from external sources virgin excavated natural material (VENM) for growth media.	Y		m3	\$80.80		\$0	D7 to spread material at \$205/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$70/m3 for imported fill material.
	Supply from external sources a combination of virgin excavated natural material (VENM) and spoil from large excavation for filling voids and/or capping etc.	Y		m3	\$72.50		\$0	D10 push into void at \$270/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$60/m3 for imported fill material.
	Clearing and grubbing of trees and vegetation	Y		ha	\$4,730.00		\$0	Clearing and grubbing of light vegetation growth e.g. regrowth
	Topsoil stripping	Y		m3	\$4.86		\$0	Stripping or topsoil at an approximate depth of 0.2 m into stockpiles; load and haul to final rehabilitation location required or respreading where necessary.
	Growth media supplementation with manure	Y		ha	\$747.50		\$0	Addition of manure to improve soil quality.
	Utilise biotic soil media - organic topsoil alternative	Y		m2	\$2.50		\$0	Material that can be applied as an alternative to spreading topsoil prior to hydromulching.
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment) Subtotal							\$0	
Water Management	Clean water dams to be retained after decommissioning – make safe and minor earthworks	Y		allow	\$2,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) @ ~\$200 per hour and pasture grass.
	Large clean water dams (i.e. ≥ 2 ha) to be retained after mine closure – make safe and minor earthworks	Y		allow	\$10,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) + pasture grass.
	Remove sediments from the floor of the dam to enable it to be converted into clean water structure (Select Haul Distance from list)	Y		m3	Select from List		\$0	This item includes the volume of contaminated sediment requiring removal using an excavator, truck and dozer to clean out the dam.
Water Management Subtotal							\$0	
Maintenance of Rehabilitated Areas	Maintenance of areas that have been shaped and seeded and revegetation has been 'successful'	Y		ha	\$925.00		\$0	Rehabilitation maintenance might include re-seeding, watering, fertilising, minor re-shaping, erosion control, inspections/audits - does not include major repair works.
	Existing rehabilitation repair - minor	Y		ha	\$1,200		\$0	Areas requiring minor repair - rills, minor growth media replacement.
	Existing rehabilitation repair - moderate	Y		ha	\$1,700		\$0	Areas requiring moderate repair - rills, significant growth media replacement.
	Existing rehabilitation repair - major	Y		ha	\$2,500		\$0	Areas requiring major repair - rills, gullies, growth media replacement, some level of additional surface water management.
	Existing rehabilitation repair - total failure of landform	Y		ha	\$40,000		\$0	Areas that require extensive rehabilitation repair - re-design and re-construction of landform.
Maintenance of Rehabilitated Areas Subtotal							\$0	
Additional Items Subtotal							\$0	
Total Cost for Overburden & Waste Domain							\$0	

Underground Operations

Domain 4b: Subsidence and Management

Total Cost for Subsidence and Management Activities

\$0

Additional Assumptions: Record any relevant assumptions to this domain below:

		Key Rehabilitation Area Data for Domain	
		Total Landform Establishment:	Enter data below manually
		Total Growth Media Development:	
		Total Ecosystem Establishment:	

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Subsidence Repairs	Minor stabilisation works and maintenance of mine subsidence areas - ripping etc.	Y		ha	\$1,470		\$0		Undertaken using Dozer. Costs subject to the extent of subsidence impacts
	Crack filling to repair subsidence impacts	Y		m	\$1,450		\$0		Undertake more substantial works to backfill cracks and/or sink holes (e.g., filling with mulch prior to grouting, grouting, etc.) Costs subject to the extent of subsidence impacts. Include >5 km haul of fill.
	Water course restoration to repair subsidence impacts	Y		allow	Use alternate rate cell		\$0		Undertake more substantial works to remediate water courses (e.g., channel bed repairs, rock bar repairs, swamp stabilisation etc.)
	Create cut-through to re-establish natural water courses/drainage channels following subsidence	Y		allow	\$3,000		\$0		Includes all earthworks and revegetation required to re-establish the natural drainage profile of the subsided area.
Subsidence Repairs Subtotal							\$0		
Vents, Shafts and Boreholes	Maintenance and monitoring of sealed adits/portals and shafts (for a total of 5 years)	Y		allow	\$25,000		\$0		Assume 1 x day visual inspection (10hrs inc 'travel) for suitably qualified / competent person + reporting, for an annual inspection @ \$5,000 per year. Exclusions are intrusive investigation and testing (e.g. concrete strength etc).
Vents, Shafts and Boreholes Subtotal							\$0		
Water Management	On-site treatment of contaminated water due to high salt (includes removal of metals etc, brine disposal and cost of mobile water treatment unit)	Y		ML	\$3,600		\$0		Rate can fluctuate depending on treatment type however this is a suitable standard rate for current programs at mining operations.
	On-site treatment of contaminated water due to low pH (includes removal of metals etc, neutralisation treatments and cost of mobile water treatment unit)	Y		ML	\$1,500		\$0		Rate can fluctuate depending on treatment type however this is a suitable standard rate for current programs at mining operations.
Water Management Subtotal							\$0		
Creek Diversions	Repairs and/or stabilisation of new or compromised water course diversion	Y		m	\$2,500		\$0		Assumes material is suitable for revegetating and has a reasonable chance of stabilising.
	Long term maintenance of water course diversion - Channel constructed through backfilled material	Y		m	\$1,500		\$0		Assumes maintenance has been kept up and significant works are not required.
	Long term maintenance of water course diversion - Channel constructed through competent material	Y		m	\$750.00		\$0		Assumes maintenance has been kept up and significant works are not required.
	Installation of rock armouring	Y		m2	\$6.00		\$0		Assumes competent material is locally available - multiply costs by 2 for sourcing and transporting from offsite location.
Creek Diversions Subtotal							\$0		
Land Management	Pest management on buffer lands, non-disturbed, and rehabilitated areas	Y		ha	\$150.00		\$0		Feral animal baiting programs if required and waste materials required to be removed.
	Land management of undisturbed areas (rehabilitation, weeds, ferals, erosion and sediment control works)	Y		ha	\$400.00		\$0		Undisturbed areas within the lease boundary that require land management activities.
Land Management Subtotal							\$0		
Heritage Items	The restoration and care and maintenance of items that have heritage significance	Y		allow	Use alternate rate cell		\$0		Item for the redistribution of Aboriginal artefacts, preservation of European heritage items or a combination of activities.
Heritage Items Subtotal							\$0		
Sundry Items	Development of an 'Unplanned' Project Closure Plan - State Significant Development with closure planning well progressed i.e. preferred cover design, closure environment modelled e.g. groundwater /subsidence / pit lakes, preliminary seal designs, etc. and only finalisation of detailed engineering designs required	Y		allow	\$100,000		\$0		Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities. Assumes outcomes of studies readily available including modelling, landform design, geochemistry, demolition, etc. Costs to finalise options by domain and finalise designs for construction. Assume a simple site e.g. single open cut, no legacy operations historic in the area, little social dependence, etc. Depending on site size, complexity, final land use requirements and knowledge base investigations can range from ~\$75k to >\$1 M. Sites with more than 1 pit to add \$50,000 to rate.

Development of an 'Unplanned' Project Closure Plan - Non State Significant Development with at least ≥2 of the following aspects requiring closure planning, but no significant issues realised at this time: previous subsidence, medium or higher geochemistry risk and/or spontaneous combustion propensity, known/ likely contamination, tailings / rejects, final void	Y		allow	\$90,000		\$0	Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities. Estimated cost for developing closure plan including studies - basic to satisfy risks and decisions includes risk assessment, options analysis, Closure Plan. Sites with more than 1 pit to add \$50,000 to rate.
Development of an 'Unplanned' Project Closure Plan - Non State Significant Development with no EPL and/or only one of the following relevant aspects: previous subsidence, low to medium geochemistry risk and/or spontaneous combustion propensity, known limited contamination, small approved final void	Y		allow	\$15,000		\$0	Assumes sediment control is the key concern for rehabilitation e.g. small mines, exploration operations. Includes risk assessment, sampling and analyses on <5 samples, one study and Closure Plan.
Development of an 'Unplanned' Project Closure Plan - State Significant Development with only preliminary to conceptual closure planning in place	Y		allow	\$300,000		\$0	Includes costs for key investigations and studies including designs e.g. geochemistry, Contamination Remediation Action Plan, subsidence risk, cover/capping and final landform, site wide surface water, etc. Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities. Assume at least 15 types of studies required ranging from geotechnical to ecology and social, development of a closure plan including address of obligations. Assume a simple site e.g. single open cut, no legacy operations historic in the area, little social dependence, etc. Depending on site size, complexity, final land use requirements and knowledge base investigations can range to >\$3 M. Sites with more than 1 pit to add \$50,000 to rate.
Development of an 'Unplanned' Project Closure Plan - Non State Significant Development with at least ≥2 of the following aspects resulting in significant issues requiring remediation: previous subsidence, medium or higher geochemistry risk and/or spontaneous combustion propensity, known/ likely contamination, tailings / rejects, final void	Y		allow	\$125,000		\$0	Includes costs for key investigations and studies including economic treatments and designs e.g. geochemistry, Contamination Remediation Action Plan, subsidence risk, cover/capping and final landform, site wide surface water, etc. Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities.
Develop a Review of Environmental Factors (REF) to facilitate rehabilitation including contamination works.	Y		allow	\$27,950		\$0	Based on experience for a REF after completion of a detailed closure study (e.g. contamination investigation) costs could range from \$10,000 to \$100,000 ex GST. Note this does not apply to a Statement of Environmental Effects or Environmental Impact Statement.
Site security during closure	Y		yr.	\$75,000		\$0	Provisional sum for site security measures required during closure. This includes nightly patrols and first response in the event of an out of hours incident.
Choose type of HAZMAT Clean-up required - cleaning and decontaminating plant and equipment, chemical storage locations, oil and grease traps, tanks, vessels, and pipe work etc	Y		allow	\$0		\$0	Select type of HAZMAT Clean-up Required Type of HAZMAT Clean-up required - cleaning and decontaminating plant and equipment, chemical storage locations, oil and grease traps, tanks, vessels, and pipe work etc
Removal and disposal of radiation devices	Y		each	\$31,630		\$0	Provisional sum for removal and disposal of monitoring devices on conveyors using a radiation source (i.e., Americium - 241, Plutonium - 238, Caesium - 137 etc). Source Isotope type, quantity, strength, weight, source holder type, source holder weight, pick-up location (among others) will directly affect pricing.
Additional fees for accessing State, Crown or other public lands for rehabilitation/remediation activities	Y		allow	Use alternate rate cell		\$0	Provisional sum.
Sundry Items Subtotal						\$0	
Mobilisation and Demobilisation							
Mobilisation & Demobilisation for small mine or quarry - small fleet	Y		Item	\$12,000		\$0	May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.
Mobilisation & Demobilisation for small mine or quarry - medium to large fleet	Y		Item	\$35,000		\$0	May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.
Mobilisation & Demobilisation (Distance to site <150 km)	Y		item	\$100,000		\$0	May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.

	Mobilisation & Demobilisation (Distance to site >150 km but <500 km)	Y		item	\$150,000		\$0		May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.	
	Mobilisation & Demobilisation (Distance to site >500 km but <1000 km)	Y		item	\$300,000		\$0		May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.	
	Mobilisation & Demobilisation (Distance to site >1000 km)	Y		item	\$500,000		\$0		May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.	
Mobilisation and Demobilisation Subtotal							\$0			
Additional Items	Other 1 <insert>	N			This is				This item includes <<to be added by the operator>>	
	Other 2 <insert>	N			deliberately				This item includes <<to be added by the operator>>	
	Other 3 <insert>	N			left blank				This item includes <<to be added by the operator>>	
Additional Items Subtotal							\$0			
Total Cost for Subsidence and Management Activities							\$0			

Underground Operations

Domain 1c: Infrastructure

Total Cost for Infrastructure Domain

\$0

Additional Assumptions: Record any relevant assumptions to this domain below:

Key Rehabilitation Area Data for Domain		Enter data below manually
Total Landform Establishment:		
Total Growth Media Development:		
Total Ecosystem Establishment:		

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Termination of Services and Demolition Works	Disconnect and terminate all services (Water, electricity, gas etc at point of attachment to site)	Y		allow	\$35,000		\$0		For disconnection of all services, at building boundaries, physical cut at the point of attachment or distribution location. If infrastructure is not consolidated (i.e., administration, camp and workshops are in separate places), consider multiple disconnection fees.
	Disconnect and terminate services at remote areas (i.e. pump stations, remote workshops, sewage treatment plant etc.)	Y		allow	\$5,850		\$0		Used for infrastructure remote from primary connection. Can also be used for small mines / quarries that do not have dedicated supplies from supply authorities such as steel lattice power lines.
	Removal of low/medium voltage powerlines including disconnection, rolling up the wires and removing the poles - does not include the removal of substations	Y		km	\$15,000		\$0		Applies to power lines on stobie, concrete or similar poles.
	Removal of power lines on tower or lattice structures (this includes disconnection, rolling up the wires and removing the structures) - does not include the removal of substations	Y		km	\$100,000		\$0		Applies to power lines on steel tower and steel lattice structures assuming 3 towers / km.
	Remove small rail, road, water course overpass - manage potential interruptions and demolish and remove bridge supports/pylons/bridge structure etc. and dispose of waste material on-site/locally	Y		Item	\$350,000		\$0		Smaller structures - minimal civil works to demolish (constructed for the purposes of mining related works - does not include transport to regional disposal facility or equivalent).
	Remove medium rail, road, water course overpass - manage potential interruptions and demolish and remove bridge supports/pylons/bridge structure etc. and dispose of waste material on-site/locally	Y		Item	\$500,000		\$0		Medium structures - minimal civil works to demolish (constructed for the purposes of mining related works - does not include transport to regional disposal facility or equivalent).
	Remove large / significant rail, road, water course overpass - manage potential interruptions and demolish and remove bridge supports/pylons/bridge structure etc. and dispose of waste material on-site/locally	Y		Item	\$1,300,000		\$0		Large structures - includes significant water management e.g. watercourse diversion and civil works to demolish (constructed for the purposes of mining related works - does not include transport to regional disposal facility or equivalent).
	Demolish and/or remove substations (assumes they are in a closed building). Dispose of waste material on-site/locally	Y		m2	\$100.00		\$0		Simple structure to demolish mechanically (no labour required), assumes single story building with no asbestos and segregation of contents for scrap as applicable.
	Demolish and remove switchyard. Dispose of waste material on-site/locally	Y		m2	\$75.00		\$0		Includes demolition and removal of all switchgear and transformers etc. and segregation of contents for scrap as applicable.
	Demolish and remove demountable structures on concrete stumps. Assumes not being re-used	Y		m2	\$40.00		\$0		Crib huts, temporary offices and other 'non permanent' structures. Does not include transport to regional disposal facility or equivalent.
	Demolish and remove small buildings/tanks (admin buildings, single story accommodation etc) and disposal on-site/locally	Y		m2	\$61.00		\$0		Simple structure to demolish, assumes no greater than 2 stories high. Does not include transport to regional disposal facility or equivalent.
	Demolish and remove light industrial buildings and disposal on-site/locally	Y		m2/floor	\$90.00		\$0		Needs to be calculated per floor/level (Assume 1 floor/level = 3.4 m) - does not include transport to regional disposal facility or equivalent. Assumes asbestos free and mechanically demolished.
	Demolish and remove industrial buildings (workshops tyre change and servicing area etc not CHPP/process plant) and disposal on-site/locally	Y		m2/floor	\$130.00		\$0		Needs to be calculated per floor/level (Assume 1 floor/level = 3.4 m). Does not include transport to regional disposal facility or equivalent.
	Demolish and remove CHPP/process plant (include the area of each floor of the structure) and disposal on-site/locally	Y		m2/floor	\$225.00		\$0		Needs to be calculated per floor/level (Assume 1 floor/level = 3.4 m). Does not include transport to regional disposal facility or equivalent.
	Collapse, demolish and remove washery, crushers, hoppers, mills, furnaces, agglomeration, electrowinning, floatation, sizing stations, rotary breakers, etc (include the area of each floor of the structure) and disposal on-site/locally	Y		m2/floor	\$225.00		\$0		Needs to be calculated per floor/level (Assume 1 floor/level = 3.4 m). Does not include transport to regional disposal facility or equivalent.
	Collapse, demolish and remove stacker OR reclaim (radial or luffing etc. with maneuverability for stockpile control) and disposal on-site/locally	Y		allow	\$750,000		\$0		Cost for removal of stacker or reclaim unit only. Does not include terminate services, remove rails and ballast etc. Does not include transport to regional disposal facility or equivalent.
Collapse, demolish and remove bucket wheel stacker/reclaimer and disposal on-site/locally	Y		allow	\$2,000,000		\$0		Cost for just removal of the bucket wheel stacker/reclaim units. Does not include terminate services, remove rails and ballast etc. Does not include transport to regional disposal facility or equivalent.	

Remove stacker/reclaimer rails and ballast and demolish and remove concrete footings etc and disposal on-site/locally	Y		m	\$75.00		\$0	Includes both rails, does not include the conveyor system. Does not include transport to regional disposal facility or equivalent.
Collapse, Cut and Remove 5000T coal silo and disposal on-site/locally	Y		allow	\$92,500		\$0	Collapse structure and remove. Does not include transport to regional disposal facility or equivalent.
Collapse, Cut and Remove 3000 T coal silo and disposal on-site/locally	Y		allow	\$77,500		\$0	Collapse structure and remove. Does not include transport to regional disposal facility or equivalent.
Collapse, Cut and Remove 1250 T coal silo and disposal on-site/locally	Y		allow	\$62,500		\$0	Collapse structure and remove. Does not include transport to regional disposal facility or equivalent.
Collapse, Cut and Remove rail loading bins and disposal on-site/locally	Y		allow	\$65,000		\$0	Collapse structure and remove. Does not include transport to regional disposal facility or equivalent.
Demolish and Remove large concrete rail loading bin - and disposal on-site/locally	Y		allow	\$460,000		\$0	Collapse structure and remove. Does not include transport to regional disposal facility or equivalent.
Demolish and remove onground conveyors, transfer stations & gantries (scrap only – does not include dismantling for reuse at another site) and disposal on-site/locally	Y		m	\$185.00		\$0	Estimate for on-ground conveyor including anything up to 10 m off the ground. Does not include transport to regional disposal facility or equivalent.
Demolish and remove elevated conveyors, transfer stations & gantries (scrap only, does not include dismantling for reuse at another site) and disposal on-site/locally	Y		m	\$295.00		\$0	Estimate for elevated conveyor up to -10 m off the ground. Does not include transport to regional disposal facility or equivalent.
Demolish and remove overhead conveyors, transfer stations & gantries (scrap only, does not include dismantling for reuse at another site) and disposal on-site/locally. This may include small scale fixed material stacking infrastructure	Y		m	\$850		\$0	Estimate for overhead conveyor including conveyors that are >10 m off the ground that require a crane to remove. Does not include transport to regional disposal facility or equivalent.
Remove and demolish conveyor from reclaim tunnel (Does not include excavation and demolition of reclaim tunnel roof)	Y		m	\$150.00		\$0	Due to no canopy or infrastructure attached.
Demolition of reclaim tunnel concrete (Assumes complete removal and dumping in mine pit void)	Y		m	\$950.00		\$0	Assumes this area will be used for another land-use that requires the structure to be dug up and re-buried somewhere else.
Demolition and removal of vent raise fans, electrical substation and winch and disposal on-site/locally	Y		allow	\$25,000		\$0	Does not include filling and capping the shaft. Does not include transport to regional disposal facility or equivalent.
Demolish and remove small tank clean (Thickener etc 3 - 9 m diameter) and disposal on-site/locally	Y		allow	\$10,000		\$0	Assume tank is clean - contents removed. If tank is full allow extra 30% for excavator and 2 men to dig out and dispose. Does not include transport to regional disposal facility or equivalent.
Demolish and remove medium tank clean (Thickener etc 10 - 15 m diameter) and disposal on-site/locally	Y		allow	\$30,000		\$0	Assume tank is clean - contents removed. If tank is full allow extra 30% for excavator and 2 men to dig out and dispose. Does not include transport to regional disposal facility or equivalent.
Demolish and remove large tank clean (Thickener etc 15 - 30 m diameter) and disposal on-site/locally	Y		allow	\$45,000		\$0	Assume tank is clean - contents removed. If tank is full allow extra 30% for excavator and 2 men to dig out and dispose. Does not include transport to regional disposal facility or equivalent.
Demolish and remove extra large tank clean (Thickener etc >30 m diameter) and disposal on-site/locally	Y		allow	\$100,000		\$0	Assume tank is clean - contents removed. If tank is full allow extra 30% for excavator and 2 men to dig out and dispose. Does not include transport to regional disposal facility or equivalent.
Demolish and remove tank clean (Thickener etc) >50 m diameter and disposal on-site/locally	Y		allow	\$100,000		\$0	Estimate only - may require a detailed assessment from demolition expert due to specialised equipment required for removal. Does not include transport to regional disposal facility or equivalent.
Removal of UG tank <5000 L - including pipes, bunds etc. and disposal on-site/locally	Y		allow	\$21,000		\$0	Assume tank is clean (contents removed), does not include transport to regional disposal facility or equivalent.
Removal of UG tank 5000 L - 15000 L - including pipes, bunds etc. and disposal on-site/locally	Y		allow	\$30,000.00		\$0	Assume tank is clean (contents removed), does not include transport to regional disposal facility or equivalent.
Remove small underground pipe and disposal on-site/locally	Y		m	\$25.00		\$0	For example: 300 mm pipes - 0.5 m deep, does not include transport to regional disposal facility or equivalent.
Remove medium underground pipe and disposal on-site/locally	Y		m	\$60.00		\$0	For example: 500 mm pipes - 1 m deep, does not include transport to regional disposal facility or equivalent.
Remove large underground pipe and disposal on-site/locally	Y		m	\$165.00		\$0	For example: 1 m pipes - 2 m deep.
Remove above ground pipe (supported) and disposal on-site/locally	Y		m	\$12.00		\$0	~300 mm pipes and assumes pipes are in close proximity to infrastructure areas. Does not include transport to regional disposal facility or equivalent.
Remove surface pipelines (unsupported) and disposal on-site/locally	Y		m	\$15		\$0	~300 mm pipes and assumes pipes are used for water transfer between pits (or similar) and remotely located. Does not include transport to regional disposal facility or equivalent.

Remove pump and pontoon from small lake or dam including pipes and electrical supply or diesel tanks	Y		allow	\$20,000.00		\$0	Includes equipment for retrieval - boats, etc. and labour. Does not include transport to regional disposal facility or equivalent.
Remove bitumen (car park and access roads) and dispose on-site/locally	Y		m2	\$10.00		\$0	Scalp bitumen and stabilised material. Generally haulage rates will be \$0.60 - \$1.20 / km, depending on truck fleet, loaders etc. For off-site disposal use alternate rate option and add \$0.90 / km for transport.
Remove bitumen (airstrip) and dispose on-site/locally	Y		m2	\$20.00		\$0	Scalp bitumen and stabilised material. Generally haulage rates will be \$0.60 - \$1.20 / km, depending on truck fleet, loaders etc. For off-site disposal use alternate rate option and add \$0.90 / km for transport.
Remove concrete pads & footings (<300 mm thickness) and disposal on-site/locally	Y		m2	\$36.00		\$0	Breaking up slab and disposal or for conversion to aggregate. Generally haulage rates will be \$0.60 - \$1.20 / km, depending on truck fleet, loaders etc. For off-site disposal use alternate rate option and add \$0.90 / km for transport.
Remove concrete pads & footings (>300 mm thickness) and disposal on-site/locally	Y		m2	\$75.00		\$0	Breaking up slab and disposal or for conversion to aggregate. Generally haulage rates will be \$0.60 - \$1.20 / km, depending on truck fleet, loaders etc. For off-site disposal use alternate rate option and add \$0.90 / km for transport.
Crush concrete to make road aggregate - 75 mm	Y		tonne	\$10.00		\$0	Does not include haulage of materials - assumes crushing plant is readily available.
Crush concrete to make road aggregate - 50 mm	Y		tonne	\$13.00		\$0	Does not include haulage of materials - assumes crushing plant is readily available.
Crush concrete to make road aggregate - 30 mm	Y		tonne	\$15.00		\$0	Does not include haulage of materials - assumes crushing plant is readily available.
Remove fence (cyclone/wire fence) and disposal on-site/locally	Y		m	\$20.00		\$0	Roll up fence and remove posts.
Removal of small plastic tanks	Y		each	\$1,000.00		\$0	Remove small poly tanks used for water storage, etc.
Demolish and remove galvanised/corrugated light weight tanks	Y		each	\$500.00		\$0	Demolish and remove small lightweight metal tanks. No costs included for managing liquids, etc.
Demolish and remove communication towers	Y		each	\$5,000.00		\$0	Cost includes demolition and removal of tower only; separate costs required for disconnection of services, demolition of footings, etc.
Removal of UG services (power within main gate areas, etc.)	Y		allow	\$50,000.00		\$0	Assume service disconnection at the mine boundary is at surface level. This cost covers all fees and charges
Waste disposal to Council landfill (general waste) - haulage >10 km but <15 km	Y		tonne	\$7.00		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill (general waste) - haulage >15 km but <25 km	Y		tonne	\$9.00		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill (general waste) - haulage >25 km but <50 km	Y		tonne	\$12.50		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill (industrial demolition / concrete / scrap metal) - haulage >10 km but <15 km	Y		tonne	\$32.00		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill (industrial demolition / concrete / scrap metal) - haulage >15 km but <25 km	Y		tonne	\$36.00		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill (industrial demolition / concrete / scrap metal) - haulage >25 km but <50 km	Y		allow	Use alternate rate call		\$0	Rate accounts for round trip haulage to Council landfill but excludes landfill fees. Input quantity against Waste disposal to Council landfill - fees for relevant waste type.
Waste disposal to Council landfill - fees (general waste)	Y		tonne	\$193.00		\$0	Fee for waste disposal of general waste to local Council landfill; transport rates separate. Please note that this is not applicable to operations with approval for building and demolition waste disposal on site.
Waste disposal to Council landfill - fees (industrial demolition / concrete / scrap metal)	Y		tonne	\$174.00		\$0	Fee for waste disposal of industrial demolition / concrete / scrap metal waste to local Council landfill; transport rates separate. Rate does not assume material is recyclable. Please note that this is not applicable to operations with approval for building and demolition waste disposal on site.
Termination of Services and Demolition Works Subtotal						\$0	

Rail Infrastructure									
	Remove rail loop and spur, ballast etc. and disposal on-site/locally	Y		m	\$60.00			\$0	Remove all materials to allow area to be reshaped and rehabilitated - does not include transport to regional disposal facility or equivalent.
	Remove train loading facilities and disposal on-site/locally	Y		m2	\$185.00			\$0	Remove rail load point infrastructure including gantries and control structures. Does not include transport to regional disposal facility or equivalent.
	Reshape rail spur and load out areas. Does not include growth media and revegetation	Y		ha	\$2,860			\$0	D10 Dozer and 16 H Grader (50% utilisation).
					Rail Infrastructure Subtotal			\$0	
Contaminated Materials									
	Undertake a preliminary site investigation (Phase 1). This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple studies may be required.	Y		Cluster	\$15,000			\$0	The preliminary investigation would include at minimum a desktop assessment of the area and site history, incidents, etc. as per the National Environmental Protection (NEPM) Phase 1 assessment (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. A cluster may include: - Mine infrastructure (i.e., fuel / chemical store, workshop, vehicle wash-down, sewage treatment etc.) - Processing plants (i.e., ore and product storage, mine waste storage and disposal, rail load-out etc.) - Remote pit-top facilities (i.e., vehicle re-fuel, sewage treatment, secondary workshop, chemical storage etc.)
	Undertake an intrusive site investigation on sites with small footprints to investigate e.g. ≤15 ha. This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple intrusive investigations should be included.	Y		Cluster	\$44,000			\$0	The intrusive investigation would include at minimum a site walkover and field sampling as per the National Environmental Protection (NEPM) Phase 2 intrusive investigation (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. Note: An intrusive investigation is not required for all contaminated areas and should be applied considering the rehabilitation program, site history, location, etc. A cluster area where it is highly anticipated that contamination has occurred (i.e., underground tanks / pipes that are known to have leaked, chemical stores with earthen bunds, around ineffective oil/water separators etc.) and further field work is required involving intrusive investigation. Assumes site is easily accessible and a small area e.g. ~10-15 ha requires investigation and testing (test pits, boreholes, etc.) based on Sampling and Analysis Quality Plan. Includes SAQP, fieldwork, sampling and analysis.
	Undertake an intrusive site investigation on sites with large footprints to investigate e.g. >15 ha. This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple intrusive investigations should be included.	Y		Cluster	\$106,000			\$0	The intrusive investigation would include at minimum a site walkover and field sampling as per the National Environmental Protection (NEPM) Phase 2 intrusive investigation (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. Note: An intrusive investigation is not required for all contaminated areas and should be applied considering the rehabilitation program, site history, location, etc. A cluster area where it is highly anticipated that contamination has occurred (i.e., underground tanks / pipes that are known to have leaked, chemical stores with earthen bunds, around ineffective oil/water separators etc.) and further field work is required involving intrusive investigation. Assume site has a history of contamination and/or a large area >15 ha requires investigation and testing (test pits, boreholes, etc.) based on Sampling and Analysis Quality Plan. Includes SAQP, fieldwork, sampling and analysis.
	Develop a Remediation Action Plan on sites with small footprints based on outcomes of intrusive investigation including strategies to address contamination exceedances	Y		allow	\$35,000			\$0	Develop remediation plan for approval including designs and detailed costs. Costs may increase if detailed designs required for construction.
	Develop a Remediation Action Plan on sites with large footprints based on outcomes of intrusive investigation including strategies to address contamination exceedances	Y		allow	Use alternate rate cell			\$0	Assumes complex site; detailed design drawings required for cover.
	Removal and disposal of contaminated water from tanks, bunded areas and sumps	Y		L	\$0.35			\$0	Cost for recent sump clean-up from resource activity - requires specialists to treat.

Remove material (carbonaceous / metalliferous spillage or otherwise) from footprint of the process facility (leach pads) / stockpile area (ROM product) / roads and dump in a void on-site (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here	This item includes scraping and removal of the volume of carbonaceous material using dozer, grader etc. to make safe an area and enable the establishment of rehabilitation.
Load, cart and dispose of Hazardous classified contaminated material off site to a licensed landfill. Assumes cartage to a licensed landfill.	Y		m3	\$800.00		\$0		Includes load, haul and dump fees to a licensed facility.
Load, cart and disposal of Restricted classified contaminated material off site to a licensed landfill. Add \$50/m3 for cartage from regional areas	Y		m4	\$660.00		\$0		Includes load, haul and dump fees to a licensed facility.
Load, cart and disposal of Low Level contaminated material off site to a licensed landfill. Add \$50/m3 for cartage to regional landfill	Y		m3	\$220.00		\$0		Includes load, haul and dump fees to a licensed facility.
Onsite remediation of hydrocarbon contaminated soils manual land farming (Select Volume from List)	Y		m3	Select from List			Select Volume Here	Spreading of contaminated soils on a prepared surface and stimulation of aerobic microbial activity within the soils through aeration and/or the addition of minerals, nutrients and moisture to promote the aerobic degradation of organic chemicals - time frame of up to 24 months.
Mobilisation of cement stabilisation plant and equipment for hydrocarbon (i.e., PAH, long chain hydrocarbons, etc.) contaminated soil treatment	Y		Item	\$150,000		\$0		Required if treatment of hydrocarbon contamination is required to be fast tracked.
On-site remediation of hydrocarbon contaminated soils - using a mobile treatment unit	Y		m3	\$165.00		\$0		Additional cost as the treatment process is fast tracked.
Remove and dispose of asbestos (<750 m2)	Y		m2	\$50.00		\$0		Where an assessment/estimation has been made to confirm the volume of asbestos to be removed.
Remove and dispose of asbestos (>750 m2)	Y		m2	\$40.00		\$0		Where an assessment/estimation has been made to confirm the volume of asbestos to be removed.
Waste disposal to Council landfill - fees (asbestos)	Y		tonne	\$290		\$0		Landfill fees to regional landfill.
Treatment of known Acid Sulfate Soils	Y		ha	\$2,580		\$0		Assumes ASS is treatable via neutralisation and does not require capping and isolation. Assumes 1% by weight lime addition and treatment to 100 mm depth only.
Removal and disposal of plastic liner (i.e. dam, leach pad, sump etc.)	Y		m2	\$1		\$0		Provisional sum for cutting using ripping tynes and on-site disposal of the liner.
Long haulage brine/salt for disposal (Select Haul Distance from list)	Y	2	tonne	Select from List			Select Haul Distance Here	Costs for haulage to location for authorised disposal.
Brine disposal to landfill - fees only	Y		tonne	\$288		\$0		Rate for trackable liquid levy of \$78.20 per tonne and authorised disposal to landfill.
Long haulage water (clean or contaminated) (Select Haul Distance from list)	Y		tonne	Select from List			Select Haul Distance Here	Assumes transport in a 20,000 L tanker. Add disposal costs to additional items where warranted.
Contaminated Materials Subtotal						\$0		
Vents, Shafts and Boreholes								
Seal portals / drifts (width >3 m) – only entry seal / plug required with in front of access backfill with engineered fill for 5 m	Y		allow	\$126,000		\$0		This cost is not applicable to coal operations which require backfilling to MDG6001 or similar due to gases. Costs include engineering and QA/QC. Costs assume engineered fill backfilled between 2 x 1 m plugs for sealing, + haul material to backfill per >5 km distance + concrete pump and secondary support.
Seal portals / drifts (width >3 m) accessible to men and machinery requiring a bulkhead – grout backfill against a concrete bulkhead to be constructed	Y		allow	\$250,000		\$0		Cost includes engineering the bulkhead and underground construction (access available) followed by grout backfill via workings and rehabilitation (reshape, bulk push and full rehabilitation). Assume tunnel length of 20 m. For every additional m add \$7,250 for grouting. If no bulkhead required, deduct \$60,000.
Seal portals / drifts (width >3 m) not accessible by men or machinery – grout backfill against a concrete bulkhead existing or to be constructed	Y		allow	\$250,000		\$0		Cost includes engineering the bulkhead if required and construction via access directly above heading followed by grout backfill via boreholes every 10 m to fill voids and rehabilitation (bulk push, final trim, seeding and full rehabilitation). Assume tunnel length of 20 m. For every additional m add \$8,700 for grouting. If no bulkhead required, deduct \$60,000. Assumes any existing bulkhead is observable by camera and satisfies regulations and engineer (location, etc.).
Seal small adits (width ≤3 m) accessible by men and/or machinery or neither requiring a bulkhead –backfill with appropriate material against a concrete bulkhead existing or to be constructed. The rate includes reshaping and rehabilitation of the batter around the entrance of the adit	Y		allow	\$25,000		\$0		Costs estimated from executed works program in NSW from multiple sites. Rate assumes standard works program with suitable access, and additional roof and rib stabilisation works etc. is not required.
Costs to grout fill tunnel via mine workings to seal and eliminate voids and/or likelihood of failures of ground	Y		m	\$7,250		\$0		Workings are accessible to run grout lines via machine or seam dip is favourable i.e. dips inbye
Costs to grout fill tunnel by drilling directly above to seal and eliminate voids and/or likelihood of failures of ground	Y		m	\$8,700		\$0		Area directly above heading is accessible by drill rig with depth of cover <30 m and access outbye. One borehole required every 10m to fill void.

Demolish ventilation fans	Y		Item	\$30,000		\$0		Costs for demolition of ventilation fan prior to sealing shaft.
Seal and rehabilitate ventilation shafts on hard rock operations (no to low gas risk) or coal operations - allows for works in a remote location	Y		allow	\$150,000		\$0		Rate accounts for a range of factors including variations in depth and size, accessibility limitations, equipment transport to the shaft etc. Assumes engineered fill is available within 10 km round trip and no bulkhead required. Excludes demolition of ventilation fans.
Install gate or grill over the adit (Where site might be used by bats)	Y		Item	\$200,000		\$0		Rate accounts for a range of factors including establishing clear access, and/or working in remote locations without services, and/or stabilisation works to prevent the entry collapsing and compromising the gate etc.
Option 1 - Coal bore hole Exploration boreholes – rehabilitate coal boreholes and drill pads as required	Y		depth (m)	\$44.55		\$0		Cost to grout and cap an open exploration borehole. Assume a 20 m x 20 m drill pad requires rehabilitation - push cover of nearby growth media, rip and seed.
Option 3 - Mineral RAB and aircore drill holes Exploration boreholes – backfill open Rotary Airblast (RAB) or aircore drill holes with cuttings	Y		allow	\$42.50		\$0		May include cutting of casing, installation of a casing cap, and/or manually backfilling the hole with drill cuttings. Does not include reshaping / ripping the drill pad, amelioration / seeding etc.
Option 2 - Mineral drill hole requiring grouting Exploration boreholes – grout and cap open bore holes	Y		allow	\$5,700		\$0		Includes grouting and capping 100 - 200 m exploration boreholes to meet the requirements of Departmental Guidelines.
Boreholes – cap and seal open bore holes with steel casing (i.e., goaf drainage etc.)	Y		allow	\$6,960		\$0		Holes deeper than 100 m - includes cutting steel collar 6 m below surface, grouting and capping.
Boreholes – cap and seal open bore holes - surface-to-in-seam gas drainage	Y		allow	\$17,890		\$0		Surface-to-in-seam gas drainage boreholes.
Boreholes – cap and seal open bore holes - vertical gas drainage	Y		allow	\$16,000		\$0		Vertical gas drainage boreholes.
Boreholes – grout (with concrete) cap and seal bore holes (i.e. where sealing aquifers)	Y		allow	\$35,000		\$0		Includes multi skin sleeves to prevent aquifer mixing.
Boreholes – cap and seal service boreholes for UG coal operations	Y		allow	\$45,000		\$0		Includes large diameter boreholes used for supplying electricity (66kV), compressed air, water, solsenic etc.
Option 4 - Mineral diamond drill hole Rehabilitation of diamond drill holes and pad including sealing drill holes for mineral exploration	Y		Item	\$2,070		\$0		Bog out cuttings, remove fencing, remove rubbish, push sumps in, rehabilitate pads and tracks, cut and plug collars. Includes labour and equipment, disposal of rubbish locally on site
Option 5 - Mineral reverse circulation drill holes Rehabilitation of reverse circulation drill holes and pad including sealing drill holes for mineral exploration	Y		Item	\$1,340		\$0		Sealing required, but not complete filling with concrete/grout
Option 6 - Rehabilitation of drill hole collars Rehabilitation of drill hole collars (mineral exploration)	Y		each	\$415		\$0		Cut collar, remove, cap, backfill capped collar and cover with nearby organic or growth material
Vents, Shafts and Boreholes Subtotal						\$0		
Roads and Tracks								
Unsealed roads / vehicle park-up areas – minor works including deep rip and trim	Y		ha	\$1,040.00		\$0		Assumes ~6 m road width - 16H Grader.
Unsealed roads / access tracks / vehicle park-up areas with windrows and/or small earthen bunds – minor earthworks and deep rip and trim	Y		ha	\$1,500		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - no seed
Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip and seed (pasture grass)	Y		ha	\$3,700		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$4,485		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed

	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (pasture grass)	Y		ha	\$4,870		\$0	D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$7,025		\$0	D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Remove stabilised material (blue metal, aggregate etc.) from roadways and disposal on-site/locally (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here This item includes the scraping and removal of the volume of stabilised material from the road, laydown or other surface using an excavator, dozer and grader to enable the establishment of rehabilitation.
Roads and Tracks Subtotal							\$0	
Earthworks / Structural Works (Landform Establishment)	Major bulk pushing to achieve grades nominated in the approval/permit – Select Push Length	Y		m3	Select from List			Select Push Length Here Major bulk pushing to achieve grades nominated in the approval/permit
	Minor reshaping and pushing	Y		ha	\$3,900		\$0	D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation).
	Fill dams, voids etc. - Source local material, cart and spread to cap or backfill, cap thickness determined by approval / permit (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here This item includes the volume of material requiring backfill using an excavator and scraper to fill the void and enable the establishment of rehabilitation.
	Shotcrete application on cuttings and steep slopes	Y		m2	\$185.00		\$0	This rate is used to rehabilitate steep slopes of weathered rock, roadway cuttings, etc that cannot be cut back and stabilised.
	Trim, rock rake & deep rip (includes levelling / landscaping and rip in 1 direction)	Y		ha	\$1,130.00		\$0	Underlaken using D10 dozer and 16M grader.
	Deep rip hard stand / lay down areas	Y		ha	\$960.00		\$0	D10 deep ripping.
	Structural works, banks, waterways - contour banks, drainage channels and other soil conservation measures	Y		ha	\$1,600		\$0	Combination of dozer and excavator work plus grader for ~4 hours each per ha.
	Construction of spine drains / drop structures and/or stabilising water course entry points - required for large catchments	Y		m2	\$27.00		\$0	Installation of on-site rock material (rip-rap) where managing water run-off from disturbed land and/or upon entry to water courses - prevents erosion of gully head (assumes competent material is locally available). If required to be sourced off site, assume an additional \$20/m2.
Earthworks / Structural Works (Landform Establishment) Subtotal							\$0	
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment)	Source, cart and spread growth media (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here If topsoil is not available on-site, then Virgin Excavated Natural Material (VENM) may need to be externally sourced.
	Planting mature trees (>15 cm)	Y		allow	\$15.00		\$0	4 m centres.
	Planting tube stock (<15 cm)	Y		allow	\$6.60		\$0	4 m centres.
	Direct seeding / fertiliser (pasture grass species)	Y		ha	\$1,875		\$0	Includes treating, weighing, mixing with fertiliser + spreading by tractor or helicopter (aerial seeding).
	Direct seeding / fertiliser (tree or native grass species)	Y		ha	\$4,135		\$0	Includes treating, weighing, mixing with fertiliser + spreading by tractor or helicopter (aerial seeding).
	Hydro-seeding with straw mulching and bitumen tack with native seed	Y		m2	\$1.90		\$0	Process to be used on flat well prepared surfaces under irrigation e.g. sewage treatment irrigation areas. Ranges from \$0.15 - \$0.50 depending on size and input variables. Native seed +\$1.00
	Hydro-seeding with straw mulching and bitumen tack with pasture seed	Y		m2	\$0.43		\$0	Process to be used on flat well prepared surfaces under irrigation e.g. sewage treatment irrigation areas. Ranges from \$0.15 - \$0.50 depending on size and input variables. Pasture seed +\$0.10
	Hydromulch - base grade or standard for flat areas that can be irrigated by water cart	Y		m2	\$0.80		\$0	Assumes use on flat areas with a gradient of less than 4:1, and where irrigation from water cart may be possible. Industry standard application rate of 2500kg/ha. Product will last short term (less than 3 months) and vegetation is required to grow ASAP for stability. This cost includes cover crop only, additional seeding required.
	Hydromulch - bonded fibre matrix grade for steep areas to stabilise up to 12 months	Y		m2	\$1.80		\$0	Assumes use on steep areas where stabilisation is required for up to 12 months. Application rate of ~3500kg/ha. This cost includes cover crop only, additional seeding required.
	Hydromulch - high performance flexible growth medium grade	Y		m2	\$2.50		\$0	Assumes use on extreme slopes where stabilisation is required for up to 18 months. Application rate of ~4,000kg/ha minimum. This cost includes cover crop only, additional seeding required.
	Single application of fertiliser (pasture)	Y		ha	\$420.00		\$0	Assumes 250 kg / ha. These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Single application of fertiliser (trees)	Y		ha	\$140.00		\$0	These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Spoil amelioration (adding lime / gypsum etc.)	Y		ha	\$1,000.00		\$0	Assumes 2.5 t / ha as an average application rate.

growth media amelioration with biosolids	Y		ha	\$1,015		\$0	Recent experience with agronomy projects.
Construct no-climb stock fence around rehabilitated areas	Y		m	\$22.00		\$0	Standard rate for no-climb stock fencing.
Construct standard stock fence around rehabilitated areas	Y		m	\$13.00		\$0	Standard rate for standard stock fencing.
Purchase and erect warning signs	Y		allow	\$250.00		\$0	Compliance with AS 1319-1994 - Safety signs for the occupational environment - installed every 25 m.
Supply from external sources virgin excavated natural material (VENM) for growth media.	Y		m3	\$80.80		\$0	D7 to spread material at \$205/hr, Excavator (\$220/hr) load Artic Trucks (90c/km) from imported stockpile - allow nominal rate of \$70/m3 for imported fill material.
Supply from external sources a combination of virgin excavated natural material (VENM) and spoil from large excavation for filling voids and/or capping etc.	Y		m3	\$72.50		\$0	D10 push into void at \$270/hr, Excavator (\$220/hr) load Artic Trucks (90c/km) from imported stockpile - allow nominal rate of \$60/m3 for imported fill material.
Clearing and grubbing of trees and vegetation	Y		ha	\$4,730.00		\$0	Clearing and grubbing of light vegetation growth e.g. regrowth
Topsoil stripping	Y		m3	\$4.86		\$0	Stripping or topsoil at an approximate depth of 0.2 m into stockpiles; load and haul to final rehabilitation location required or respreading where necessary.
Growth media supplementation with manure	Y		ha	\$747.50		\$0	Addition of manure to improve soil quality.
Utilise biotic soil media - organic topsoil alternative	Y		m2	\$2.50		\$0	Material that can be applied as an alternative to spreading topsoil prior to hydromulching.
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment) Subtotal						\$0	
Water Management							
Clean water dams to be retained after decommissioning – make safe and minor earthworks	Y		allow	\$2,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) @ ~\$200 per hour and pasture grass.
Large clean water dams (i.e. ≥ 2 ha) to be retained after mine closure – make safe and minor earthworks	Y		allow	\$10,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) + pasture grass.
Remove sediments from the floor of the dam to enable it to be converted into clean water structure (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here This item includes the volume of contaminated sediment requiring removal using an excavator, truck and dozer to clean out the dam.
Removal of evaporation fans and/or other water transfer and management infrastructure	Y		allow	\$25,000		\$0	Provisional sum for removal of water management infrastructure.
Water Management Subtotal						\$0	
Maintenance of Rehabilitated Areas							
Maintenance of areas that have been shaped and seeded and revegetation has been 'successful'	Y		ha	\$925.00		\$0	Rehabilitation maintenance might include re-seeding, watering, fertilising, minor re-shaping, erosion control, inspections/audits - does not include major repair works.
Existing rehabilitation repair - minor	Y		ha	\$1,200		\$0	Areas requiring minor repair - rills, minor growth media replacement.
Existing rehabilitation repair - moderate	Y		ha	\$1,700		\$0	Areas requiring moderate repair - rills, significant growth media replacement.
Existing rehabilitation repair - major	Y		ha	\$2,500		\$0	Areas requiring major repair - rills, gullies, growth media replacement, some level of additional surface water management.
Existing rehabilitation repair - total failure of landform	Y		ha	\$40,000		\$0	Areas that require extensive rehabilitation repair - re-design and re-construction of landform.
Maintenance of Rehabilitated Areas Subtotal						\$0	
Additional Items Subtotal						\$0	
Total Cost for Infrastructure Domain						\$0	

Underground Operations

Domain 2c: Tailings & Rejects

Total Cost for Tailings & Rejects Domain

\$0

Additional Assumptions: Record any relevant assumptions to this domain below:

		Key Rehabilitation Area Data for Domain	Enter data below manually
		Total Landform Establishment:	
		Total Growth Media Development:	
		Total Ecosystem Establishment:	

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Contaminated Materials	Undertake a preliminary site investigation (Phase 1). This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple studies may be required.	Y		Cluster	\$15,000		\$0		The preliminary investigation would include at minimum a desktop assessment of the area and site history, incidents, etc. as per the National Environmental Protection (Site Contamination) Measure (NEPM) Phase 1 assessment (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. A cluster may include: - Mine infrastructure (i.e., fuel / chemical store, workshop, vehicle wash-down, sewage treatment etc.) - Processing plants (i.e., ore and product storage, mine waste storage and disposal, rail load-out etc.) - Remote pit-top facilities (i.e., vehicle re-fuel, sewage treatment, secondary workshop, chemical storage etc.)
	Undertake an intrusive site investigation on sites with small footprints to investigate e.g. ≤15 ha. This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple intrusive investigations should be included.	Y		Cluster	\$44,000		\$0		The intrusive investigation would include at minimum a site walkover and field sampling as per the National Environmental Protection (Site Contamination) Measure (NEPM) Phase 2 intrusive investigation (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. Note: An intrusive investigation is not required for all contaminated areas and should be applied considering the rehabilitation program, site history, location, etc. A cluster area where it is highly anticipated that contamination has occurred (i.e., underground tanks / pipes that are known to have leaked, chemical stores with earthen bunds, around ineffective oil/water separators etc.) and further field work is required involving intrusive investigation. Assumes site is easily accessible and a small area e.g. ~10-15 ha requires investigation and testing (test pits, boreholes, etc.) based on Sampling and Analysis Quality Plan. Includes SAQP, fieldwork, sampling and analysis.
	Undertake an intrusive site investigation on sites with large footprints to investigate e.g. >15 ha. This accounts for current and historical locations where areas of disturbance are clustered. If there are multiple cluster areas on site, multiple intrusive investigations should be included.	Y		Cluster	\$106,000		\$0		The intrusive investigation would include at minimum a site walkover and field sampling as per the National Environmental Protection (Site Contamination) Measure (NEPM) Phase 2 intrusive investigation (EP Act Section 389 (2) (iv)) or similar approved and recognised assessment method. Note: An intrusive investigation is not required for all contaminated areas and should be applied considering the rehabilitation program, site history, location, etc. A cluster area where it is highly anticipated that contamination has occurred (i.e., underground tanks / pipes that are known to have leaked, chemical stores with earthen bunds, around ineffective oil/water separators etc.) and further field work is required involving intrusive investigation. Assume site has a history of contamination and/or a large area >15 ha requires investigation and testing (test pits, boreholes, etc.) based on Sampling and Analysis Quality Plan. Includes SAQP, fieldwork, sampling and analysis.
	Develop a Remediation Action Plan on sites with small footprints based on outcomes of intrusive investigation including strategies to address contamination exceedances	Y			allow	\$35,000		\$0	

	Develop a Remediation Action Plan on sites with large footprints based on outcomes of intrusive investigation including strategies to address contamination exceedances	Y		allow	Use alternate rate cell		\$0		Assumes complex site; detailed design drawings required for cover.
	Removal and disposal of contaminated water from tanks, bunded areas and sumps	Y		L	\$0.35		\$0		Cost for recent sump clean-up from resource activity - requires specialists to treat.
	Remove material (carbonaceous / metalliferous spillage or otherwise) from footprint of the process facility (leach pads) / stockpile area (ROM product) / roads and dump in a void on-site (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here	This item includes scraping and removal of the volume of carbonaceous material using dozer, grader etc. to make safe an area and enable the establishment of rehabilitation.
	Load, cart and dispose of Hazardous classified contaminated material off site to a licensed landfill. Assumes cartage to a licensed landfill.	Y		m3	\$800.00		\$0		Includes load, haul and dump fees to a licensed facility.
	Load, cart and disposal of Low Level contaminated material off site to a licensed landfill. Add \$50/m3 for cartage to regional landfill	Y		m3	\$220.00		\$0		Includes load, haul and dump fees to a licensed facility.
	Onsite remediation of hydrocarbon contaminated soils manual land farming (Select Volume from List)	Y		m3	Select from List			Select Volume Here	Spreading of contaminated soils on a prepared surface and stimulation of aerobic microbial activity within the soils through aeration and/or the addition of minerals, nutrients and moisture to promote the aerobic degradation of organic chemicals - time frame of up to 24 months.
	Mobilisation of cement stabilisation plant and equipment for hydrocarbon (i.e., PAH, long chain hydrocarbons, etc.) contaminated soil treatment	Y		Item	\$150,000		\$0		Required if treatment of hydrocarbon contamination is required to be fast tracked.
	On-site remediation of hydrocarbon contaminated soils - using a mobile treatment unit	Y		m3	\$165.00		\$0		Additional cost as the treatment process is fast tracked.
	Remove and dispose of asbestos (<750 m2)	Y		m2	\$50.00		\$0		Where an assessment/estimation has been made to confirm the volume of asbestos to be removed.
	Remove and dispose of asbestos (>750 m2)	Y		m2	\$40.00		\$0		Where an assessment/estimation has been made to confirm the volume of asbestos to be removed.
	Waste disposal to Council landfill - fees (asbestos)	Y		tonne	\$290		\$0		Landfill fees to regional landfill.
Contaminated Materials Subtotal							\$0		
Roads and Tracks	Unsealed roads / vehicle park-up areas – minor works including deep rip and trim	Y		ha	\$1,040.00		\$0		Assumes ~6 m road width - 16H Grader.
	Unsealed roads / access tracks / vehicle park-up areas with windrows and/or small earthen bunds – minor earthworks and deep rip and trim	Y		ha	\$1,500		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - no seed
	Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip and seed (pasture grass)	Y		ha	\$3,700		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$4,485		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (pasture grass)	Y		ha	\$4,870		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$7,025		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Remove stabilised material (blue metal, aggregate etc.) from roadways and disposal on-site/locally (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here	This item includes the scraping and removal of the volume of stabilised material from the road, laydown or other surface using an excavator, dozer and grader to enable the establishment of rehabilitation.
Roads and Tracks Subtotal							\$0		
Earthworks / Structural Works (Landform Establishment)	Major bulk pushing to achieve grades nominated in the approval/permit – Select Push Length	Y		m3	Select from List			Select Push Length Here	Major bulk pushing to achieve grades nominated in the approval/permit
	Minor reshaping and pushing	Y		ha	\$3,900		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation).
	Fill dams, voids etc. - Source local material, cart and spread to cap or backfill, cap thickness determined by approval / permit (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here	This item includes the volume of material requiring backfill using an excavator and scraper to fill the void and enable the establishment of rehabilitation.
	Trim, rock rake & deep rip (includes levelling / landscaping and rip in 1 direction)	Y		ha	\$1,130.00		\$0		Undertaken using D10 dozer and 16M grader.
	Structural works, banks, waterways - contour banks, drainage channels and other soil conservation measures	Y		ha	\$1,600		\$0		Combination of dozer and excavator work plus grader for ~4 hours each per ha.
	Construction of spine drains / drop structures and/or stabilising water course entry points - required for large catchments	Y		m2	\$27.00		\$0		Installation of on-site rock material (rip-rap) where managing water run-off from disturbed land and/or upon entry to water courses - prevents erosion of gully head (assumes competent material is locally available). If required to be sourced off site, assume an additional \$20/m2.

Earthworks / Structural Works (Landform Establishment) Subtotal						\$0		
Mine Waste								
Ideal Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with little chemical reactivity (no to low risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and good physical properties (not significantly hydrophilic, shear strength does not limit equipment choice, no artificial strengthening required)	Y		ha	\$82,000		\$0		This includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume material with the appropriate chemical and physical properties. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness of approximately 0.5 m to 1 mand 0.15 m - 0.2 m growth media (assume at least 1 m thick cover required for carbonaceous material covers). Water quality from runoff, seepage etc. meets site-specific environment water quality values. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in additional to any long haulage volume in 8.05.
Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
Efficient Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with moderate chemical reactivity (low to medium risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and moderate physical properties (not significantly hydrophilic, shear strength limits equipment choice somewhat, no artificial strengthening required)	Y		ha	\$146,500		\$0		This item includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume of material to cap / cover facilities where the tailings or rejects base is at a strength that enables economically efficient construction methods with small plant. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness ranging from >1 m to 2 m thickness constructed in 1 m layers + growth media up to 0.2 m depth. This may require additional materials (such as capillary breaks, geofabric, etc.) - use alternate rate cells below, specific material types (e.g. acid neutralising / consuming materials, competent rock etc.), and associated activities (i.e., load / haul / place / crush / screen / borrow etc.). Costs for haulage of specialised/additional materials must be added separately if required. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage.
Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).

	Adverse Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with moderate chemical reactivity (medium to high risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or moderate to high propensity for spontaneous combustion) and moderate physical properties (not significantly hydrophilic, shear strength limits equipment choice somewhat, no artificial strengthening required)	Y		ha	\$313,000		\$0		This item includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume of material to cap / cover facilities of high geochemical risk, and / or low shear strength that prohibits economically efficient construction methods. This rate assumes suitable capping material/s are available on site within 10 km, and an average cap thickness of approximately >2 m + growth media up to 0.2 m depth. This may require additional materials (i.e., capillary breaks, geofabric, etc.), specific material types (e.g. acid neutralising / consuming materials, competent rock etc.), and associated activities (i.e. load / haul / place / crush / screen / borrow etc.). Costs for haulage of specialised materials must be added separately if required. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in addition to any long haulage volume in 8.05.
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Difficult Tailings Capping- reshaping, capping / sealing of weak or soft surfaced tailings facility with poor physical properties (significantly hydrophilic, low shear strength limits equipment choice greatly, artificial strengthening required) OR visible adverse impacts on legacy sites from chemical reactivity over lengthy exposure prior to rehabilitation	Y		ha	\$843,000		\$0		This option is typically driven by time constraints and/or when tailings properties significantly restrict adequate desiccation, resulting in a tailings shear strength that is very weak excluding access by conventional small plant. Small equipment used for rehabilitation. This excludes any additional material required to form the final landform profile in addition to this cap. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in addition to any long haulage volume in 8.05.
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.	Y		allow	Use alternate rate cell		\$0		Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).
	Long haulage soil / weathered rock / sediment e.g. capping/cover, removal of contamination, etc. (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here	Capping/cover material available within 50 km round trip e.g. waste / overburden dumps, borrow areas, etc.
Mine Waste Subtotal							\$0		
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment)	Source, cart and spread growth media (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here	If topsoil is not available on-site, then Virgin Excavated Natural Material (VENM) may need to be externally sourced.
	Direct seeding / fertiliser (pasture grass species)	Y		ha	\$1,875		\$0		Includes treating, weighing, mixing with fertiliser + spreading by tractor or helicopter (aerial seeding).
	Direct seeding / fertiliser (tree or native grass species)	Y		ha	\$4,135		\$0		Includes treating, weighing, mixing with fertiliser + spreading by tractor or helicopter (aerial seeding).
	Hydro-seeding with straw mulching and bitumen tack with native seed	Y		m2	\$1.90		\$0		Process to be used on flat well prepared surfaces under irrigation e.g. sewage treatment irrigation areas. Ranges from \$0.15 - \$0.50 depending on size and input variables. Native seed +\$1.00
	Hydro-seeding with straw mulching and bitumen tack with pasture seed	Y		m2	\$0.43		\$0		Process to be used on flat well prepared surfaces under irrigation e.g. sewage treatment irrigation areas. Ranges from \$0.15 - \$0.50 depending on size and input variables. Pasture seed +\$0.10

Hydromulch - base grade or standard for flat areas that can be irrigated by water cart	Y		m2	\$0.80		\$0	Assumes use on flat areas with a gradient of less than 4:1, and where irrigation from water cart may be possible. Industry standard application rate of 2500kg/ha. Product will last short term (less than 3 months) and vegetation is required to grow ASAP for stability. This cost includes cover crop only, additional seeding required.
Hydromulch - bonded fibre matrix grade for steep areas to stabilise up to 12 months	Y		m2	\$1.80		\$0	Assumes use on steep areas where stabilisation is required for up to 12 months. Application rate of ~3500kg/ha. This cost includes cover crop only, additional seeding required.
Hydromulch - high performance flexible growth medium grade	Y		m2	\$2.50		\$0	Assumes use on extreme slopes where stabilisation is required for up to 18 months. Application rate of ~4,000kg/ha minimum. This cost includes cover crop only, additional seeding required.
Single application of fertiliser (pasture)	Y		ha	\$420.00		\$0	Assumes 250 kg / ha. These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
Single application of fertiliser (trees)	Y		ha	\$140.00		\$0	These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
Spoil amelioration (adding lime / gypsum etc.)	Y		ha	\$1,000.00		\$0	Assumes 2.5 t / ha as an average application rate.
growth media amelioration with biosolids	Y		ha	\$1,015		\$0	Recent experience with agronomy projects.
Construct no-climb stock fence around rehabilitated areas	Y		m	\$22.00		\$0	Standard rate for no-climb stock fencing.
Construct standard stock fence around rehabilitated areas	Y		m	\$13.00		\$0	Standard rate for standard stock fencing.
Purchase and erect warning signs	Y		allow	\$250.00		\$0	Compliance with AS 1319-1994 - Safety signs for the occupational environment - installed every 25 m.
Supply from external sources virgin excavated natural material (VENM) for growth media.	Y		m3	\$80.80		\$0	D7 to spread material at \$205/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$70/m3 for imported fill material.
Supply from external sources a combination of virgin excavated natural material (VENM) and spoil from large excavation for filling voids and/or capping etc.	Y		m3	\$72.50		\$0	D10 push into void at \$270/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$60/m3 for imported fill material.
Clearing and grubbing of trees and vegetation	Y		ha	\$4,730.00		\$0	Clearing and grubbing of light vegetation growth e.g. regrowth
Topsoil stripping	Y		m3	\$4.86		\$0	Stripping or topsoil at an approximate depth of 0.2 m into stockpiles; load and haul to final rehabilitation location required or respreading where necessary.
Growth media supplementation with manure	Y		ha	\$747.50		\$0	Addition of manure to improve soil quality.
Utilise biotic soil media - organic topsoil alternative	Y		m2	\$2.50		\$0	Material that can be applied as an alternative to spreading topsoil prior to hydromulching.
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment) Subtotal						\$0	
Water Management							
Clean water dams to be retained after decommissioning – make safe and minor earthworks	Y		allow	\$2,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) @ ~\$200 per hour and pasture grass.
Large clean water dams (i.e. ≥ 2 ha) to be retained after mine closure – make safe and minor earthworks	Y		allow	\$10,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) + pasture grass.
Remove sediments from the floor of the dam to enable it to be converted into clean water structure (Select Haul Distance from list)	Y		m3	Select from List		\$0	Select Haul Distance Here This item includes the volume of contaminated sediment requiring removal using an excavator, truck and dozer to clean out the dam.
Water Management Subtotal						\$0	
Maintenance of Rehabilitated Areas							
Maintenance of areas that have been shaped and seeded and revegetation has been 'successful'	Y		ha	\$925		\$0	Rehabilitation maintenance might include re-seeding, watering, fertilising, minor re-shaping, erosion control, inspections/audits - does not include major repair works.
Existing rehabilitation repair - minor	Y		ha	\$1,200		\$0	Areas requiring minor repair - rills, minor growth media replacement.
Existing rehabilitation repair - moderate	Y		ha	\$1,700		\$0	Areas requiring moderate repair - rills, significant growth media replacement.
Existing rehabilitation repair - major	Y		ha	\$2,500		\$0	Areas requiring major repair - rills, gullies, growth media replacement, some level of additional surface water management.
Existing rehabilitation repair - total failure of landform	Y		ha	\$40,000		\$0	Areas that require extensive rehabilitation repair - re-design and re-construction of landform.
Maintenance of Rehabilitated Areas Subtotal						\$0	
Additional Items Subtotal						\$0	
Total Cost for Tailings & Rejects Domain						\$0	

Underground Operations

Domain 3c: Overburden & Waste

Total Cost for Overburden & Waste Domain

\$0

Additional Assumptions: Record any relevant assumptions to this domain below:

		Key Rehabilitation Area Data for Domain	Enter data below manually
		Total Landform Establishment:	
		Total Growth Media Development:	
		Total Ecosystem Establishment:	

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Contaminated Materials	Treatment of known Acid Sulfate Soils	Y		ha	\$2,580		\$0		Assumes ASS is treatable via neutralisation and does not require capping and isolation. Assumes 1% by weight lime addition and treatment to 100 mm depth only.
	Removal and disposal of plastic liner (i.e. dam, leach pad, sump etc.)	Y		m2	\$1		\$0		Provisional sum for cutting using ripping tyres and on-site disposal of the liner.
	Long haulage brine/salt for disposal (Select Haul Distance from list)	Y		tonne	Select from List			Select Haul Distance Here	Costs for haulage to location for authorised disposal.
	Brine disposal to landfill - fees only	Y		tonne	\$288		\$0		Rate for trackable liquid levy of \$78.20 per tonne and authorised disposal to landfill.
	Long haulage water (clean or contaminated) (Select Haul Distance from list)	Y		tonne	Select from List			Select Haul Distance Here	Assumes transport in a 20,000 L tanker. Add disposal costs to additional items where warranted.
Contaminated Materials Subtotal							\$0		
Roads and Tracks	Unsealed roads / vehicle park-up areas – minor works including deep rip and trim	Y		ha	\$1,040.00		\$0		Assumes ~6 m road width - 16H Grader.
	Unsealed roads / access tracks / vehicle park-up areas with windrows and/or small earthen bunds – minor earthworks and deep rip and trim	Y		ha	\$1,500		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - no seed
	Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip and seed (pasture grass)	Y		ha	\$3,700		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / vehicle park-up areas – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$4,485		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (pasture grass)	Y		ha	\$4,870		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - pasture grass seed
	Unsealed roads / haul roads / vehicle park-up areas with windrows and/or small earthen bunds – Minor earthworks, final trim and deep rip, ameliorate and seed (native tree/shrub/grass)	Y		ha	\$7,025		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation) - native tree/shrub seed
	Remove stabilised material (blue metal, aggregate etc.) from roadways and disposal on-site/locally (Select Haul Distance from list)	Y		m3	Select from List			Select Haul Distance Here	This item includes the scraping and removal of the volume of stabilised material from the road, laydown or other surface using an excavator, dozer and grader to enable the establishment of rehabilitation.
Roads and Tracks Subtotal							\$0		
Earthworks / Structural Works (Landform Establishment)	Major bulk pushing to achieve grades nominated in the approval/permit – Select Push Length	Y		m3	Select from List			Select Push Length Here	Major bulk pushing to achieve grades nominated in the approval/permit
	Minor reshaping and pushing	Y		ha	\$3,900		\$0		D10 Dozer @ \$400 per hour and 16 H grader @ \$230 per hour (50% utilisation).
	Fill dams, voids etc. - Source local material, cart and spread to cap or backfill, cap thickness determined by approval / permit (Select Haul Distance from List)	Y		m3	Select from List			Select Haul Distance Here	This item includes the volume of material requiring backfill using an excavator and scraper to fill the void and enable the establishment of rehabilitation.
	Shotcrete application on cuttings and steep slopes	Y		m2	\$185.00		\$0		This rate is used to rehabilitate steep slopes of weathered rock, roadway cuttings, etc that cannot be cut back and stabilised.
	Trim, rock rake & deep rip (includes levelling / landscaping and rip in 1 direction)	Y		ha	\$1,130.00		\$0		Undertaken using D10 dozer and 16M grader.
	Structural works, banks, waterways - contour banks, drainage channels and other soil conservation measures	Y		ha	\$1,600		\$0		Combination of dozer and excavator work plus grader for ~4 hours each per ha.
Construction of spine drains / drop structures and/or stabilising water course entry points - required for large catchments	Y		m2	\$27.00		\$0		Installation of on-site rock material (rip-rap) where managing water run-off from disturbed land and/or upon entry to water courses - prevents erosion of gully head (assumes competent material is locally available). If required to be sourced off site, assume an additional \$20/m2.	
Earthworks / Structural Works (Landform Establishment) Subtotal							\$0		

Mine Waste

<p>Ideal Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with little chemical reactivity (no to low risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and good physical properties (not significantly hydrophilic, shear strength does not limit equipment choice, no artificial strengthening required)</p>	<p>Y</p>	<p>ha</p>	<p>\$82,000</p>	<p></p>	<p>\$0</p>	<p>This includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume material with the appropriate chemical and physical properties. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness of approximately 0.5 m to 1 m and 0.15 m - 0.2 m growth media (assume at least 1 m thick cover required for carbonaceous material covers). Water quality from runoff, seepage etc. meets site-specific environment water quality values. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage and spreading in addition to any long haulage volume in 8.05.</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>
<p>Efficient Tailings Capping - reshaping, capping / sealing of trafficable tailings facility with moderate chemical reactivity (low to medium risk Potential Acid Forming (PAF) / Neutral Mine Drainage (NMD) / Saline Mine Drainage (SMD) and/or low to moderate propensity for spontaneous combustion) and moderate physical properties (not significantly hydrophilic, shear strength limits equipment choice somewhat, no artificial strengthening required)</p>	<p>Y</p>	<p>ha</p>	<p>\$146,500</p>	<p></p>	<p>\$0</p>	<p>This item includes sourcing, carting, spreading, moisture conditioning and compaction of a suitable volume of material to cap / cover facilities where the tailings or rejects base is at a strength that enables economically efficient construction methods with small plant. This rate assumes suitable capping material is available on site within 10 km, and an average cap thickness ranging from >1 m to 2 m thickness constructed in 1 m layers + growth media up to 0.2 m depth. This may require additional materials (such as capillary breaks, geofabric, etc.) - use alternate rate cells below, specific material types (e.g. acid neutralising / consuming materials, competent rock etc.), and associated activities (i.e., load / haul / place / crush / screen / borrow etc.). Costs for haulage of specialised/additional materials must be added separately if required. If site haulage longer than 10 km round trip add the volume of the relevant material requiring haulage for this distance in 8.05 (spreading costs for tailings cap material included in rate). If additional material to make up landform, provide buttress or other works aside from tailings cap, use rate from 9.02 for relevant haulage</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>
<p>Additional materials required for reshaping, capping / sealing of structure to facilitate water quality from runoff, seepage etc. meeting site-specific environment water quality values.</p>	<p>Y</p>	<p>allow</p>	<p>Use alternate rate cell</p>	<p></p>	<p>\$0</p>	<p>Include additional cost to import materials (i.e., shale / clay, competent drainage materials etc.) and / or additional requirements (i.e., geofabric / composite lining etc.).</p>

	Hydromulch - base grade or standard for flat areas that can be irrigated by water cart	Y		m2	\$0.80		\$0	Assumes use on flat areas with a gradient of less than 4:1, and where irrigation from water cart may be possible. Industry standard application rate of 2500kg/ha. Product will last short term (less than 3 months) and vegetation is required to grow ASAP for stability. This cost includes cover crop only, additional seeding required.
	Hydromulch - bonded fibre matrix grade for steep areas to stabilise up to 12 months	Y		m2	\$1.80		\$0	Assumes use on steep areas where stabilisation is required for up to 12 months. Application rate of ~3500kg/ha. This cost includes cover crop only, additional seeding required.
	Hydromulch - high performance flexible growth medium grade	Y		m2	\$2.50		\$0	Assumes use on extreme slopes where stabilisation is required for up to 18 months. Application rate of ~4,000kg/ha minimum. This cost includes cover crop only, additional seeding required.
	Single application of fertiliser (pasture)	Y		ha	\$420.00		\$0	Assumes 250 kg / ha. These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Single application of fertiliser (trees)	Y		ha	\$140.00		\$0	These rates have fluctuated over the last few years however in light of current conditions (lower fuel prices, reduced demand etc) this is a suitable standard rate.
	Spoil amelioration (adding lime / gypsum etc.)	Y		ha	\$1,000.00		\$0	Assumes 2.5 t / ha as an average application rate.
	growth media amelioration with biosolids	Y		ha	\$1.015		\$0	Recent experience with agronomy projects.
	Construct no-climb stock fence around rehabilitated areas	Y		m	\$22.00		\$0	Standard rate for no-climb stock fencing.
	Construct standard stock fence around rehabilitated areas	Y		m	\$13.00		\$0	Standard rate for standard stock fencing.
	Purchase and erect warning signs	Y		allow	\$250.00		\$0	Compliance with AS 1319-1994 - Safety signs for the occupational environment - installed every 25 m.
	Supply from external sources virgin excavated natural material (VENM) for growth media.	Y		m3	\$80.80		\$0	D7 to spread material at \$205/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$70/m3 for imported fill material.
	Supply from external sources a combination of virgin excavated natural material (VENM) and spoil from large excavation for filling voids and/or capping etc.	Y		m3	\$72.50		\$0	D10 push into void at \$270/hr, Excavator (\$220/hr) load Artic Trucks (90ckm) from imported stockpile - allow nominal rate of \$60/m3 for imported fill material.
	Clearing and grubbing of trees and vegetation	Y		ha	\$4,730.00		\$0	Clearing and grubbing of light vegetation growth e.g. regrowth
	Topsoil stripping	Y		m3	\$4.86		\$0	Stripping or topsoil at an approximate depth of 0.2 m into stockpiles; load and haul to final rehabilitation location required or respreading where necessary.
	Growth media supplementation with manure	Y		ha	\$747.50		\$0	Addition of manure to improve soil quality.
	Utilise biotic soil media - organic topsoil alternative	Y		m2	\$2.50		\$0	Material that can be applied as an alternative to spreading topsoil prior to hydromulching.
Land Preparation and Revegetation (Growth Media Development and Ecosystem Establishment) Subtotal							\$0	
Water Management	Clean water dams to be retained after decommissioning – make safe and minor earthworks	Y		allow	\$2,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) @ ~\$200 per hour and pasture grass.
	Large clean water dams (i.e. ≥ 2 ha) to be retained after mine closure – make safe and minor earthworks	Y		allow	\$10,500		\$0	Provisional sum for earthworks and revegetation required to rehabilitate dam batters etc suitable for re-use by an alternate land-user - D6 Dozer (or similar) + pasture grass.
	Remove sediments from the floor of the dam to enable it to be converted into clean water structure (Select Haul Distance from list)	Y		m3	Select from List		\$0	Select Haul Distance Here This item includes the volume of contaminated sediment requiring removal using an excavator, truck and dozer to clean out the dam.
Water Management Subtotal							\$0	
Maintenance of Rehabilitated Areas	Maintenance of areas that have been shaped and seeded and revegetation has been 'successful'	Y		ha	\$925.00		\$0	Rehabilitation maintenance might include re-seeding, watering, fertilising, minor re-shaping, erosion control, inspections/audits - does not include major repair works.
	Existing rehabilitation repair - minor	Y		ha	\$1,200		\$0	Areas requiring minor repair - rills, minor growth media replacement.
	Existing rehabilitation repair - moderate	Y		ha	\$1,700		\$0	Areas requiring moderate repair - rills, significant growth media replacement.
	Existing rehabilitation repair - major	Y		ha	\$2,500		\$0	Areas requiring major repair - rills, gullies, growth media replacement, some level of additional surface water management.
	Existing rehabilitation repair - total failure of landform	Y		ha	\$40,000		\$0	Areas that require extensive rehabilitation repair - re-design and re-construction of landform.
Maintenance of Rehabilitated Areas Subtotal							\$0	
Additional Items Subtotal							\$0	
Total Cost for Overburden & Waste Domain							\$0	

Underground Operations

Domain 4c: Subsidence and Management

Total Cost for Subsidence and Management Activities

\$0

Additional Assumptions: Record any relevant assumptions to this domain below:

		Key Rehabilitation Area Data for Domain	
		Total Landform Establishment:	Enter data below manually
		Total Growth Media Development:	
		Total Ecosystem Establishment:	

Management Precinct	Activity / Description	Applicable (Y or N)	Quantity	Unit	Default Unit Rate	Alternative Unit Rate	Total Cost	Basis for Costs Estimation and Additional Relevant Information	Description / Notes:
Subsidence Repairs	Minor stabilisation works and maintenance of mine subsidence areas - ripping etc.	Y		ha	\$1,470		\$0		Undertaken using Dozer. Costs subject to the extent of subsidence impacts
	Crack filling to repair subsidence impacts	Y		m	\$1,450		\$0		Undertake more substantial works to backfill cracks and/or sink holes (e.g., filling with mulch prior to grouting, grouting, etc.) Costs subject to the extent of subsidence impacts. Include >5 km haul of fill.
	Water course restoration to repair subsidence impacts	Y		allow	Use alternate rate cell		\$0		Undertake more substantial works to remediate water courses (e.g., channel bed repairs, rock bar repairs, swamp stabilisation etc.)
	Create cut-through to re-establish natural water courses/drainage channels following subsidence	Y		allow	\$3,000		\$0		Includes all earthworks and revegetation required to re-establish the natural drainage profile of the subsided area.
Subsidence Repairs Subtotal							\$0		
Vents, Shafts and Boreholes	Maintenance and monitoring of sealed adits/portals and shafts (for a total of 5 years)	Y		allow	\$25,000		\$0		Assume 1 x day visual inspection (10hrs inc 'travel) for suitably qualified / competent person + reporting, for an annual inspection @ \$5,000 per year. Exclusions are intrusive investigation and testing (e.g. concrete strength etc).
Vents, Shafts and Boreholes Subtotal							\$0		
Water Management	On-site treatment of contaminated water due to high salt (includes removal of metals etc, brine disposal and cost of mobile water treatment unit)	Y		ML	\$3,600		\$0		Rate can fluctuate depending on treatment type however this is a suitable standard rate for current programs at mining operations.
	On-site treatment of contaminated water due to low pH (includes removal of metals etc, neutralisation treatments and cost of mobile water treatment unit)	Y		ML	\$1,500		\$0		Rate can fluctuate depending on treatment type however this is a suitable standard rate for current programs at mining operations.
Water Management Subtotal							\$0		
Creek Diversions	Repairs and/or stabilisation of new or compromised water course diversion	Y		m	\$2,500		\$0		Assumes material is suitable for revegetating and has a reasonable chance of stabilising.
	Long term maintenance of water course diversion - Channel constructed through backfilled material	Y		m	\$1,500		\$0		Assumes maintenance has been kept up and significant works are not required.
	Long term maintenance of water course diversion - Channel constructed through competent material	Y		m	\$750.00		\$0		Assumes maintenance has been kept up and significant works are not required.
	Installation of rock armouring	Y		m2	\$6.00		\$0		Assumes competent material is locally available - multiply costs by 2 for sourcing and transporting from offsite location.
Creek Diversions Subtotal							\$0		
Land Management	Pest management on buffer lands, non-disturbed, and rehabilitated areas	Y		ha	\$150.00		\$0		Feral animal baiting programs if required and waste materials required to be removed.
	Land management of undisturbed areas (rehabilitation, weeds, ferals, erosion and sediment control works)	Y		ha	\$400.00		\$0		Undisturbed areas within the lease boundary that require land management activities.
Land Management Subtotal							\$0		
Heritage Items	The restoration and care and maintenance of items that have heritage significance	Y		allow	Use alternate rate cell		\$0		Item for the redistribution of Aboriginal artefacts, preservation of European heritage items or a combination of activities.
Heritage Items Subtotal							\$0		
Sundry Items	Development of an 'Unplanned' Project Closure Plan - State Significant Development with closure planning well progressed i.e. preferred cover design, closure environment modelled e.g. groundwater /subsidence / pit lakes, preliminary seal designs, etc. and only finalisation of detailed engineering designs required	Y		allow	\$100,000		\$0		Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities. Assumes outcomes of studies readily available including modelling, landform design, geochemistry, demolition, etc. Costs to finalise options by domain and finalise designs for construction. Assume a simple site e.g. single open cut, no legacy operations historic in the area, little social dependence, etc. Depending on site size, complexity, final land use requirements and knowledge base investigations can range from ~\$75k to >\$1 M. Sites with more than 1 pit to add \$50,000 to rate.

Development of an 'Unplanned' Project Closure Plan - Non State Significant Development with at least 2 of the following aspects requiring closure planning, but no significant issues realised at this time: previous subsidence, medium or higher geochemistry risk and/or spontaneous combustion propensity, known/ likely contamination, tailings / rejects, final void	Y		allow	\$90,000		\$0	Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities. Estimated cost for developing closure plan including studies - basic to satisfy risks and decisions includes risk assessment, options analysis, Closure Plan. Sites with more than 1 pit to add \$50,000 to rate.
Development of an 'Unplanned' Project Closure Plan - Non State Significant Development with no EPL and/or only one of the following relevant aspects: previous subsidence, low to medium geochemistry risk and/or spontaneous combustion propensity, known limited contamination, small approved final void	Y		allow	\$15,000		\$0	Assumes sediment control is the key concern for rehabilitation e.g. small mines, exploration operations. Includes risk assessment, sampling and analyses on <5 samples, one study and Closure Plan.
Development of an 'Unplanned' Project Closure Plan - State Significant Development with only preliminary to conceptual closure planning in place	Y		allow	\$300,000		\$0	Includes costs for key investigations and studies including designs e.g. geochemistry, Contamination Remediation Action Plan, subsidence risk, cover/capping and final landform, site wide surface water, etc. Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities. Assume at least 15 types of studies required ranging from geotechnical to ecology and social, development of a closure plan including address of obligations. Assume a simple site e.g. single open cut, no legacy operations historic in the area, little social dependence, etc. Depending on site size, complexity, final land use requirements and knowledge base investigations can range to >\$3 M. Sites with more than 1 pit to add \$50,000 to rate.
Development of an 'Unplanned' Project Closure Plan - Non State Significant Development with at least 2 of the following aspects resulting in significant issues requiring remediation: previous subsidence, medium or higher geochemistry risk and/or spontaneous combustion propensity, known/ likely contamination, tailings / rejects, final void	Y		allow	\$125,000		\$0	Includes costs for key investigations and studies including economic treatments and designs e.g. geochemistry, Contamination Remediation Action Plan, subsidence risk, cover/capping and final landform, site wide surface water, etc. Provisional sum to be used to refine the conceptual closure plan into a detailed closure plan with execution strategies for rehabilitation activities.
Develop a Review of Environmental Factors (REF) to facilitate rehabilitation including contamination works.	Y		allow	\$27,950		\$0	Based on experience for a REF after completion of a detailed closure study (e.g. contamination investigation) costs could range from \$10,000 to \$100,000 ex GST. Note this does not apply to a Statement of Environmental Effects or Environmental Impact Statement.
Site security during closure	Y		yr.	\$75,000		\$0	Provisional sum for site security measures required during closure. This includes nightly patrols and first response in the event of an out of hours incident.
Choose type of HAZMAT Clean-up required - cleaning and decontaminating plant and equipment, chemical storage locations, oil and grease traps, tanks, vessels, and pipe work etc	Y		allow	\$0		\$0	Select type of HAZMAT Clean-up Required Type of HAZMAT Clean-up required - cleaning and decontaminating plant and equipment, chemical storage locations, oil and grease traps, tanks, vessels, and pipe work etc
Removal and disposal of radiation devices	Y		each	\$31,630		\$0	Provisional sum for removal and disposal of monitoring devices on conveyors using a radiation source (i.e., Americium - 241, Plutonium - 238, Caesium - 137 etc). Source Isotope type, quantity, strength, weight, source holder type, source holder weight, pick-up location (among others) will directly affect pricing.
Additional fees for accessing State, Crown or other public lands for rehabilitation/remediation activities	Y		allow	Use alternate rate cell		\$0	Provisional sum.
Sundry Items Subtotal						\$0	
Mobilisation and Demobilisation							
Mobilisation & Demobilisation for small mine or quarry - small fleet	Y		Item	\$12,000		\$0	May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.
Mobilisation & Demobilisation for small mine or quarry - medium to large fleet	Y		Item	\$35,000		\$0	May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.
Mobilisation & Demobilisation (Distance to site <150 km)	Y		item	\$100,000		\$0	May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.

	Mobilisation & Demobilisation (Distance to site >150 km but <500 km)	Y		item	\$150,000		\$0		May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.	
	Mobilisation & Demobilisation (Distance to site >500 km but <1000 km)	Y		item	\$300,000		\$0		May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.	
	Mobilisation & Demobilisation (Distance to site >1000 km)	Y		item	\$500,000		\$0		May include specialist demolition equipment and/or suitable plant to execute bulk earthworks as required.	
Mobilisation and Demobilisation Subtotal							\$0			
Additional Items	Other 1 <insert>	N			This is				This item includes <<to be added by the operator>>	
	Other 2 <insert>	N			deliberately				This item includes <<to be added by the operator>>	
	Other 3 <insert>	N			left blank				This item includes <<to be added by the operator>>	
Additional Items Subtotal							\$0			
Total Cost for Subsidence and Management Activities							\$0			

