## **FINAL REPORT**

CERTIFICATE No.: 24657



Boral Cement Limited N 62 008 528 523 Taylor Avenue New Berrima NSW 2577 Locked Bag 4 New Berrima NSW 2577 T +61 2 4860 2222

TEST CERTIFICATE OF:	Berrima Daily Despatch Shrinkage Limited Cement		
PRODUCED AT:	Boral Cement Limited Berrima		
TESTED AT:	Berrima Works Laboratory		
SAMPLE IDENTIFICATION:	BDDSL2300878		
DATE DESPATCHED:	14/03/2023		

PROPERTY	REQUIREM	ENTS OF AS 3972	RESULT				
Compressive Strength (AS 2350.11)							
3 Day			33.5 MPa				
7 Day	Minimum	35 MPa	46.1 MPa				
28 Day	Minimum	45 MPa	58.6 MPa				
Setting Time (AS 2350.4)							
Initial	Minimum	45 mins	165 mins				
Final	Maximum	600 mins	210 mins				
Soundness (AS 2350.5)	Maximum	5 mm	1 mm				
SO <sub>3</sub> (AS 2350.2)	Maximum	3.5 %	2.7 %				
CI (AS 2350.2)	Maximum	0.10 %	0.02 %				
Shrinkage (AS 2350.13)							
28 Day Mean	Maximum	750 μstrain	590 μstrain				

## **OTHER REPORTABLE PROPERTIES**

K <sub>2</sub> O (AS 2350.2) 0.45 % Normal Consistency (AS 2350.3) 27.5 %   Na <sub>2</sub> O (AS 2350.2) 0.09 % Fineness Index (AS 2350.8) 410 m <sup>2</sup> /kg	CHEMICAL			PHYSICAL		
Na <sub>2</sub> O (AS 2350.2) 0.09 % Fineness Index (AS 2350.8) 410 m <sup>2</sup> /kg	K <sub>2</sub> O	(AS 2350.2)	0.45 %	Normal Consistency	(AS 2350.3)	27.5 %
	Na <sub>2</sub> O	(AS 2350.2)	0.09 %	Fineness Index	(AS 2350.8)	410 m <sup>2</sup> /kg
LOI (AS 2350.2) 4.0 %	LOI	(AS 2350.2)	4.0 %			

## REMARKS

Preparation of mortar and moulding of specimens in accordance with AS 2350.12. Sampling not carried out by laboratory. Samples tested as received. This cement is a Type SL (GP) cement with up to 7.5% limestone mineral addition.

Marc Smith Technical Services Manager Date of Issue: 20/04/2023

Accredited for compliance with ISO/IEC 17025 - Testing

Page 1 of 1