

# FINAL REPORT

CERTIFICATE No.: 28090



Boral Cement Limited

ABN 62 008 528 523

Taylor Avenue New Berrima NSW 2577

Locked Bag 4 New Berrima NSW 2577

T +61 2 4860 2222

**TEST CERTIFICATE OF:** Maldon Daily Despatch Shrinkage Limited Cement  
**PRODUCED AT:** Boral Cement Limited Maldon  
**TESTED AT:** Boral Cement QA Laboratory  
**SAMPLE IDENTIFICATION:** MDDSL2600992  
**DATE DESPATCHED:** 18/03/2026

| PROPERTY                              | REQUIREMENTS OF AS 3972 |                  | RESULT           |
|---------------------------------------|-------------------------|------------------|------------------|
| Compressive Strength (AS/NZS 2350.11) |                         |                  |                  |
| 3 Day                                 |                         |                  | 35.2 MPa         |
| 7 Day                                 | Minimum                 | 35 MPa           | 46.4 MPa         |
| 28 Day                                | Minimum                 | 45 MPa           | 60.4 MPa         |
| Setting Time (AS/NZS 2350.4)          |                         |                  |                  |
| Initial                               | Minimum                 | 45 mins          | 135 mins         |
| Final                                 | Maximum                 | 600 mins         | 165 mins         |
| Soundness (AS/NZS 2350.5)             | Maximum                 | 5 mm             | 1 mm             |
| SO <sub>3</sub> (AS 2350.2)*          | Maximum                 | 3.5 %            | 2.7 %            |
| CI (AS 2350.2)*                       | Maximum                 | 0.10 %           | 0.03 %           |
| Shrinkage (AS 2350.13)                |                         |                  |                  |
| 28 Day Mean                           | Maximum                 | 750 $\mu$ strain | 600 $\mu$ strain |

## OTHER REPORTABLE PROPERTIES

### CHEMICAL

K<sub>2</sub>O (AS 2350.2)\* 0.51 %  
Na<sub>2</sub>O (AS 2350.2)\* 0.08 %  
LOI (AS 2350.2)\* 4.6 %

### PHYSICAL

Normal Consistency (AS/NZS 2350.3) 27.7 %  
Fineness Index (AS/NZS 2350.8) 410 m<sup>2</sup>/kg

## REMARKS

Preparation of mortar and moulding of specimens in accordance with AS 2350.12.

Sampling not carried out by laboratory. Samples tested as received and results only relate to the item tested.

This cement is a Type SL (GP) cement with up to 7.5% limestone mineral addition.

\*The authorised signatory for AS2530.2 is Taleb Hallal

Jimmy Zhang  
Senior Laboratory Technician

Taleb Hallal  
Chemical Analyst



Accredited for compliance with ISO/IEC 17025 - Testing