FINAL REPORT

CERTIFICATE No.: 23727



Boral Cement Limited N 62 008 528 523 Taylor Avenue New Berrima NSW 2577 Locked Bag 4 New Berrima NSW 2577 T +61 2 4860 2222

| TEST CERTIFICATE OF: | Berrima Daily Despatch Shrinkage Limited Cement | | | |
|------------------------|---|--|--|--|
| PRODUCED AT: | Boral Cement Limited Berrima | | | |
| TESTED AT: | Berrima Works Laboratory | | | |
| SAMPLE IDENTIFICATION: | BDDSL2201823 | | | |
| DATE DESPATCHED: | 7/06/2022 | | | |

| PROPERTY | REQUIREM | ENTS OF AS 3972 | RESULT | | | | |
|-----------------------------------|----------|-----------------|-------------|--|--|--|--|
| Compressive Strength (AS 2350.11) | | | | | | | |
| 3 Day | | | 34.7 MPa | | | | |
| 7 Day | Minimum | 35 MPa | 48.2 MPa | | | | |
| 28 Day | Minimum | 45 MPa | 64.0 MPa | | | | |
| Setting Time (AS 2350.4) | | | | | | | |
| Initial | Minimum | 45 mins | 105 mins | | | | |
| Final | Maximum | 600 mins | 165 mins | | | | |
| Soundness (AS 2350.5) | Maximum | 5 mm | 0 mm | | | | |
| SO ₃ (AS 2350.2) | Maximum | 3.5 % | 2.6 % | | | | |
| CI (AS 2350.2) | Maximum | 0.10 % | 0.01 % | | | | |
| Shrinkage (AS 2350.13) | | | | | | | |
| 28 Day Mean | Maximum | 750 μstrain | 480 μstrain | | | | |

OTHER REPORTABLE PROPERTIES

| CHEMICAL | | PHYSICAL | | |
|-------------------------------|--------|--------------------|-------------|------------------------|
| K ₂ O (AS 2350.2) | 0.55 % | Normal Consistency | (AS 2350.3) | 27.7 % |
| Na ₂ O (AS 2350.2) | 0.07 % | Fineness Index | (AS 2350.8) | 390 m ² /kg |
| LOI (AS 2350.2) | 4.1 % | | | |

REMARKS

Preparation of mortar and moulding of specimens in accordance with AS 2350.12. Sampling not carried out by laboratory. Samples tested as received. This cement is a Type SL (GP) cement with up to 7.5% limestone mineral addition.

Marc Smith Technical Services Manager Date of Issue: 3/08/2022

Accredited for compliance with ISO/IEC 17025 - Testing