FINAL REPORT

CERTIFICATE No.: 25231



Boral Cement Limited N 62 008 528 523 Taylor Avenue New Berrima NSW 2577 Locked Bag 4 New Berrima NSW 2577 T +61 2 4860 2222

TEST CERTIFICATE OF: Berrima Daily Despatch Shrinkage Limited Cement

PRODUCED AT: Boral Cement Limited Berrima

TESTED AT: Berrima Works Laboratory

SAMPLE IDENTIFICATION: BDDSL2303493
DATE DESPATCHED: 1/09/2023

| PROPERTY | | REQUIREMENTS OF AS 3972 | | | RESULT |
|-------------------------------|-------------|-------------------------|--------------------|---------------|------------------------|
| Compressive Strength (A | AS 2350.11) | | | | |
| 3 Day | | | | | 36.2 MPa |
| 7 Day | | Minimum | 35 MPa | | 47.8 MPa |
| 28 Day | | Minimum | 45 MPa | | 62.2 MPa |
| Setting Time (AS 2350. | 4) | | | | |
| Initial | | Minimum | 45 mins | | 150 mins |
| Final | | Maximum | 600 mins | | 210 mins |
| Soundness (AS 2350.5) | | Maximum | 5 mm | | 0 mm |
| SO ₃ (AS 2350.2) | | Maximum | 3.5 % | | 2.5 % |
| CI (AS 2350.2) | | Maximum | 0.10 % | | 0.02 % |
| Shrinkage (AS 2350.13) |) | | | | |
| 28 Day Mean | | Maximum | 750 μstrain | | 560 μstrair |
| OTHER REPORTABLE | PROPERTIES | | | | |
| CHEMICAL | THOI ENTILO | | PHYSICAL | | |
| K ₂ O (AS 2350.2) | 0.49 % | | Normal Consistency | (AS 2350.3) | 27.3 % |
| Na ₂ O (AS 2350.2) | 0.10 % | | Fineness Index | (AS 2350.8) | 385 m ² /kg |
| LOI (AS 2350.2) | 4.1 % | | | (, .5 2500.0) | oco III /kg |

REMARKS

Preparation of mortar and moulding of specimens in accordance with AS 2350.12.

Sampling not carried out by laboratory. Samples tested as received.

This cement is a Type SL (GP) cement with up to 7.5% limestone mineral addition.

Jul

Marc Smith
Technical Services Manager
Date of Issue: 11/10/2023

NATA Accreditation Number: 530 / 531 Pag

Accredited for compliance with ISO/IEC 17025 - Testing

Page 1 of 1