FINAL REPORT

CERTIFICATE No.: 25415



Boral Cement Limited N 62 008 528 523 Taylor Avenue New Berrima NSW 2577 Locked Bag 4 New Berrima NSW 2577 T +61 2 4860 2222

TEST CERTIFICATE OF: Berrima Daily Despatch Shrinkage Limited Cement

PRODUCED AT: Boral Cement Limited Berrima

TESTED AT: Berrima Works Laboratory

SAMPLE IDENTIFICATION: BDDSL2304510 **DATE DESPATCHED:** 26/10/2023

| PROPERTY | | REQUIREMENTS OF AS 3972 | | | RESULT |
|-------------------------------|-------------|-------------------------|--------------------|---------------|------------------------|
| Compressive Strength (| AS 2350.11) | | | | |
| 3 Day | | | | | 34.0 MPa |
| 7 Day | | Minimum | 35 MPa | | 45.7 MPa |
| 28 Day | | Minimum | 45 MPa | | 58.7 MPa |
| Setting Time (AS 2350. | 4) | | | | |
| Initial | | Minimum | 45 mins | | 120 mins |
| Final | | Maximum | 600 mins | | 165 mins |
| Soundness (AS 2350.5) | | Maximum | 5 mm | | 1 mm |
| SO ₃ (AS 2350.2) | | Maximum | 3.5 % | | 2.6 % |
| CI (AS 2350.2) | | Maximum | 0.10 % | | 0.03 % |
| Shrinkage (AS 2350.13 |) | | | | |
| 28 Day Mean | | Maximum | 750 μstrain | | 580 μstraii |
| OTHER REPORTABLE | PROPERTIES | | | | |
| CHEMICAL | | | PHYSICAL | | |
| K ₂ O (AS 2350.2) | 0.52 % | | Normal Consistence | y (AS 2350.3) | 28.0 % |
| Na ₂ O (AS 2350.2) | 0.08 % | | Fineness Index | (AS 2350.8) | 405 m ² /kg |
| LOI (AS 2350.2) | 4.0 % | | | , , | ,,,, |

REMARKS

Preparation of mortar and moulding of specimens in accordance with AS 2350.12.

Sampling not carried out by laboratory. Samples tested as received.

This cement is a Type SL (GP) cement with up to 7.5% limestone mineral addition.

JW.

Marc Smith
Technical Services Manager
Date of Issue: 11/12/2023

Accredited for compliance with ISO/IEC 17025 - Testing

NATA Accreditation Number: 530 / 531

Page 1 of 1