FINAL REPORT

CERTIFICATE No.: 25013



Boral Cement Limited N 62 008 528 523 Taylor Avenue New Berrima NSW 2577 Locked Bag 4 New Berrima NSW 2577 T +61 2 4860 2222

| TEST CERTIFICATE OF: | Berrima Daily Despatch High Early Strength Cement |
|------------------------|---|
| PRODUCED AT: | Boral Cement Limited Berrima |
| TESTED AT: | Berrima Works Laboratory |
| SAMPLE IDENTIFICATION: | BWDHE2302373 |
| DATE DESPATCHED: | 3/07/2023 |

| PROPERTY | REQUIREMI | ENTS OF AS 3972 | RESULT |
|-----------------------------------|-----------|-----------------|----------|
| Compressive Strength (AS 2350.11) | | | |
| 3 Day | Minimum | 25 MPa | 41.5 MPa |
| 7 Day | Minimum | 40 MPa | 53.2 MPa |
| 28 Day | | | 65.5 MPa |
| Setting Time (AS 2350.4) | | | |
| Initial | Minimum | 45 mins | 135 mins |
| Final | Maximum | 360 mins | 180 mins |
| Soundness (AS 2350.5) | Maximum | 5 mm | 1 mm |
| SO ₃ (AS 2350.2) | Maximum | 3.5 % | 2.8 % |
| CI (AS 2350.2) | Maximum | 0.10 % | 0.04 % |

| OTHER REPORTABLE PROPERTIES | | | | | |
|-----------------------------|-------------|--------|--------------------|-------------|------------------------|
| CHEMICAL | | | PHYSICAL | | |
| K ₂ O | (AS 2350.2) | 0.52 % | Normal Consistency | (AS 2350.3) | 30.0 % |
| Na ₂ O | (AS 2350.2) | 0.11 % | Fineness Index | (AS 2350.8) | 445 m ² /kg |
| LOI | (AS 2350.2) | 1.0 % | | | |
| | | | | | |

REMARKS

Preparation of mortar and moulding of specimens in accordance with AS 2350.12. Sampling not carried out by laboratory. Samples tested as received. This cement is a Type HE (GP) cement.

Marc Smith Technical Services Manager Date of Issue: 16/08/2023

Accredited for compliance with ISO/IEC 17025 - Testing