## **FINAL REPORT**

CERTIFICATE No.: 25587



N 62 008 528 523 Taylor Avenue New Berrima NSW 2577 Locked Bag 4 New Berrima NSW 2577 T +61 2 4860 2222

| TEST CERTIFICATE OF:   | Berrima Daily Despatch High Early Strength Cement |
|------------------------|---|
| PRODUCED AT:           | Boral Cement Limited Berrima                      |
| TESTED AT:             | Berrima Works Laboratory                          |
| SAMPLE IDENTIFICATION: | BWDHE2400093                                      |
| DATE DESPATCHED:       | 10/01/2024  |

| PROPERTY                          | REQUIREM | ENTS OF AS 3972 | RESULT   |
|-----------------------------------|----------|-----------------|----------|
| Compressive Strength (AS 2350.11) |          |                 |          |
| 3 Day                             | Minimum  | 25 MPa          | 38.6 MPa |
| 7 Day                             | Minimum  | 40 MPa          | 50.4 MPa |
| 28 Day                            |          |                 | 62.1 MPa |
| Setting Time (AS 2350.4)          |          |                 |          |
| Initial                           | Minimum  | 45 mins         | 120 mins |
| Final                             | Maximum  | 360 mins        | 180 mins |
| Soundness (AS 2350.5)             | Maximum  | 5 mm            | 1 mm     |
| SO <sub>3</sub> (AS 2350.2)       | Maximum  | 3.5 %           | 2.7 %    |
| CI (AS 2350.2)                    | Maximum  | 0.10 %          | 0.02 %   |

| OTHER REPORTABLE PROPERTIES |             |        |                    |             |                        |
|-----------------------------|-------------|--------|--------------------|-------------|------------------------|
| CHEMICAL                    |             |        | PHYSICAL           |             |                        |
| K <sub>2</sub> O            | (AS 2350.2) | 0.57 % | Normal Consistency | (AS 2350.3) | 30.0 %                 |
| Na <sub>2</sub> O           | (AS 2350.2) | 0.07 % | Fineness Index     | (AS 2350.8) | 430 m <sup>2</sup> /kg |
| LOI                         | (AS 2350.2) | 1.1 %  |                    |             |                        |
|                             |             |        |                    |             |                        |

## REMARKS

Preparation of mortar and moulding of specimens in accordance with AS 2350.12. Sampling not carried out by laboratory. Samples tested as received. This cement is a Type HE (GP) cement.

Marc Smith Technical Services Manager Date of Issue: 4/03/2024

Accredited for compliance with ISO/IEC 17025 - Testing